



RAILWAY TRACKS SIGNIFY STEAM OR ELECTRIC WHERE ELECTRIC TRACKS CROSS OR JOIN STEAM TRACKS.





NOTE: EXPLANATION OF COLOR SHALL BE SHOWN ON PLAN.

HIGHWAY CROSSINGS.




NOTE: NAME TO BE PROVIDED AS NECESSARY. STREET NAME OR NUMBER, HIGHWAY NAME OR ROUTE NO., FARM OR PRIVATE CROSSING.


BRIDGES



CAR RETARDERS






TRAIN STOPS



FOREIGN TRACKS
(TO BE INDICATED BY NAME)

(NAME OF INTERLOCKING)







INTERLOCKING OR BLOCK STATION


TRACK




TUNNEL



SKATE MACHINES



SECTIONALIZING SWITCHES.



REVISIONS

APRIL 12, 1947. SYMBOLS FOR RAILWAY TRACKS, MAIL CARS, TRACK INSTRUMENT AND POLE LINE CHANGED AND DRAGGING EQUIPMENT DETECTORS ADDED TO AGREE WITH A.R.R. SIG. SEC. DWG'S. 16628, 16648 & 16678. APPROVED MAR. 1945. SYMBOLS FOR CENTRAL INSTRUMENT LOCATION AND SECTIONALIZING SW'S. ADDED. APPROVED: *[Signature]* S-601-A
SUPERSEDES PLAN S-601 DATED 12-27-24.

SHEET 5 OF 7

S-601-A

THE PENNSYLVANIA RAILROAD STANDARD SYMBOLS

OFFICE OF CHIEF SIGNAL ENGINEER
PHILA., PA., JULY 25, 1935.
Approved: *[Signature]*
Chief Signal Engineer

NOT TO SCALE
Approved: *[Signature]*
Chief Engineer



	SEMI-AUTOMATIC (POWER)			SLOTTED (MECH.)	SEMI-AUTOMATIC (POWER)				AUTOMATIC (POWER)		SPECIAL (POWER)	
	SEMA-PHORE	SEMA-PHORE	POSITION LIGHT		SEMA-PHORE	SEMA-PHORE	POSITION LIGHT	SEMA-PHORE	SEMA-PHORE	POSITION LIGHT	SEMA-PHORE	POSITION LIGHT
1. 0°												
2. 45°												
3. 90°												
4. 135°												
5. 180°												
6. 225°												
7. 270°												
8. 315°												
9. 360°												
10. 405°												
11. 450°												
12. 495°												
13. 540°												
14. 585°												
15. 630°												
16. 675°												
17. 720°												
18. 765°												
19. 810°												
20. 855°												
21. 900°												
22. 945°												
23. 990°												
24. 1035°												
25. 1080°												
26. 1125°												
27. 1170°												
28. 1215°												
29. 1260°												
30. 1305°												
31. 1350°												
32. 1395°												
33. 1440°												
34. 1485°												
35. 1530°												
36. 1575°												
37. 1620°												
38. 1665°												
39. 1710°												
40. 1755°												
41. 1800°												
42. 1845°												
43. 1890°												
44. 1935°												
45. 1980°												
46. 2025°												
47. 2070°												
48. 2115°												
49. 2160°												
50. 2205°												
51. 2250°												
52. 2295°												
53. 2340°												
54. 2385°												
55. 2430°												
56. 2475°												
57. 2520°												
58. 2565°												
59. 2610°												
60. 2655°												
61. 2700°												
62. 2745°												
63. 2790°												
64. 2835°												

CIRCUIT CONTROLLER CONTACTS

CONTACTS ACTUATED MECHANICALLY BY INTERLOCKING MACHINE LEVER



LEVERS WITH END POSITION AS NORMAL

N - NORMAL POSITION.
A - LEVER SLIGHTLY MOVED FROM N TOWARD B.
X - LEVER SLIGHTLY MOVED FROM B TOWARD N.
B - NORMAL INDICATION POSITION.
C - CENTRAL POSITION.
D - REVERSE INDICATION POSITION.
Y - LEVER SLIGHTLY MOVED FROM D TOWARD R.
E - LEVER SLIGHTLY MOVED FROM R TOWARD D.
R - REVERSE POSITION.



LEVERS WITH MIDDLE POSITION AS NORMAL

L - REVERSE POSITION TO LEFT.
A - LEVER SLIGHTLY MOVED FROM L TOWARD B.
X - LEVER SLIGHTLY MOVED FROM B TOWARD L.
B - INDICATION POSITION TO LEFT.
K - LEVER SLIGHTLY MOVED FROM N TOWARD B.
N - NORMAL POSITION.
T - LEVER SLIGHTLY MOVED FROM N TOWARD D.
D - INDICATION POSITION TO RIGHT.
Y - LEVER SLIGHTLY MOVED FROM D TOWARD R.
E - LEVER SLIGHTLY MOVED FROM R TOWARD D.
R - REVERSE POSITION TO RIGHT.



HORIZONTAL LINES INDICATE THAT PORTION OF THE CYCLE OF LEVER MOVEMENT DURING WHICH THE CIRCUIT IS CLOSED

INDEPENDENT TYPE CONTACT

DEPENDENT TYPE CONTACT

VERTICAL LINE BETWEEN LETTERS IN A SYMBOL INDICATES THAT THE CIRCUIT IS CLOSED AT AND OPEN BETWEEN POINTS INDICATED.


QUICK ACTING CIRCUIT CONTROLLERS SHALL BE DESIGNATED BY THE LETTER "Q".
CONTACTS ON SWITCH LEVERS DESIGNATED "N" & "R" SHALL BE DESIGNATED "NS" & "RS" ON SB MACHINES AND SHALL BE SO ADJUSTED AS NOT TO BREAK WHILE THE LEVER IS MECHANICALLY LOCKED NORMAL OR REVERSE RESPECTIVELY BUT MUST BREAK BEFORE THE DETECTOR LOCKING TOOTH IS REACHED.

CIRCUIT CONTROLLERS OPERATED BY SEMAPHORE SIGNALS.


	THREE POSITION 0°-45°-90°	TWO POSITION 0°-45°	TWO POSITION 0°-90°	TWO POSITION 45°-90°
CLOSED AT 0° ONLY				
CLOSED AT 45° ONLY				
CLOSED AT 90° ONLY				
CLOSED 0° TO 45°				
CLOSED 45° TO 90°				

WHERE SPECIAL CONDITIONS MUST BE COVERED, SYMBOL SHALL BE ARRANGED SIMILAR TO ILLUSTRATION, THE DEGREES THROUGH WHICH CIRCUIT IS CLOSED BEING INDICATED.


AIR BREAK SWITCH




LEVER LATCH




FLOOR PUSH






STRAP KEY OR PUSH BUTTON




TRACK INSTRUMENT ONE DIRECTION




TIME RELEASE AUTOMATIC



MULTICONTACT



TRAIN STOP



REVISIONS

APRIL 17, 1947. SYMBOLS FOR CIRCUIT CONTROLLER CONTACTS CHANGED, ELEC. LOCK ARMATURE AND CONTACTS OPERATED BY PADLOCK ON ELEC. SW. LOCK ADDED TO AGREE WITH A.R.R. 316 SEC. DMS. 1675 B & 1676 B APPROVED MAR. 1944.

APPROVED:

SUPERSEDES PLAN S-601 DATED 12-27-24.

SWITCH CIRCUIT CONTROLLER

SHEET 4 OF 7

S-601-A

THE PENNSYLVANIA RAILROAD STANDARD SYMBOLS

OFFICE OF CHIEF SIGNAL ENGINEER
PHILA. PA., JULY 23, 1935

Approved:


Chief Signal Engineer

NOT TO SCALE

Approved:


Chief Engineer

DIRECT CURRENT




NOTE:- ABOVE SYMBOLS MAY BE COMBINED AS REQUIRED.
RELAYS DESIGNED FOR NON-VITAL CIRCUITS SHALL BE SHOWN THUS [L] WITH CHARACTERISTICS INDICATED ABOVE.
ALL SPECIAL FEATURES NOT COVERED BY SYMBOLS TO BE NOTED ON CIRCUIT PLANS.




RELAYS






ALTERNATING CURRENT



RELAY CONTACTS



POSITION OF CONTACTS WITH RELATION TO POLARITIES



ELECTRIC LOCKS - POWER OR ELECTRO-MECHANICAL MACHINES. SEGMENTS & QUADRANTS TO BE USED SHALL BE SPECIFIED ON SPRING COMBINATION SHEET.

REVISIONS

APRIL 12, 1947. SYMBOLS FOR RELAYS MODIFIED TO AGREE WITH A.R. 316, 322, 323, 324, 325, 326, 327, 328, 329, 330, 331, 332, 333, 334, 335, 336, 337, 338, 339, 340, 341, 342, 343, 344, 345, 346, 347, 348, 349, 350, 351, 352, 353, 354, 355, 356, 357, 358, 359, 360, 361, 362, 363, 364, 365, 366, 367, 368, 369, 370, 371, 372, 373, 374, 375, 376, 377, 378, 379, 380, 381, 382, 383, 384, 385, 386, 387, 388, 389, 390, 391, 392, 393, 394, 395, 396, 397, 398, 399, 400, 401, 402, 403, 404, 405, 406, 407, 408, 409, 410, 411, 412, 413, 414, 415, 416, 417, 418, 419, 420, 421, 422, 423, 424, 425, 426, 427, 428, 429, 430, 431, 432, 433, 434, 435, 436, 437, 438, 439, 440, 441, 442, 443, 444, 445, 446, 447, 448, 449, 450, 451, 452, 453, 454, 455, 456, 457, 458, 459, 460, 461, 462, 463, 464, 465, 466, 467, 468, 469, 470, 471, 472, 473, 474, 475, 476, 477, 478, 479, 480, 481, 482, 483, 484, 485, 486, 487, 488, 489, 490, 491, 492, 493, 494, 495, 496, 497, 498, 499, 500, 501, 502, 503, 504, 505, 506, 507, 508, 509, 510, 511, 512, 513, 514, 515, 516, 517, 518, 519, 520, 521, 522, 523, 524, 525, 526, 527, 528, 529, 530, 531, 532, 533, 534, 535, 536, 537, 538, 539, 540, 541, 542, 543, 544, 545, 546, 547, 548, 549, 550, 551, 552, 553, 554, 555, 556, 557, 558, 559, 560, 561, 562, 563, 564, 565, 566, 567, 568, 569, 570, 571, 572, 573, 574, 575, 576, 577, 578, 579, 580, 581, 582, 583, 584, 585, 586, 587, 588, 589, 590, 591, 592, 593, 594, 595, 596, 597, 598, 599, 600, 601, 602, 603, 604, 605, 606, 607, 608, 609, 610, 611, 612, 613, 614, 615, 616, 617, 618, 619, 620, 621, 622, 623, 624, 625, 626, 627, 628, 629, 630, 631, 632, 633, 634, 635, 636, 637, 638, 639, 640, 641, 642, 643, 644, 645, 646, 647, 648, 649, 650, 651, 652, 653, 654, 655, 656, 657, 658, 659, 660, 661, 662, 663, 664, 665, 666, 667, 668, 669, 670, 671, 672, 673, 674, 675, 676, 677, 678, 679, 680, 681, 682, 683, 684, 685, 686, 687, 688, 689, 690, 691, 692, 693, 694, 695, 696, 697, 698, 699, 700, 701, 702, 703, 704, 705, 706, 707, 708, 709, 710, 711, 712, 713, 714, 715, 716, 717, 718, 719, 720, 721, 722, 723, 724, 725, 726, 727, 728, 729, 730, 731, 732, 733, 734, 735, 736, 737, 738, 739, 740, 741, 742, 743, 744, 745, 746, 747, 748, 749, 750, 751, 752, 753, 754, 755, 756, 757, 758, 759, 760, 761, 762, 763, 764, 765, 766, 767, 768, 769, 770, 771, 772, 773, 774, 775, 776, 777, 778, 779, 780, 781, 782, 783, 784, 785, 786, 787, 788, 789, 790, 791, 792, 793, 794, 795, 796, 797, 798, 799, 800, 801, 802, 803, 804, 805, 806, 807, 808, 809, 810, 811, 812, 813, 814, 815, 816, 817, 818, 819, 820, 821, 822, 823, 824, 825, 826, 827, 828, 829, 830, 831, 832, 833, 834, 835, 836, 837, 838, 839, 840, 841, 842, 843, 844, 845, 846, 847, 848, 849, 850, 851, 852, 853, 854, 855, 856, 857, 858, 859, 860, 861, 862, 863, 864, 865, 866, 867, 868, 869, 870, 871, 872, 873, 874, 875, 876, 877, 878, 879, 880, 881, 882, 883, 884, 885, 886, 887, 888, 889, 890, 891, 892, 893, 894, 895, 896, 897, 898, 899, 900, 901, 902, 903, 904, 905, 906, 907, 908, 909, 910, 911, 912, 913, 914, 915, 916, 917, 918, 919, 920, 921, 922, 923, 924, 925, 926, 927, 928, 929, 930, 931, 932, 933, 934, 935, 936, 937, 938, 939, 940, 941, 942, 943, 944, 945, 946, 947, 948, 949, 950, 951, 952, 953, 954, 955, 956, 957, 958, 959, 960, 961, 962, 963, 964, 965, 966, 967, 968, 969, 970, 971, 972, 973, 974, 975, 976, 977, 978, 979, 980, 981, 982, 983, 984, 985, 986, 987, 988, 989, 990, 991, 992, 993, 994, 995, 996, 997, 998, 999, 1000.


SHEET 5 OF 7

S-601-A

THE PENNSYLVANIA RAILROAD STANDARD SYMBOLS

OFFICE OF CHIEF SIGNAL ENGINEER
PHILA. PA., JULY 23, 1935.
Approved: *[Signature]*
Chief Signal Engineer

NOT TO SCALE
Approved: *[Signature]*
Chief Engineer



SHEET 6 OF 7

S-601-A

THE PENNSYLVANIA RAILROAD STANDARD SYMBOLS

OFFICE OF CHIEF SIGNAL ENGINEER
PHILA., PA. JULY 23, 1939
Approved: *Arthur H. [Signature]*
Chief Signal Engineer.

NOT TO SCALE
Approved: *[Signature]*
Chief Engineer.





SYMBOLS

-  10 — T10 SWITCH & LOCK MOVEMENT
-  20 — T20 SWITCH & LOCK MOVEMENT
-  B — BETHLEHEM SWITCH & LOCK MOVEMENT
-  C — NEW CENTURY SWITCH STAND.

- L — LOW SWITCH LAMP.
- I — INTERMEDIATE SWITCH LAMP.
- H — HIGH SWITCH LAMP.
- ⊙ L — LOW REFLECTOR INDICATOR.
- ⊙ I — INTERMEDIATE REFLECTOR INDICATOR.
- ⊙ H — HIGH REFLECTOR INDICATOR.
- L — LOW TARGET (NO LAMP OR REFLECTOR INDICATOR)
- I — INTERMEDIATE TARGET (NO LAMP OR REFLECTOR INDICATOR)
- H — HIGH TARGET (NO LAMP OR REFLECTOR INDICATOR)

- HD — HEAVY DUTY CIRCUIT CONTROLLER
- LD — LIGHT DUTY CIRCUIT CONTROLLER
- PD — POINT DETECTOR.
- HO — HAND OPERATED
- PC — PIPE CONNECTED. (NOT NECESSARY TO INDICATE WHERE 5-232 AND 5-233 ARE PROVIDED).

APPLICATION OF SYMBOLS



RUNS OF CONNECTIONS

- PIPE (MECHANICAL)
- UNDERGROUND OR AERIAL CABLE (NOT IN DUCT)
- WIRE DUCT
- COMPRESSED AIR
- MECHANICAL PIPE & DUCT
- MECHANICAL PIPE AND AIR
- DUCT AND AIR
- MECHANICAL PIPE DUCT AND AIR

AIR PIPE AND FITTINGS

- EXPANSION JOINT
- TEE
- PIPE ANCHOR
- REDUCER OR BUSHING (POINT TO SMALLER PIPE)
- UNION
- COMBINATION COCK AND UNION
- MANIFOLD CONDENSER
- MAIN RESERVOIR
- AUXILIARY RESERVOIR
- PLUG COCK (DRAIN OR BLOW OFF)
- VALVE
- ET
- ENGINE TAP

REVISIONS

SYMBOLS FOR HAND-OPERATED SWITCH MECHANISMS, SWITCH TARGETS, ETC., DRAWN FROM SKETCH PLAN DATED 3-24-41.

SHEET 7 OF 7

5-601-A



THE PENNSYLVANIA RAILROAD STANDARD SYMBOLS

OFFICE OF CHIEF ENGINEER,
PHILA., PA., APRIL 12, 1947.

NOT TO SCALE

APPROVED:

W. A. Griffith
ASST. CHIEF ENGINEER - T.C. & S.

APPROVED:

W. A. Griffith
CHIEF ENGINEER.

RULE	INDICATION	NAME	FIGURE						
			A	B	C	D	E	F	G
280	PROCEED; MANUAL BLOCK CLEAR.	CLEAR-BLOCK							
281	PROCEED.	CLEAR							
282	PROCEED APPROACHING NEXT SIGNAL AT MEDIUM SPEED. NOTE-TRAINS MAY PROCEED APPROACHING NEXT SIGNAL AT NOT EXCEEDING 45 MILES PER HOUR AT SIGNALS DISPLAYING A YELLOW TRIANGLE OUTLINED IN BLACK.	APPROACH-MEDIUM							
283	PROCEED; MEDIUM SPEED WITHIN INTERLOCKING LIMITS. NOTE-TRAINS MAY PROCEED AT NOT EXCEEDING 45 MILES PER HOUR AT SIGNALS DISPLAYING A YELLOW TRIANGLE OUTLINED IN BLACK.	MEDIUM-CLEAR							
285	PROCEED PREPARED TO STOP AT NEXT SIGNAL. TRAIN EXCEEDING MEDIUM SPEED MUST AT ONCE REDUCE TO THAT SPEED.	APPROACH							
285 A	TRAIN EXCEEDING MEDIUM SPEED MUST AT ONCE REDUCE TO THAT SPEED. WHERE A FACING SWITCH IS CONNECTED WITH THE SIGNAL, APPROACH THAT SWITCH PREPARED TO STOP. APPROACH NEXT SIGNAL PREPARED TO STOP.	CAUTION							
287	PROCEED; SLOW SPEED WITHIN INTERLOCKING LIMITS.	SLOW-CLEAR							
288	PROCEED PREPARED TO STOP AT NEXT SIGNAL. SLOW SPEED WITHIN INTERLOCKING LIMITS.	SLOW-APPROACH							
289	BLOCK OCCUPIED; FOR PASSENGER TRAINS, STOP; FOR TRAINS OTHER THAN PASSENGER TRAINS, PROCEED PREPARED TO STOP SHORT OF A TRAIN OR OBSTRUCTION, BUT NOT EXCEEDING 15 MILES PER HOUR.	PERMISSIVE-BLOCK							
290	PROCEED AT RESTRICTED SPEED.	RESTRICTING							
291	STOP; THEN PROCEED AT RESTRICTED SPEED. NOTE-FREIGHT TRAINS OF 90 OR MORE CARS OR HAVING TONNAGE OF 90% OR MORE OF THE PRESCRIBED ENGINE RATING MAY PROCEED AT RESTRICTED SPEED WITHOUT STOPPING AT SIGNALS DISPLAYING A YELLOW DISK ON WHICH IS SHOWN THE LETTER "G" IN BLACK.	STOP-AND-PROCEED							
292	STOP.	STOP-SIGNAL							
293	LIMIT OF THE BLOCK. NOTE-FIG. A- YELLOW LIGHT TO BE PLACED NEXT TO TRACK GOVERNED.	BLOCK-LIMIT							
293 A	PROCEED PREPARED TO STOP AT NEXT BLOCK-LIMIT SIGNAL. TRAIN EXCEEDING MEDIUM SPEED MUST AT ONCE REDUCE TO THAT SPEED. NOTE- WILL NOT APPLY TO TRAINS AUTHORIZED TO PASS THE BLOCK-LIMIT STATION AS THOUGH CLEAR-BLOCK SIGNAL WERE DISPLAYED.	APPROACH BLOCK-LIMIT							
294	ORDERS. NOTE-FIG. A- TO APPLY TO TRAINS GOVERNED BY FIXED SIGNAL WITH WHICH CONNECTED. NOTE-FIG. B- BY DAY THE YELLOW LAMP IS NOT DISPLAYED.	TRAIN-ORDER							

NOTE:-

IN THE ILLUSTRATION OF TYPICAL ASPECTS, RULES 280 TO 294, INCLUSIVE:

R - RED
P - PURPLE
Y - YELLOW
G - GREEN

SPEEDS

MEDIUM SPEED - NOT EXCEEDING ONE-HALF THE SPEED

AUTHORIZED FOR PASSENGER TRAINS BUT NOT EXCEEDING 30 MILES PER HOUR.

REDUCED SPEED - PREPARED TO STOP SHORT OF TRAIN OR OBSTRUCTION.

SLOW SPEED - NOT EXCEEDING 15 MILES PER HOUR.

RESTRICTED SPEED - NOT EXCEEDING 15 MILES PER HOUR PREPARED TO STOP SHORT OF TRAIN, OBSTRUCTION OR SWITCH NOT PROPERLY LINED AND TO LOOK OUT FOR BROKEN RAIL.

REVISIONS

REDRAWN FROM APPROVED PLAN S-602-F, DATED JANUARY 5, 1938 AND REVISED.
H. SEPTEMBER 10, 1942. INDICATION FOR RULE 283 MODIFIED. APPROVED N. L. Stanton
I. JUNE 7, 1944. RULE 293 A ADDED. APPROVED N. L. Stanton
U. AUGUST 20, 1944. RULES 282 & 283 CHANGED-NOT ADDED-EFFECTIVE 9-15-44. APPROVED N. L. Stanton
K. MARCH 14, 1945. NOTE FOR RULE 283 CORRECTED. APPROVED McQuiff
L. SEPTEMBER 28, 1945. RULE 289 CHANGED AND RULE 294 REARRANGED. APPROVED McQuiff

1 SHEET



S-602-L

THE PENNSYLVANIA RAILROAD STANDARD SIGNAL ASPECTS

OFFICE OF CHIEF ENGINEER, PHILA., PA., JULY 12, 1941.

Approved N. L. Stanton
Assistant Chief Engineer-Signals

Approved W. J. Sengen
Chief Engineer

INSTRUMENTS AND APPARATUS		DESIGNATION		EXAMPLES & EXPLANATIONS.
		R.R.R.	A.A.R.	
AUXILIARY CIRCUIT CONTROLLERS		SC	CC	15C, 25C - 1CC, 2CC
AUTOMATIC SHORT ARM GATES		G	XG	1G, 2G - 1XG, 2XG (2GA, 2GB - 2XGA, 2XGB TWO GATES ON SAME SIDE)
AUTOMATIC SHORT ARM GATE LIGHTS		GA, GB, GS		1GA, 1GB, 1GS. (5 - STEADILY BURNING LAMP)
BATTERY DESIGNATIONS	CABIN OR CENTRAL LOCATIONS	M, MI, MZ		B(M), C(M), B(MI), C(MI)
	HOME SIGNAL LOCATIONS	HA, HB, 26L		B(HA), C(HA), B(26L), C(26L) - 26L IS DESIGNATION OF INSTRUMENT CASE
	DISTANT & AUTOMATIC SIGNAL LOCATIONS	731, 834		B(731), C(731), B(834), C(834) - NUMBER IS TAKEN FROM SIGNAL NUMBER
	HIGHWAY CROSSING AND CUT-SECTION LOCATIONS	741, 824		B(741), C(741) - 741, 824 - LOCATION NUMBER TAKEN FROM NEAREST MILE POST
	COMMONS TO DISTANT SIGNAL LOCATION AND BEYOND.	GE	EG	COMMONS TO THE EAST
		CW	WC	" " " WEST
CN		NC	" " " NORTH	
CS		SC	" " " SOUTH	
ELECTRIC SWITCH LOCKS		WK	WL	AWK, 17WK, 19WKA, 19WKB
HIGHWAY CROSSING SIGNALS	CROSSING BELLS	VB	XX	1VB, 2VB - 1XX, 2XX
	FLASHING LIGHT SIGNALS	CL		1CL, 2CL
	LAMP UNITS ON FLASHING LIGHT SIGNALS	CLA, CLB, CLC, CLD		1CLA, 1CLB, 1CLC, 1CLD 2CLA, 2CLB, 2CLC, 2CLD
INDICATION LIGHTS		EL	K	2PEL, 26LEL, 5EL - 2RAK, 26LAK, 5K
INDICATION LOCKS	K	M OR L	2K, 4K - 2M, 4L (SEE SH. 5)	WHERE ONE LOCK IS USED ON LEVER
	SK	M	4SK - 4M - SIGNAL INDICATION LOCK	WHERE MORE THAN ONE LOCK IS USED ON LEVER
	TK	FL	4TK - 4FL - TRAFFIC LOCK	
	NK	NM	3NK - 3NM - NORMAL IND. LOCK	
	RK	RM	3RK - 3RM - REVERSE IND. LOCK	
	DK	L	3DK - 3L - DETECTOR LOCK	
PANEL TYPE BLOCKING DEVICE		W, E, N, S		1W, 1E, 2W, 2E 1S, 1N, 2S, 2N 1 & 2 - TRACK NUMBERS W, E, N, S - WEST, EAST, NORTH OR SOUTH SIDE OF PANEL TURNBUTTON IS LOCATED
SIGNALS		A, B, C, D		2RA, 2RB, 2RC 8LA, 8LB 26A, 26B, 26C SIGNAL NUMBER FOLLOWED BY A, B, C, ETC., FOR EACH ARM AND SIGNAL CONTROLLED BY SAME LEVER OPERATION.
SIGNAL LIGHT WIRES		L	E	2RASL, 2RAHL, 2RAJL - 2RAE, 2RAHE, 2RADE
SIGNAL REPEATING INDICATORS		M	GK	1M, 2M, 8RM - 1RGK, 2HGK (SEE SH. 4)
SMASHBOARDS		SB		45B, 65BA, 65BB
SPRING COMBINATION (CROSS REFERENCES WHERE JUMPERS ARE NOT SHOWN)		X7-22L		X = JUMPER, 7 = LEVER TO WHICH JUMPER GOES; 22 = GROOVE TO WHICH JUMPER GOES; L = SIDE OF BAND JUMPER IS CONNECTED TO.
TIME RELEASES		SR	TE	5R, 4SR, 5SR, 2SR, 6SR, 8LSR - 2TE, 6TE
TORPEDO PLACING MACHINES		TP		1TP, 2TP - 1 & 2 - TRACK NUMBERS
TRACK INSTRUMENTS		T, TE, TW		1TE, 1TW - ONE DIRECTION, 1T, 2T - TWO DIRECTIONS
TRACK RELAY LOCALS		TL	TQ	4TL, 7TL, 118TL, 141-3TL - 118TQ, 141-3TQ
TRAFFIC LOCK INSTRUMENTS (WHERE TRAFFIC LEVERS ARE NOT AVAILABLE)		F	FL	1F, 2F, 3EF, 3WF - 1FL, 3EFL
TRAIN ORDER SIGNALS		TO		ATO, BTO
TRAIN STOPS		TS	V	04LTS, W27TS - 04LV, W27V

RELAYS		DESIGNATION		EXAMPLES & EXPLANATIONS
		R.R.R.	A.A.R.	
AIR PRESSURE INDICATION RELAYS		AP20M	AP20PSR	RELAY RELEASES WHEN AIR PRESSURE DROPS BELOW 20 POUNDS.
		AP45M	AP45PSR	RELAY RELEASES WHEN AIR PRESSURE DROPS BELOW 45 POUNDS.
A.P.B. DIRECTIONAL RELAYS		S	SR	269S, 270S, 1E5 - 269SR, 270SR, 1E5R
APPROACH RELAYS		P	AR	2LP - 2LAR (WHERE APPROACH SECTIONS ARE INDICATED INDEPENDENTLY, APPROX. SHALL BE THE SIGNAL NUMBER WHICH RELAY INDICATES APPROACH THERE TO: 2LP, 214P - 2LAR, 214AR)
CALLING-ON RELAYS		CR	CO5R	2LCR, 8RCR, 12CR - 2LCOSR, 8RCOSR, 12COSR
DIRECTION SELECTING RELAYS		DS	FR	346DS, 364-1DS - 346FR, 364-1FR - WHERE MORE THAN ONE RELAY IS REQUIRED IN A BLOCK, 346DSR, 346DSB - 346FRB, 346FRB
DRAGGING EQUIPMENT DETECTOR RELAYS	DETECTOR RELAY	DTR	DEDR	1DTR, 2DTR - 1DEDR, 2DEDR
	DETECTOR LINE RELAY	DTM	DEDR	1DTM, 2DTM - 1DEDR, 2DEDR
	RESTORE RELAY	DTMU	PB5R	1DTMU, 3DTMU, 1PB5R, 3PB5R
HIGHWAY CROSSING SIGNALS AND AUTOMATIC SHORT ARM GATES	BELL CONTROL RELAY	VBR	XXR	1VBR, 2VBR - 1XXR, 2XXR
	CROSSING SIGNAL CONTROL RELAY	XR	XPR	1XR FOR ONE CROSSING - 2XR AND 3XR FOR SECOND AND THIRD CROSSINGS.
	CUT-OUT RELAYS	COR	PB5R	1COR, 2COR - 1PB5R, 2PB5R
	DIRECTIONAL (SLOW-RELEASE) RELAYS	EM, WM, NM, SM	EX5R, WX5R	2EM, 2WM - 2EX5R, 2WX5R (WHERE MORE THAN ONE CROSSING IS INVOLVED - 2EMA, 2WMA - 2EX5RA, 2WX5RA)
	FLASHER RELAYS	LR	EOR	WHERE MORE THAN ONE CROSSING IS INVOLVED, 1LR, 1RB - EOR, EOR, ETC.
	GATE CLEARING RELAY	GTNR	XGNR	1GTNR, 2GTNR - 1GNR, 2GNR
	GATE DELAY RELAY	GTR	XGNRPR	1GTR, 2GTR - 1GNRPR, 2GNRPR
	INTERLOCKING RELAYS	EM, WM	EXR, WXR	1EM, 1EMA - 1EXR, 1EXRA (WHERE RELAY IS CONNECTED DIRECT TO TRACK IT SHALL TAKE DESIGNATION OF TRACK SECTION TO WHICH IT IS CONNECTED)
	LINE CONTROL RELAYS	CLR	ETPR, WTPR	1CLR, 1CLER (E INDICATES RELAY CONTROLS FOR EASTWARD MOVEMENT, 1ETPR, 1WTPR (E & W - REPEATS SECTIONS EAST AND WEST)
	INDICATION LIGHT RELAYS	ELR	KR	4ARKL, 7TEL, 9ELR - 4AKR, 7TKR, 9KR

NOTE:

A.A.R. CIRCUIT NOMENCLATURE SHALL BE USED FOR ALL NEW WORK AND EXTENSIVE RENEWALS.
FOR COMPLETE A.A.R. CIRCUIT NOMENCLATURE SEE SHEETS 4 AND 5

REVISIONS

OCTOBER 3, 1949.
A.A.R. CIRCUIT NOMENCLATURE ADDED.
APPROVED:
H. L. Salmon
SUPERSEDES APPROVED
PLAN S-802 DATED 4-16-23.

SHEET 1 OF 5

S-802

THE PENNSYLVANIA RAILROAD
STANDARD

DESIGNATION OF INSTRUMENTS & APPARATUS
INDICATED ON SIGNAL CIRCUIT PLANS

OFFICE OF CHIEF ENGINEER,
PHILA., PA., MAY 5, 1947.

APPROVED:

H. L. Salmon
ASST. CHIEF ENGINEER, T.C.S.

APPROVED:

H. L. Salmon
CHIEF ENGINEER

RELAYS		DESIGNATION P.R.R. A.A.R.		EXAMPLES & EXPLANATIONS
OVERLOAD RELAYS		OR		3-OR, 5-OR
POLE-CHANGING RELAYS		PCR		1PCR, 6RPCR, 8LPCR, 10PCR
POWER-OFF RELAYS		POR		POR - (WHERE MORE THAN ONE RELAY IS REQUIRED: POR A, POR B.)
POWER-OFF REPEATING RELAYS		PORM	PORPR	PORM - (WHERE MORE THAN ONE RELAY IS REQUIRED: PORM A, PORM B - PORPR A, PORPR B)
REPEATING RELAYS		M	PR	9TM, 23NM, 23RM - 9TPR, 23NLPR, 23RLPR 7TMA, 7TMB, 7TMC - 7TPR, 7TPPR, 7TPPR
ROUTE LOCKING RELAYS		E W	ESR WSR	3E, 5W - 3ESR, 5WSR. (E AND W INDICATES DIRECTION, LIKEWISE NORTH AND SOUTH)
ROUTE SELECTING RELAYS		HM	BPR	2HM - 2BPR - REPEATER OF TRACK SECTION BEYOND INTERLOCKING WITH NECESSARY SELECTION. MAY BE USED WHERE TWO OR MORE SIGNED ROUTES ARE INVOLVED.
SIGNAL CONTROL RELAYS	HOME SIGNAL - APPROACH OR PERM.	H	HR	4RAH, 6LAH - 4RAHR, 6LAHR
	HOME SIGNAL - SLOW APPROACH	HA	HAR	6LBHA - 6LBHAR WHERE SLOW APPROACH OR RESTRICTING INDICATION IS PROVIDED BUT NOT BOTH. SUFFIX 'A' & 'B' MAY BE OMITTED.
	HOME SIGNAL - RESTRICTING	HB	HBR	6LBHB - 6LBHBR
	HOME SIGNAL - STOP & PROCEED	N	NR	4RBN, 6LBN - 4RBNR, 6LBNR
	HOME SIGNAL - CLEAR	J	DR	4RAJ, 4RAJ WHERE SEPARATE RELAY IS USED 4RADR, 4RADR FOR EACH ARM
	DISTANT AND AUTOMATIC SIGNALS OR CLEAR	J	DR	4RJ - 4RDR WHERE ONE RELAY IS USED
POLARIZED APPROACH AND CLEAR CONTROL RELAYS		HJ	HDR	169HJ, 170-1HJ, 170-2HJ - 169HDR, 170-1HDR, 170-2HDR
SIGNAL LOCK RELAYS		KR	RGPR	4LKR - 2MRGPR (LINE REPEATING RELAYS)
SLOW ACTING RELAYS		SA	PR	169HJSA - 169HDR 395TSA - 395TPR USE FOR BOTH SLOW-RELEASE AND SLOW PICKUP RELAYS, SYMBOL COVERING CHARACTERISTICS.
SMASHBOARD CONTROL RELAYS		5BNR		65BNR - FOR NORMAL DRIVE (STOP)
		5BRR		65BRR - FOR REVERSE DRIVE (CLEAR)
		5BR		65BR - WHERE CLEAR DRIVE ONLY IS PROVIDED
SPECIAL RELAYS		T	Z	1T, 2T - WHERE USED FOR DESIGNATED TRACK.
		U		6U, 10RU - WHERE USED IN CONNECTION WITH SIGNAL LEVER Z - USE FOR ANY SPECIAL TERM (TO BE NOTED ON PLAN)
SWITCH REPEATING RELAYS		SS	WPR	35S - 3WPR DIRECT REPEATER OF SWITCH.
		55A, 55B	WPR A, WPR B	355A, 355B - 3WPR A, 3WPR B MULTIPLE REPEATERS
		55NM, 55RM	NWPR, RWPR	355NM - 3NWPR NEUTRAL REPEATERS (N - NORMAL) 355RM - 3RWPR REPEATER, R - REVERSE REPEATER
TIME ELEMENT RELAYS		TER		1TER, 4TER, 6LTER (L - LONG TIME), 6STER (S - SHORT TIME)
TIME ELEMENT REPEATING RELAYS		TEM	TEPR	1TEM, 4TEM - 1TEPR, 4TEPR
TIME ELEMENT CHECK CONTACT REPEATING STICK RELAYS		TES	TESR	1TES, 4TES - 1TESR, 4TESR
TIME LOCKING STICK RELAYS		KM	MPSR	4RKM, 6LKM, 10KM - 4RMPSR, 6LMPSR, 10MPSR
TORPEDO PLACING MACHINE RELAYS	CONTROL RELAY	TPS		2TPS, 4TPS
	FIRING INDICATION RELAY	TPNM		2TPNM, 4TPNM
	REVERSE MOVEMENT RELAY	E, W		2RE, 6LW
	SIGNAL RETAINING STICK RELAY	TPWS, TPES		2TPWS, 4TPES
TRACK RELAYS		TR		1TR, 395TR, 430-ATR - TRACK RELAYS SHALL TAKE DESIGNATION OF TRACK CIRCUIT TO WHICH THEY ARE CONNECTED. (SEE PLANS 5-801)
TRACK INDICATING RELAYS		A	HSR	2RA, 6LA, 10A - 2RHSR, 6LHSR, 10HSR
STICK RELAY REPEATING TRACK RELAY		TS	TPSR	9TS, 4TTTS - 9TPSR, 4TTTPSR
TRAFFIC RELAYS		FR		8EFR, 8WFR, 14EFR, 14WFR
TRAIN ORDER SIGNAL CONTROL RELAYS		TOR		4TOR, 8TOR
TWO-RATE CHARGE RELAYS		TRCR		TRCR - WHERE MORE THAN ONE RELAY IS REQUIRED - TRCA, TRCB

CODED TRACK CIRCUITS		DESIGNATION P.R.R. A.A.R.		EXAMPLES & EXPLANATIONS
INSTRUMENTS & APPARATUS				
ARC SUPPRESSOR		AS		1DTAS, 2DTAS
CODE CONTROL RELAY		V	VR	1V, 7TV, 9TVE, 9TVW,
		H	HR	395H, 430-1H, 430-2H - 395HR, 430-1HR, 430-2HR
		CD	CDR	110LCD -
CODE DETECTING RELAYS		SA	TPR	15A, 25A - CUT-SECTION
		BJ	BDR	395BJ, 430-1BJ - 395BDR, 430-1BDR 120 CODE
		J AJ	DR ADR	157J, 430-1AJ, - 157DR, 430-1ADR 180 CODE
CODE DETECTING UNIT		CDU		1CDU, 2CDU
CODE FOLLOWING TRACK RELAY		TR		7TR, 395TR, 430-ATR
CODE FOLLOWING TRACK REPEATING RELAY		FSA	TFPR	1FSA, 2FSA - FRONT CONTACT REPEATERS
		B5A	TBPR	1B5A, 2B5A - BACK CONTACT REPEATERS
CODE TRANSMITTER		CT		CTA, CTB, 75CT, 120CT, 180CT
CODE TRANSMITTER REPEATER		CTM	CTPR	1CTM, 2CTM
DECODING TRANSFORMER		DT		1DT, 2DT, 430-IDT
DECODING UNIT		DU		120DU, 180DU
FREQUENCY CONVERTER		FC		1FC, 117FC
IMPULSE RELAY		IR		395IR, 430-AIR
IMPULSE TRANSFORMER		IT		395IT, 430-AIT
LOCKOUT RELAY		LOR		395LOR, 430-AIOR
RELAY - RETURN CODE CONTROLLED		AP	ATPR	395TAP
RESONANT TRANSFORMER RECTIFIER UNIT		RTR		4LRTR, 25RTR
REVERSIBLE CODED TRACK RELAY		TR		WTR, ETR, 5XTR, NXTR
STEADY ENERGY DETECTOR RELAY		TRAS		67TRAS, 78TRAS
TRACK RELAY - RETURN CODE		AR	ATR	1TAR, 395TAR
TRACK TRANSFORMER		TT		XITT, 395TT
TRACK TRANSFORMER-PRIMARY CODE		TP		XITP, 395TP
TUNED ALTERNATOR		TA		1TA, XITA, 395TA

NOTE:
A.A.R. CIRCUIT NOMENCLATURE SHALL BE USED FOR ALL NEW WORK AND EXTENSIVE RENEWALS.
FOR COMPLETE A.A.R. CIRCUIT NOMENCLATURE SEE SHEETS 4 AND 5.

REVISIONS

OCTOBER 3, 1949.
A.A.R. CIRCUIT NOMENCLATURE ADDED.
APPROVED:
W. H. Salmon
SUPERSEDES APPROVED PLAN 5-802 DATED 4-16-23.
DESIGNATIONS FOR CODED TRACK CIRCUITS ADDED.

SHEET 2 OF 5

S-802

THE PENNSYLVANIA RAILROAD STANDARD DESIGNATION OF INSTRUMENTS & APPARATUS INDICATED ON SIGNAL CIRCUIT PLANS

OFFICE OF CHIEF ENGINEER,
PHILA., PA., MAY 5, 1947.

APPROVED:

W. H. Salmon
ASST. CHIEF ENGINEER, T.-C.-S.

APPROVED:

W. H. Salmon
CHIEF ENGINEER

C.T.C. AND ALL-RELAY INSTALLATIONS				
INSTRUMENTS & APPLICATIONS		DESIGNATION P.R.R. A.A.R.		EXAMPLES & EXPLANATIONS
CARRIER CONTROL (100 CYCLE) RELAY FOR ELECTRIC SWITCH LOCKS		LWKR	WLR	3LWKR, 7LWKR - 3WLR, 7WLR
CODE RECEIVING OR LEVER REPEATING STICK RELAYS	SIGNALS	HJ	HJR	2RHJ, 2LHJ, 110RHJ, 110LHJ - 2RHJR, 2LHJR
	BLOCK SIGNALS (PERM.)	PHJ	PHJR	95RPHJ, 97LPHJ - 95RPHJR
	BLOCK SIGNALS (CLEAR)	CHJ	CHJR	95RCHJ, 97LCHJ - 95RCHJR
	CALLING-ON SIGNALS	CR	COR	2CR, 110CR - 2COR
	D.E.D. RESTORE	DTMS	DEDSR	100DTMS, 140DTMS - 100DEDSR
	ELECTRIC SWITCH LOCKS	WKS	WLSR	89WKS, 121WKS - 89WLSR
	MAINTAINER'S CALL	MC	MCR	59MC - 59MCR
	SWITCHES	NWS, RWS	NWSR, RWSR	3NWS, 3RWS - 3NWSR, 3RWSR (N-NORMAL, R-REVERSE)
TRAFFIC	FS	FJR	8EFS, 8WFS, 10NFS, 10SFS E, W, N, S = DIRECTION.	
TROLLEY SECTIONALIZING SWs.		OS, GS		22-OS, 22-GS O = OPEN, C = CLOSED
DIRECTION SELECTING RELAYS		DJ	FR	1E0J, 1W0J, 2E0J, 2W0J - 1EFR, 1WFR
DIRECTION STICK RELAYS		S	SR	82RS, 82LS - 82SR
ROUTE CHECK NETWORK		HJM	HJPR	110RHJM, 110LHJM - 110RHJPR
SIGNAL INDICATION STICK RELAYS		KM	ASR	2RKJ, 2LKM, 110RKJ, 110LKM - 2RASR, 2LASR
SPECIAL STICK RELAYS		TJ	TKSR	2TJ, 2GTS - 2TKSR
SPECIAL TRAFFIC CHECKING RELAYS		F, FS	FR, FJR	1TWJ, 1TWFS, 2TEJ, 2TEFS - 1WFR, 1WFSR
SPECIAL REPEATING RELAY FOR ELEC. SW. LOCKS		WKS	WLSR	3WKS, 7WKS - 3WLSR, 7WLSR
SWITCH INDICATION LOCK RELAYS		KM	LR	105KM, 107KM - 105LR, 107LR
SWITCH (SS & WR) AGREEMENT RELAYS		NM, RM	NWCR, RWCR	3NM, 3NMA, 3NMB, 3RM, 3RMA, 3RMB - 3NWCR, 3RWCR
TIME ELEMENT CONTROL RELAYS		LRKM	ASPR	2LRKM, 2GLRKM - 2ASPR, 2GLASPR
TIME ELEMENT SELECTION RELAYS		S, ST	STR	112S, 112ST. (ST = SHORT TIME) - 112STR
TIME ELEMENT RELAYS		TER, STER, LTER		2GTER, 2GSTER (SHORT TIME), 2GLTER (LONG TIME)
TRAFFIC INDICATION LOCK RELAYS		KM	FLR	110KM, 115KM - 110FLR, 115FLR
TROLLEY SECTIONALIZING SWITCH IND. RELAY		OK, CK		22-OK, 22-CK O = OPEN, C = CLOSED

C.T. C. MACHINE NETWORK			
INSTRUMENTS & APPARATUS	DESIGNATION		EXAMPLES & EXPLANATIONS
	R.R.	A.A.R.	
D.E.D. INDICATING RELAYS		DTK DEK	124DTK - 124DEK.
"L" SIGNAL CONTROL RELAYS		LG	142LG
"R" SIGNAL CONTROL RELAYS		RG	142RG
NORMAL SIGNAL CONTROL RELAYS		NG	142NG
"L" SIGNAL INDICATING RELAYS		LHK	142LHK
"R" SIGNAL INDICATING RELAYS		RHK	142RHK
SWITCH INDICATING RELAYS		WK	141NWK, 141RWK (N = NORMAL, R = REVERSE).
SWITCH LOCK CONTROL RELAYS		WLP	134WLP
SWITCH LOCK INDICATION RELAYS	K	WLK	141K - 141WLK
TRACK INDICATING RELAYS		TK	141TK, 134ETK, 134NTK
TRAFFIC CONTROL RELAYS	LP	FLP	134LP - 134FLP
TRAFFIC INDICATING RELAYS		FK	134EFK, 134WFK

REVISIONS

OCTOBER 3, 1949.
A.R.R. CIRCUIT NOMENCLATURE ADDED.
APPROVED:
H. L. Salmonson

FIG. 31

S-802



THE PENNSYLVANIA RAILROAD
STANDARD
DESIGNATION OF INSTRUMENTS & APPARATUS
INDICATED ON SIGNAL CIRCUIT PLANS

OFFICE OF CHIEF ENGINEER,
PHILA. PA. MAY 5 1947.

APPROVED:

A. Griffiths

APPROVAL

J. H. Bennett
CHIEF ENGINEER

TABLE OF MEANING OF LETTERS
DESCRIPTIVE AND DESIGNATIVE TERMS.

A - APPROACH
B - BLOCK - BUTTON - POSITIVE ENERGY - BRIDGE - BACK
C - COMMON - CHANGER - COUNTER - CORRESPONDENCE - CIRCUIT
D - CONTROLLER - CODE - CHECKING CONTACTS - CHANGE
E - PROCEED INDICATION OF A SIGNAL - DETECTOR - DECODING - DRAGGING
F - EAST - EASTWARD - ELECTRIC LIGHT - ELEMENT - EQUIPMENT - ELECTRONIC
G - TRAFFIC - FRONT - FREQUENCY
H - GREEN - SIGNAL (OPERATING MECHANISM) - GROUND - GATE
I - HOME - APPROACH INDICATION OF A SIGNAL
J - SKATE - DUAL CONTROL
K - INDICATOR
L - LEFT - LOCK PREVENTING INITIAL MOVEMENT OF A LEVER FROM NORMAL OR REVERSE POSITION - LOCKING - LEVER - LIGHT
M - SPLIT BATTERY - LOCK VALVE - LOCK
N - LOCK PREVENTING FINAL OR INDICATING MOVEMENT OF A LEVER - MAGNETIC - MARKER - MANUAL
O - NORMAL - NORTH - NORTHWARD - NEGATIVE
P - ORDER - OPERATION - OFF - OVERLOAD - OUT - OVER
Q - POLE - POWER - PURPLE - PUSH - REPEATING - PRIMARY
R - LOCAL OR SECONDARY COIL (AS IN DOUBLE-ELEMENT RELAY OR MECHANISM)
S - RIGHT - RED - REVERSE - RELAY - POWER OPERATED CONTROLLER OR CONTACTOR - ROUTE - STOP INDICATION ON SIGNAL - RAIL
T - SOUTH - SOUTHWARD - STICK - STORAGE
U - TRACK - TIME - TRAIN - TELEPHONE - TRANSFORMER - TRANSMITTER
V - RETAINED UNIT
W - TRAIN STOP (TRACK ELEMENT) - ELECTRO-PNEU. STOP VALVE
X - SWITCH (OPERATING MECHANISM) - WEST - WESTWARD - WHITE
Y - CROSSING - INTERLOCKING - BELL - BUZZER - A.C.
Z - SLOT - YELLOW - HOLD CLEAR
Z - USE FOR ANY SPECIAL TERM (TO BE NOTED ON PLAN)

IN ORDER TO DISTINGUISH BETWEEN RIGHT AND LEFT POSITION OF THREE-POSITION LEVERS, USE R (RIGHT) OR L (LEFT) AFTER THE LEVER NUMBER, AS 10R, 10L. WHEN ONE LEVER CONTROLS TWO OR MORE FUNCTIONS, USE LETTERS A, B, C, ETC., AFTER THE LEVER NUMBERS: FOR EXAMPLE, 10A, 10B, 10C, ETC. IN CASE OF THREE-POSITION LEVERS CONTROLLING TWO OR MORE FUNCTIONS IN EACH POSITION, USE COMBINATIONS AS FOLLOWS: 10RA, 10LA, ETC.

EXAMPLES OF COMBINATIONS USED TO DESIGNATE WIRES AND OPERATED UNITS

ENERGY WIRES

(SUFFIX FIGURE SHOULD BE USED TO INDICATE VOLTAGES: FOR EXAMPLE, CX110 MEANING COMMON A.C. 110 VOLTS.)
C - COMMON D.C.
EC - COMMON EAST, MEANING D.C. FROM SYSTEM EAST, LIKEWISE NORTH, SOUTH AND WEST.
FC - COMMON TRAFFIC LOCKING
CX - COMMON A.C.
ENX - NEGATIVE ENERGY A.C. FROM POR FOR AN ELECTRIC LIGHT, OR EAST NEGATIVE A.C. ENERGY, LIKEWISE NORTH, SOUTH AND WEST.
NX - NEGATIVE A.C. ENERGY
BL - POSITIVE SIDE OF SPLIT BATTERY
NL - NEGATIVE SIDE OF SPLIT BATTERY
CL - COMMON OF SPLIT BATTERY
N - NEGATIVE D.C. ENERGY
P - POSITIVE D.C. ENERGY
EB - POSITIVE ENERGY EAST, LIKEWISE NORTH, SOUTH AND WEST
BB - BATTERY, SECOND BATTERY
BBB - BATTERY, THIRD BATTERY
BX - POSITIVE A.C. ENERGY
EBX - POSITIVE ENERGY A.C. FROM POR FOR AN ELECTRIC LIGHT, OR EAST POSITIVE A.C. ENERGY, LIKEWISE NORTH, SOUTH AND WEST

OPERATED UNITS RELATING TO TRACK CIRCUITS

T - TRACK SECTION
TR - TRACK RELAY
TPR - RELAY REPEATING TRACK RELAY
TPPR - RELAY REPEATING TRACK REPEATING RELAY
TSR - TRACK STICK RELAY
TSPR - RELAY REPEATING TRACK STICK RELAY
TK - INDICATOR, INDICATING CONDITION OF A TRACK CIRCUIT
TPSR - STICK RELAY REPEATING TRACK RELAY
BPR - BLOCK REPEATER RELAY, RELAY REPEATING THE TRACK CIRCUITS IN A BLOCK
BK - BLOCK INDICATOR

WIRES RELATING TO TRACK CIRCUITS

TB - TRACK POSITIVE - POSITIVE ENERGY TO RAIL
TN - TRACK NEGATIVE - NEGATIVE ENERGY TO RAIL
RB - RELAY POSITIVE - WIRE FROM POSITIVE RAIL TO RELAY
RN - RELAY NEGATIVE - WIRE FROM NEGATIVE RAIL TO RELAY
TR - POSITIVE CONTROL OF LOCAL COIL, DOUBLE ELEMENT A.C. RELAY
WB - POSITIVE RAIL TO SWITCH CIRCUIT CONTROLLER
WN - NEGATIVE RAIL TO SWITCH CIRCUIT CONTROLLER

OPERATED UNITS RELATING TO SWITCHES

W - SWITCH OPERATING MECHANISM OR LOCK VALVE
WR - RELAY, CONTROLLER OR CONTACTOR CONTROLLING BOTH NORMAL AND REVERSE OPERATIONS OF A SWITCH OR AN ELECTRIC SWITCH LOCK
WNR - RELAY, CONTROLLER OR CONTACTOR CONTROLLING THE NORMAL OPERATION OF A SWITCH OR AN ELECTRIC SWITCH LOCK
WRR - RELAY, CONTROLLER OR CONTACTOR CONTROLLING THE REVERSE OPERATION OF A SWITCH OR AN ELECTRIC SWITCH LOCK
WRPR - RELAY REPEATING WR OR NORMAL POSITION OF WR
WNRPR - RELAY REPEATING WNR OR REVERSE POSITION OF WR
WRPR - RELAY REPEATING WRR OR REVERSE POSITION OF WR
WRRPR - RELAY REPEATING WRR OR REVERSE POSITION OF WR
NWPR - RELAY REPEATING NORMAL POSITION OF SWITCH OR NORMAL POSITION OF WPR
RWPR - RELAY REPEATING REVERSE POSITION OF SWITCH OR REVERSE POSITION OF WPR
WK - INDICATOR INDICATING THE POSITIONS OF A SWITCH
WL - SWITCH LOCK OPERATING MECHANISM ON A SWITCH
NWLPR - RELAY REPEATING NORMAL POSITION OF SWITCH LOCK
NJPR - RELAY REPEATING NORMAL POSITION OF DUAL-CONTROL LEVER
RJPR - RELAY REPEATING REVERSE POSITION OF DUAL-CONTROL LEVER
NWK - INDICATOR INDICATING THE NORMAL POSITION OF A SWITCH
RWK - INDICATOR INDICATING THE REVERSE POSITION OF A SWITCH
WAK - INDICATOR INDICATING THE CONDITION APPROACHING A SWITCH
RWLPR - RELAY REPEATING REVERSE POSITION OF A SWITCH LOCK
WCR - SWITCH CORRESPONDENCE RELAY

OPERATING UNITS RELATING TO SIGNALS

HR - RELAY CONTROLLING APPROACH INDICATION OF A THREE-POSITION SIGNAL OR THE PROCEED INDICATION OF A TWO-POSITION SIGNAL IN ONE-ARM SIGNALING
DR - RELAY CONTROLLING PROCEED INDICATION OF A SIGNAL
HDR - RELAY CONTROLLING APPROACH AND PROCEED INDICATION OF A SIGNAL
HPR - RELAY REPEATING HR OR APPROACH INDICATION POSITION OF HDR
HJR - HOME STICK RELAY CONTROLLING THE APPROACH INDICATION OF A SIGNAL
DPR - RELAY REPEATING DR OR PROCEED INDICATION POSITION OF HDR
RGPR - RELAY REPEATING SIGNAL MECHANISM AT STOP
HGPR - RELAY REPEATING SIGNAL MECHANISM AT APPROACH
RHGPR - RELAY REPEATING SIGNAL MECHANISM AT APPROACH AND STOP
DGPR - RELAY REPEATING SIGNAL MECHANISM AT PROCEED
RGK - INDICATOR INDICATING SIGNAL MECHANISM AT STOP
HGK - INDICATOR INDICATING SIGNAL MECHANISM AT APPROACH
DGK - INDICATOR INDICATING SIGNAL MECHANISM AT PROCEED
ETOH - EAST TRAIN ORDER HR, LIKEWISE WEST, NORTH AND SOUTH
ETOHDR - EAST TRAIN ORDER HDR, LIKEWISE WEST, NORTH AND SOUTH
ETOPHR - EAST TRAIN ORDER REPEATER HR, LIKEWISE WEST, NORTH AND SOUTH
ETOPDR - EAST TRAIN ORDER REPEATER DR, LIKEWISE WEST, NORTH AND SOUTH
HDGPR - RELAY REPEATING SIGNAL MECHANISM IN THE APPROACH AND PROCEED POSITION
HDGK - INDICATOR INDICATING SIGNAL MECHANISM IN THE APPROACH AND PROCEED POSITION
HY - HOLD CLEAR OR RETAINING MECHANISM OF THE APPROACH INDICATION OF A SIGNAL
DY - HOLD CLEAR OR RETAINING MECHANISM OF THE PROCEED INDICATION OF A SIGNAL
HG - APPROACH INDICATION OPERATING MECHANISM OF A SIGNAL
DG - PROCEED INDICATION OPERATING MECHANISM OF A SIGNAL
RG - STOP INDICATION OPERATING MECHANISM OF A SIGNAL

REVISIONS

CIRCUIT NOMENCLATURE IN ACCORDANCE WITH PART 33, A.A.R. SIGNAL SECTION MANUAL, COMPLETE TO 1949.

FOR ALL NEW WORK AND
EXTENSIVE RENEWALS

SHEET 4 OF 5

5-802



THE PENNSYLVANIA RAILROAD
STANDARD
**DESIGNATION OF INSTRUMENTS & APPARATUS
INDICATED ON SIGNAL CIRCUIT PLANS**

OFFICE OF CHIEF ENGINEER,
PHILA., PA., OCTOBER 3, 1949.

APPROVED:
H. G. Salmonson
ASST. CHIEF ENGINEER - SIGNALS

APPROVED:
J. H. Smith
CHIEF ENGINEER

STICK, TRAFFIC AND DIRECTIONAL OPERATED UNITS

SR - STICK RELAY
ESR - EAST STICK RELAY, LIKEWISE NORTH, SOUTH AND WEST
LSR - LOCKING STICK RELAY
EASR - EAST APPROACH STICK RELAY, LIKEWISE NORTH, SOUTH AND WEST
ASR - APPROACH STICK RELAY
FL - TRAFFIC LOCK PREVENTING INITIAL MOVEMENT OF A TRAFFIC LEVER FROM NORMAL OR REVERSE
FLM - TRAFFIC LOCK PREVENTING INITIAL MOVEMENT OF A TRAFFIC LEVER FROM NORMAL OR REVERSE AND ALSO PREVENTING FINAL OR INDICATION MOVEMENT OF SAME LEVER
FR - TRAFFIC RELAY
FLR - TRAFFIC LOCK RELAY CONTROLLING FL
FLMR - TRAFFIC LOCK RELAY CONTROLLING FLM
FLK - TRAFFIC LOCK INDICATOR
FSR - TRAFFIC STICK RELAY
EFSR - EAST TRAFFIC STICK RELAY, LIKEWISE NORTH, SOUTH AND WEST

OPERATED UNITS RELATING TO INDICATORS, LOCKS, INDICATION MAGNETS, AND RELAYS USED FOR LOCKING PURPOSES

M - LOCK PREVENTING THE FINAL MOVEMENT OF A LEVER
L - LOCK PREVENTING THE INITIAL MOVEMENT OF A CONTROLLED FUNCTION OR LEVER
NK - NORMAL INDICATOR INDICATING NORMAL POSITION OF A UNIT
RK - REVERSE INDICATOR INDICATING REVERSE POSITION OF A UNIT
TER - TIME ELEMENT RELAY
NM - LOCK PREVENTING THE FINAL MOVEMENT OF A LEVER TO THE NORMAL POSITION
RM - LOCK PREVENTING THE FINAL MOVEMENT OF A LEVER TO THE REVERSE POSITION
NL - LOCK PREVENTING THE MOVEMENT OF A LEVER OR A CONTROLLED FUNCTION FROM ITS NORMAL POSITION
RL - LOCK PREVENTING THE MOVEMENT OF A LEVER OR A CONTROLLED FUNCTION FROM ITS REVERSE POSITION
LR - RELAY CONTROLLING L LOCK
LPR - REPEATER OF L LOCK RELAY
MR - RELAY CONTROLLING M LOCK
MPR - REPEATER OF M LOCK RELAY
TE - TIME ELEMENT
TESR - TIME ELEMENT STICK RELAY
LK - LOCK INDICATOR REPEATING ELECTRIC LOCKING
TEPR - RELAY REPEATING ENERGIZED POSITION OF TE
TECPR - RELAY REPEATING CHECKING CONTACT OF TE

OPERATED UNITS RELATING TO HIGHWAY CROSSING SIGNALS

XX - CROSSING BELL
EXR - EASTWARD INTERLOCKING OR CROSSING RELAY, LIKEWISE NORTH, SOUTH AND WEST
XS - WIG-WAG MECHANISM - CROSSING GATE MECHANISM
XY - SLOT FOR WIG-WAG MECHANISM - CROSSING GATE MECHANISM
EOR - ELECTRIC LIGHT OPERATING RELAY (FLASHER RELAY)
XSR - DIRECTIONAL RELAY TO HOLD CROSSING SIGNAL CLEAR AS TRAIN RECEDES FROM CROSSING

OPERATED UNITS RELATING TO APPROACH AND ANNUNCIATING OF TRAINS

AX - ANNUNCIATOR INDICATING APPROACH TRAFFIC
EAX - EASTWARD ANNUNCIATOR INDICATING APPROACH OF EASTWARD TRAFFIC, LIKEWISE NORTH, SOUTH AND WEST
AER - RELAY USED FOR APPROACH LIGHTING

MISCELLANEOUS OPERATED UNITS

AK - APPROACH INDICATOR
AR - APPROACH RELAY
PCR - POLE CHANGING RELAY
NLPR - RELAY REPEATING THE NORMAL POSITION OF A LEVER
RLPR - RELAY REPEATING THE REVERSE POSITION OF A LEVER
E - ELECTRIC LIGHT
TO - TRAIN ORDER
WTO - WEST TRAIN ORDER SIGNAL GOVERNING WESTWARD TRAFFIC, LIKEWISE NORTH, SOUTH AND WEST
RR - ROUTE RELAY
VR - TRAIN STOP RELAY
VSR - TRAIN STOP STICK RELAY
VPR - TRAIN STOP REPEATER RELAY
VY - TRAIN STOP RETAINING MECHANISM
KR - INTERLOCKING RELAY
TOR - TRAIN ORDER RELAY
POR - POWER OFF RELAY
LOR - LIGHT OUT RELAY
ME - MARKER LIGHT
OR - OVERLOAD RELAY
GDR - GROUND DETECTOR RELAY
CU - CODE TRANSMITTER
DU - DECODING UNIT
RLNPR - RAIL LOCK NORMAL REPEATING RELAY
RLRPR - RAIL LOCK REVERSE REPEATING RELAY
DEDR - DRAGGING EQUIPMENT DETECTOR
FCOR - FREQUENCY CHANGE OVER RELAY

WIRES RELATING TO RELAYS ENDING WITH DESIGNATION SHOWN BELOW MAY BE DESIGNATED AS INDICATED

WIRE	RELAY
BP	BPR
D	DR
H	HR
HO	HOR
P	PR
S	SR
TE	TER
WC	WCR

REVISIONS

CIRCUIT NOMENCLATURE IN ACCORDANCE WITH PART 33, A.A.R. SIGNAL SECTION MANUAL, COMPLETE TO 1949.

FOR ALL NEW WORK AND
EXTENSIVE RENEWALS

SHEET 5 OF 5

S-802



THE PENNSYLVANIA RAILROAD STANDARD DESIGNATION OF INSTRUMENTS & APPARATUS INDICATED ON SIGNAL CIRCUIT PLANS

OFFICE OF CHIEF ENGINEER,
PHILA., PA., OCTOBER 31, 1949.

APPROVED

H. J. Salmonson
ASST. CHIEF ENGINEER-SIGNALS

APPROVED

J. W. W. W.
CHIEF ENGINEER


NOTES:-

1. RAIL BONDS AND CONNECTORS FOR TRACK CIRCUITS AND SWITCHES SHALL BE IN ACCORDANCE WITH P.R.R. STANDARD PLANS, BASIC NOS. S-179, S-180, S-182 AND S-184, FOR STEAM AND A.C. ELECTRIFIED TERRITORY; AND IN ACCORDANCE WITH CHIEF OF MOTIVE POWER PLANS FOR D.C. ELECTRIFIED TERRITORY. (SEE LIST ON THIS SHEET FOR DETAIL REFERENCES.)

2. THE POLARITY OF TRACK CIRCUIT CONNECTIONS ON CIRCUIT PLANS SHALL BE INDICATED.

3.  INSULATING JOINTS, TRACK CIRCUIT ON BOTH SIDES.

4.  INSULATING JOINTS, TRACK CIRCUIT ON ONE SIDE ONLY.

5.  TRACK CIRCUIT WIRE.

6. INSULATING JOINTS IN TURNOUTS, CROSSOVERS, MOVABLE POINT CROSSINGS AND DOUBLE SLIP CROSSINGS, MARKED * OR ©, SHALL NOT BE STAGGERED MORE THAN FIVE FEET. AT OTHER LOCATIONS THEY SHALL BE IN ACCORDANCE WITH CURRENT ISSUE OF C.E. 78.

7. INSULATING JOINTS BETWEEN FROGS IN CROSSOVERS, MARKED ©, MAY BE LOCATED AT HEEL END OF FROG WHERE DESIGN OF FROG IS SUCH THAT SINGLE RAIL HEEL JOINTS ARE PROVIDED FOR. THE MINIMUM LENGTH OF RAIL USED SHALL CONFORM TO THAT PRESCRIBED BY THE CURRENT ISSUE OF C.E. 78 EXCEPT SHORTER RAILS OF MINIMUM LENGTH GIVEN IN FOLLOWING TABLE MAY BE LOCATED IN THE CROSSOVER AND CONNECTED TO HEEL OF FROG TO AVOID STAGGERING THE INSULATING JOINTS AT THE CENTER OF THE CROSSOVER MORE THAN FIVE FEET:

CROSSOVER	MINIMUM LENGTH OF RAIL	
	100 & 130-LB.	131-LB. & HEAVIER
No. 8	7'-0"	11'-0"
No. 10	8'-0"	11'-0"
No. 15	11'-0"	-

8. INSULATING JOINTS MARKED * SHALL BE LOCATED AS PROVIDED FOR IN CURRENT ISSUE OF C.E. 78, APPENDIX-PLANS OF LEAD RAILS.

9. INSULATING JOINTS MARKED * (ARROW AND NUMBER INDICATING THE SWITCH FOR WHICH FOULING IS PROVIDED) ARE FOR FOULING PROTECTION.

10. INSTRUCTIONS FOR LOCATING INSULATING RAIL JOINTS FOR FOULING PROTECTION:-
INSULATING RAIL JOINTS FOR FOULING PROTECTION SHALL BE LOCATED BY DETERMINING THE POINT WHERE THE DISTANCE BETWEEN TRACKS IS THAT OF THE ESTABLISHED INTER-TRACK SPACING. WHERE TRACKS DIVERGE BACK OF THAT POINT, THE JOINTS SHALL BE LOCATED NOT LESS THAN TEN FEET BACK OF SAID POINT TO PROVIDE FOR THE MAXIMUM OVERHANG OF EQUIPMENT BEYOND THE CONTACT POINT OF THE WHEELS; OR, WHERE TRACKS ARE PARALLEL AT THAT POINT, THE JOINTS SHALL BE LOCATED AT OR BACK OF SAID POINT, TO ESTABLISH THE CLEARANCE POINT.

IN GENERAL, INSULATING RAIL JOINTS FOR FOULING PROTECTION SHALL BE SO LOCATED AS TO AFFORD THE SAME CLEARANCE BETWEEN EQUIPMENT ON THE CONVERGING TRACKS AS IS PROVIDED ON PARALLEL TRACKS WITH THE ESTABLISHED INTER-TRACK SPACING.

REFERENCES FOR DETAIL BONDING

TERRITORY	S-803 SHEET NO.		TRACK CIRCUIT CONNECTIONS	TRACK BONDS		SWITCH POINT		FROG		FOULING CONNECTION		INTERLOCKED TRACK CIRCUIT CONN.	DOUBLE SLIP SWITCH	NON-INTERLOCKED SWITCH POINT		S-803 SHEET NO.
	INTER-LOCKED	NON-INTER-LOCKED		RAIL HEAD	LONG BOND	INTER-LOCKED	NON-INTER-LOCKED	INTER-LOCKED	NON-INTER-LOCKED	INTER-LOCKED	NON-INTER-LOCKED			INTER-LOCKED	NON-INTER-LOCKED	
STEAM ROAD																
NON-CAB SIGNAL	2	4	S-184	S-180	S-179	S-182, SH. 2, FIG. J	S-182, SH. 1, FIG. E	S-182, SH. 2, FIG. I	S-182, SH. 1, FIG. D	S-182, SH. 2, FIG. H	S-182, SH. 1, FIG. C	S-182, SH. 2, FIG. K	S-182, SH. 1, FIG. P	S-182, SH. 1, FIG. A	S-182, SH. 1, FIG. G	S-182, SH. 1, FIG. G
CAB SIGNAL	3	5	S-184	S-180	S-179	S-182, SH. 2, FIG. J	S-182, SH. 1, FIG. E	S-182, SH. 2, FIG. I	S-182, SH. 1, FIG. D	S-182, SH. 2, FIG. H	S-182, SH. 1, FIG. C	S-182, SH. 2, FIG. K	S-182, SH. 1, FIG. P	S-182, SH. 1, FIG. A	S-182, SH. 1, FIG. G	S-182, SH. 1, FIG. G
A.C. ELECTRIFIED																
NON-CAB SIGNAL	2	4	S-184	S-180	S-179	S-182, SH. 2, FIG. J	S-182, SH. 1, FIG. E	S-182, SH. 2, FIG. I	S-182, SH. 1, FIG. D	S-182, SH. 2, FIG. H	S-182, SH. 1, FIG. C	S-182, SH. 2, FIG. K	S-182, SH. 1, FIG. P	S-182, SH. 1, FIG. A	S-182, SH. 1, FIG. G	S-182, SH. 1, FIG. G
CAB SIGNAL	3	5	S-184	S-180	S-179	S-182, SH. 2, FIG. J	S-182, SH. 1, FIG. E	S-182, SH. 2, FIG. I	S-182, SH. 1, FIG. D	S-182, SH. 2, FIG. H	S-182, SH. 1, FIG. C	S-182, SH. 2, FIG. K	S-182, SH. 1, FIG. P	S-182, SH. 1, FIG. A	S-182, SH. 1, FIG. G	S-182, SH. 1, FIG. G
D.C. ELECTRIFIED																
NON-CAB SIGNAL	2	4	S-184	F 89011		F 407399	F 407399	F 407399	F 407399	F 407399	F 407399	F 407399	F 407399	F 407399	F 407399	F 407399
CAB SIGNAL	3	5	S-184	F 89011		F 407399	F 407399	F 407399	F 407399	F 407399	F 407399	F 407399	F 407399	F 407399	F 407399	F 407399

△ = FOR BONDING AND INSULATION OF SWITCHES IN D.C. ELECTRIFIED TERRITORY CHIEF OF MOTIVE POWER PLAN REFERENCES ARE GIVEN. REQUISITES AS SHOWN ON PLAN S-803, AND APPLICATIONS AS SHOWN ON PLAN S-182, SHOULD BE FOLLOWED.

GENERAL NOTES AND DETAIL REFERENCES

REVISIONS

SUPPLEMENT S-803, SH. 1, DATED 5-15-88
AND C.O.P. PLAN ET-773-D, DATED 4-11-85

SHEET 1 OF 5

S-803



THE PENNSYLVANIA RAILROAD STANDARD BONDING AND INSULATION OF SWITCHES


OFFICE OF CHIEF ENGINEER,
PHILA., PA., DEC. 29, 1948.

APPROVED:



ASST. CHIEF ENGINEER, T.-C.-S.

APPROVED:



CHIEF ENGINEER




**FEED AND RELAY LEADS FOR TRACK CIRCUITS
FIGURE 2A**




**MULTIPLE TRACK CIRCUIT FOR TURNOUT
FIGURE 2B**




**SERIES TRACK CIRCUIT FOR TURNOUT
FIGURE 2C**



**CROSSOVER
FIGURE 2D**



**DOUBLE SLIP CROSSING
FIGURE 2E**



**MOVABLE POINT CROSSING
FIGURE 2F**

NOTES:-

1. FOR GENERAL NOTES AND DETAIL REFERENCES SEE SHEET NO. 1.
 ○ = SEE SHEET NO. 1, NOTES 6 & 7.
 * = SEE SHEET NO. 1, NOTES 6 & 8.
2. FROGS SHALL BE BONDED IN ACCORDANCE WITH PLAN S-182, SH. 2, FIG. 1.
3. SWITCH POINTS SHALL BE BONDED IN ACCORDANCE WITH PLAN S-182, SH. 2, FIG. J USING J(R) RAIL BOND LOCATION.

INTERLOCKED SWITCHES

STEAM ROAD
ELECTRIFIED TERRITORY
NON-CAB SIGNAL TERRITORY
OR WHERE
NO CODE OR CAB SIGNAL
PROTECTION IS REQUIRED
OVER SWITCHES IN CAB
SIGNAL TERRITORY

SUPERSEDES S-803, SH. 2, DATED 5-13-27.

SHEET 2 OF 5

S-803



**THE PENNSYLVANIA RAILROAD
STANDARD
BONDING AND INSULATION OF SWITCHES**


OFFICE OF CHIEF ENGINEER,
PHILA., PA., DEC. 29, 1948.

APPROVED:

H. Griffith
ASST. CHIEF ENGINEER, T. C. S.


APPROVED:

J. H. Hensitt
CHIEF ENGINEER




TURNOUT - MEDIUM SPEED FACING
WITH INTERVENING TRACK CIRCUIT BETWEEN
TURNOUT AND REVERSE SIGNAL ON EITHER TRACK.

FIGURE 3A



TURNOUT - MEDIUM SPEED FACING
WITH NO INTERVENING TRACK CIRCUIT BETWEEN TURNOUT AND REVERSE SIGNAL.
TURNOUT - MAIN TRACK AND SIDE TRACK
FOR OVERRUN PROTECTION WHERE DERAIL IS NOT PROVIDED ON SIDE TRACK. (SEE PLAN S-881.)


FIGURE 3B



TURNOUT - MEDIUM SPEED TRAILING
INTERVENING TRACK CIRCUIT BETWEEN SIGNAL
AND TURNOUT SHALL BE PROVIDED ON EITHER TRACK
FOR OVERRUN PROTECTION. (SEE PLAN S-881.)

STEAM ROAD ONLY


FIGURE 3C



TURNOUT - MEDIUM SPEED TRAILING
INTERVENING TRACK CIRCUIT BETWEEN SIGNAL
AND TURNOUT SHALL BE PROVIDED ON EITHER TRACK
FOR OVERRUN PROTECTION. (SEE PLAN S-881.)

ELECTRIFIED TERRITORY ONLY


FIGURE 3D



CROSSOVER - MEDIUM SPEED IN ONE DIRECTION
WITH NO INTERVENING TRACK CIRCUIT BETWEEN HOME SIGNAL
AND CROSSOVER ON NO. 2 TRACK.

STEAM ROAD ONLY


FIGURE 3E



CROSSOVER - MEDIUM SPEED IN ONE DIRECTION

STEAM ROAD - EXCEPT AS SPECIFIED IN FIG. 3E
ELECTRIFIED TERRITORY

FIGURE 3F



CROSSOVER - MEDIUM SPEED IN BOTH DIRECTIONS

FIGURE 3G

NOTES:-

1. FOR GENERAL NOTES AND DETAIL REFERENCES SEE SHEET NO. 1.
⊙ = SEE SHEET NO. 1, NOTES 6 & 7.
* = SEE SHEET NO. 1, NOTES 6 & 8.
2. BONDING AND INSULATION OF TURNOUTS AND CROSSOVERS OVER WHICH RESTRICTING CAB SIGNAL INDICATIONS ONLY ARE DISPLAYED SHALL BE IN ACCORDANCE WITH SHEET NO. 2, EXCEPT AS SPECIFIED IN FIG. 3B.
3. FROGS SHALL BE BONDED IN ACCORDANCE WITH PLAN S-182, SH. 2, FIG. I.
4. SWITCH POINTS SHALL BE BONDED IN ACCORDANCE WITH PLAN S-182, SH. 2, FIG. J, USING J(R) RAIL BAND LOCATION EXCEPT WHERE J(B) IS SPECIFIED BY NOTE.
5. BANDS MARKED ⊙ SHALL BE LOCATED INSIDE AND ADJACENT TO RAIL AS SHOWN.
6. → = DIRECTION OF TRAFFIC FOR WHICH CODE IS GIVEN.
7. ∇ = HEEL OF SWITCH.

REVISIONS

INTERLOCKED SWITCHES

STEAM ROAD
ELECTRIFIED TERRITORY
CAB SIGNAL TERRITORY

SUPERSEDES S-803, SH. 6, DATED 5-15-36
AND SH. 7, DATED 1-11-29.

SHEET 3 OF 5

S-803



THE PENNSYLVANIA RAILROAD
STANDARD
BONDING AND INSULATION OF SWITCHES


OFFICE OF CHIEF ENGINEER,
PHILA., PA., DEC. 29, 1948.

APPROVED:


W. Griffith
ASST. CHIEF ENGINEER, T-C-S.

APPROVED:


W. H. Smith
CHIEF ENGINEER




TURNOUT-RIGHT HAND
FIGURE 4A




TURNOUT-LEFT HAND
FIGURE 4B




CROSSOVER-RIGHT HAND
FIGURE 4C




CROSSOVER-LEFT HAND
FIGURE 4D




CROSSOVER - RIGHT HAND
BETWEEN MAIN TRACK AND SIDE TRACK
(SEE FIGURE 4H)
FIGURE 4E



CROSSOVER - LEFT HAND
BETWEEN MAIN TRACK AND SIDE TRACK
(SEE FIGURE 4H)
FIGURE 4F




MIDDLE SIDING
FIGURE 4G



CROSSOVER
FOULING CIRCUIT TO BE PROVIDED BETWEEN MAIN TRACK AND SIDE TRACK WHERE DISTANCE BETWEEN FROGS IS EXCESSIVE. SHUNT CIRCUITS AS SHOWN IN FIGURES 4E, 4F, 5D OR 5H SHALL BE PROVIDED AS CONDITIONS REQUIRE.
FIGURE 4H

NOTES:-

- FOR GENERAL NOTES AND DETAIL REFERENCES SEE SHEET NO. 1.
* = SEE SHEET NO. 1, NOTES 6 & 7.
- FROGS SHALL BE BONDED IN ACCORDANCE WITH PLAN S-182, SH 1, FIG. D.
- SWITCH POINTS SHALL BE BONDED IN ACCORDANCE WITH PLAN S-182, SH 1, FIG. E.
- ARRANGEMENT FOR LOCKING OF TURNOUTS AND CROSSOVERS SHALL BE IN ACCORDANCE WITH STD. PLAN BASIC NOS. S-228, S-229, S-232 & S-233 AS INDICATED.
- INSULATING JOINTS MARKED * IN CENTER OF CROSSOVER BETWEEN MAIN TRACKS, FIGS. 4C & 4D, SHALL BE INSTALLED IN ELECTRIFIED TERRITORY ONLY. FOULING WIRES SHALL NOT BE USED.
- IN A.C. AND D.C. ELECTRIFIED TERRITORY POWER BONDING SHALL BE IN ACCORDANCE WITH REFERENCES SHOWN IN TABLE ON SHEET NO. 1; T20 HEAVY DUTY CIRCUIT CONTROLLERS SHALL BE PROVIDED, AND SHUNT CIRCUITS ARRANGED AS FOLLOWS:-



REVISIONS

NON-INTERLOCKED SWITCHES

NON-CAB SIGNAL TERRITORY
STEAM ROAD
FOR A.C. AND D.C. ELECTRIFIED
TERRITORY. (SEE NOTE 6)

SHEET 4 OF 5



S-803

THE PENNSYLVANIA RAILROAD
STANDARD
BONDING AND INSULATION OF SWITCHES











OFFICE OF CHIEF ENGINEER,
PHILA., PA., DEC. 29, 1948.

APPROVED:


ASST. CHIEF ENGINEER, T.C.S.

APPROVED:

CHIEF ENGINEER



- NOTES:-**
- FOR GENERAL NOTES AND DETAIL REFERENCES SEE SHEET NO. 1.
* = SEE SHEET NO. 1, NOTES 6 & 7.
 - FROGS SHALL BE BONDED IN ACCORDANCE WITH PLAN S-182, SH. 1, FIG. D.
 - SWITCH POINTS SHALL BE BONDED IN ACCORDANCE WITH PLAN S-182, SH. 1, FIG. E.
 - ARRANGEMENT FOR LOCKING OF TURNOUTS AND CROSSOVERS SHALL BE IN ACCORDANCE WITH STD. PLAN BASIC NOS. S-228, S-229, S-232 & S-233 AS INDICATED.
 - INSULATING JOINTS MARKED * IN CENTER OF CROSSOVER BETWEEN MAIN TRACKS, FIGS. 5A, 5B, 5C, 5E, 5F & 5G, SHALL BE INSTALLED IN ELECTRIFIED TERRITORY ONLY. FOULING WIRES SHALL NOT BE USED.
 - IN A.C. ELECTRIFIED TERRITORY POWER BONDING SHALL BE IN ACCORDANCE WITH REFERENCES SHOWN IN TABLE ON SHEET NO. 1; HEAVY DUTY CIRCUIT CONTROLLERS SHALL BE PROVIDED, AND SHUNT CIRCUITS ARRANGED AS FOLLOWS:



7. IN D.C. ELECTRIFIED TERRITORY POWER BONDING SHALL BE IN ACCORDANCE WITH REFERENCES SHOWN IN TABLE ON SH. 1; HEAVY DUTY CIRCUIT CONTROLLERS SHALL BE PROVIDED AND SHUNT CIRCUITS ARRANGED SIMILAR TO DETAILS (A), (C) & (D) IN NOTE 6; EXCEPT FOR FIGS. 5B, 5C, 5F & 5G WHERE D.C. TYPE HEAVY DUTY CIRCUIT CONTROLLERS SO CONNECTED TO OPERATE WITH MECHANICAL LOCKING OF T20 MECHANISMS, FOR CAB SIGNAL SHUNT, WITH SHUNT CIRCUITS ARRANGED SIMILAR TO DETAIL (B) IN NOTE 6, SHALL BE PROVIDED. MECHANICAL STICK CONTACTS IN T20 MECHANISM TO BE USED AS FOLLOWS FOR POINT DETECTOR PROTECTION:

NON-INTERLOCKED SWITCHES

CAB SIGNAL TERRITORY
STEAM ROAD
FOR A.C. ELECTRIFIED TERRITORY
(SEE NOTE 6)
FOR D.C. ELECTRIFIED TERRITORY
(SEE NOTE 7)

SHEET 5 OF 5

SUPERSEDES S-803, SH. 5, DATED 5-13-27

S-803











THE PENNSYLVANIA RAILROAD STANDARD BONDING AND INSULATION OF SWITCHES

OFFICE OF CHIEF ENGINEER,
PHILA., PA., DEC. 29, 1948.

APPROVED: *W. C. Griffith*
ASST. CHIEF ENGINEER, T.-C.-5.





APPROVED:

W. C. Griffith
CHIEF ENGINEER




NOTES:-

1. FOR GENERAL NOTES AND DETAIL REFERENCES SEE SHEET NO. 1.
* = SEE SHEET NO. 1, NOTES 6 & 7.
2. FROGS SHALL BE BONDED IN ACCORDANCE WITH PLAN S-182, SH. 1, FIG. D.
3. SWITCH POINTS SHALL BE BONDED IN ACCORDANCE WITH PLAN S-182, SH. 1, FIG. E.
4. ARRANGEMENT FOR LOCKING OF TURNOUTS AND CROSSOVERS SHALL BE IN ACCORDANCE WITH STD. PLAN BASIC NOS. S-228, S-229, S-232 & S-233 AS INDICATED.
5. INSULATING JOINTS MARKED * IN CENTER OF CROSSOVER BETWEEN MAIN TRACKS, FIGS. 5A, 5B, 5C, 5E, 5F & 5G, SHALL BE INSTALLED IN ELECTRIFIED TERRITORY ONLY. FOULING WIRES SHALL NOT BE USED.
6. IN A.C. ELECTRIFIED TERRITORY POWER BONDING SHALL BE IN ACCORDANCE WITH REFERENCES SHOWN IN TABLE ON SHEET NO. 1; HEAVY DUTY CIRCUIT CONTROLLERS SHALL BE PROVIDED, AND SHUNT CIRCUITS ARRANGED AS FOLLOWS:



7. IN D.C. ELECTRIFIED TERRITORY POWER BONDING SHALL BE IN ACCORDANCE WITH REFERENCES SHOWN IN TABLE ON SH. 1; HEAVY DUTY CIRCUIT CONTROLLERS SHALL BE PROVIDED AND SHUNT CIRCUITS ARRANGED SIMILAR TO DETAILS (A), (C) & (D) IN NOTE 6; EXCEPT FOR FIGS. 5B, 5C, 5E, 5F & 5G WHERE D.C. TYPE HEAVY DUTY CONTROLLERS SO CONNECTED TO OPERATE WITH MECHANICAL LOCKING OF T20 MECHANISMS. FOR CAB SIGNAL SHUNT, WITH SHUNT CIRCUITS ARRANGED SIMILAR TO DETAIL (B) IN NOTE 6, SHALL BE PROVIDED. MECHANICAL STICK CONTACTS IN T20 MECHANISM TO BE USED AS FOLLOWS FOR POINT DETECTOR PROTECTION:



REVISIONS

NON-INTERLOCKED SWITCHES

CAB SIGNAL TERRITORY
STEAM ROAD
FOR A.C. ELECTRIFIED TERRITORY
(SEE NOTE 6)
FOR D.C. ELECTRIFIED TERRITORY
(SEE NOTE 7)

SHEET 5 OF 5

SUPERSEDED S-803, SH. 5, DATED 5-13-27.

S-803




THE PENNSYLVANIA RAILROAD
STANDARD
BONDING AND INSULATION OF SWITCHES

OFFICE OF CHIEF ENGINEER,
PHILA., PA., DEC. 29, 1948.


APPROVED: *H. C. Gifford*
ASST. CHIEF ENGINEER, T.C.S.

APPROVED:

R. C. Smith
CHIEF ENGINEER




ENERGY FOR POWER-OFF RELAY IS SUPPLIED FROM SECONDARY OF LIGHTING TRANS, THIS BEING THE PREFERABLE ARRANGEMENT, RELAYS WOUND FOR 110V MAY BE USED, ENERGY BEING SUPPLIED FROM THE 110V. BUS.



ARRANGEMENT SHALL BE USED WHERE NOT MORE THAN 10 AMPERES ARE REQUIRED.

FIG. 1



ARRANGEMENT SHALL BE USED WHERE MORE THAN 10 AMPERES ARE REQUIRED, A SEPARATE POWER-OFF RELAY AND LIGHTING BUS BEING PROVIDED FOR EACH 10 AMPERES TO BE SUPPLIED.

FIG. 2

NOTE :-

BATTERY OF SUFFICIENT CAPACITY FOR EIGHT HOURS CONTINUOUS SERVICE SHALL BE PROVIDED. EACH SIGNAL MAY BE CONSIDERED AS CONSUMING 2 1/2 AMPERES IN DETERMINING CAPACITY OF BATTERY.

REVISIONS.

SUPERSEDES PLAN S-805 DATED 10-18-21.

S-806

1 SHEET





THE PENNSYLVANIA RAILROAD
TYPICAL
ARRANGEMENT FOR LIGHTING POSITION LIGHT
SIGNALS WHEN NORMAL POWER FAILS

OFFICE OF CHIEF SIGNAL ENGINEER
PHILA., PA., MAY 16, 1922.



Approved *Arthur*
Chief Signal Engineer

NOT TO SCALE
Approved *William*
Chief Engineer





STYLE TV-30 TRACK RELAY (NON-FREQUENCY). U.S. & S.CO.

FOR USE ON STEAM ROAD OR ELECTRIFIED TERRITORY -- D.C. PROPULSION. SERVICE INTENDED SHALL BE SPECIFIED IN ORDERING.
 ANY COMBINATION OF CONTACTS, NOT EXCEEDING FIFTEEN (15) FRONTS AND ONE (1) BACK FOR A TWO POSITION RELAY AND SEVEN (7) NORMAL, SEVEN (7) REVERSE AND ONE (1) DE-ENERGIZED CONTACT FOR A THREE POSITION RELAY, MAY BE PROCURED.
 WHERE LOOP CIRCUITS ARE USED, TERMINAL POST 29 IS NOT AVAILABLE FOR A CONTACT SPACE, BEING USED FOR THE LOOP CONNECTION TO THE MID TAP OF THE TRACK WINDING.




RESONANT CENTRIFUGAL FREQUENCY. U.S. & S.CO.
ELECTRICALLY BRAKED.

FOR USE ON TRACK CIRCUITS IN ELECTRIFIED TERRITORY, A.C. PROPULSION.
 ANY COMBINATION OF CONTACTS NOT EXCEEDING A TOTAL OF TEN (10), MAY BE PROCURED.



VANE FREQUENCY. U.S. & S.CO.

FOR USE ON TRACK CIRCUITS WITHIN INTERLOCKING LIMITS IN ELECTRIFIED TERRITORY, A.C. PROPULSION.
 MAXIMUM NUMBER OF CONTACTS: - FOUR (4) FRONT AND TWO (2) BACK, NON-INDEPENDENT.



STYLE SLV13 - VANE (NON-FREQUENCY). U.S. & S.CO.

MAY BE WOUND AS A TRACK (FOR USE WITHIN INTERLOCKING LIMITS ON STEAM ROAD OR ELECTRIFIED TERRITORY -- D.C. PROPULSION) OR LINE RELAY. SERVICE INTENDED SHALL BE SPECIFIED IN ORDERING.
 WHEN WOUND AS A LINE RELAY IT SHALL BE USED ONLY WHERE ITS CONTROLLING CIRCUIT IS ENTIRELY CONFINED TO THE CASE OR BUILDING WHERE THE RELAY IS LOCATED.
 ANY COMBINATION OF CONTACTS, NOT EXCEEDING A TOTAL OF EIGHT (8), MAY BE PROCURED.

REVISIONS

6-7-26. STYLE TV30 RELAY ADDED AND CONTACT TERMINAL POSTS RENUMBERED.
 APPROVED: *CH*
 REDRAWN FROM SHEET 2 OF PLAN S-806, DATED 3-9-23.

SHEET 1 OF 2

S-806

**THE PENNSYLVANIA RAILROAD
CONTACT ARRANGEMENT
OF ALTERNATING CURRENT RELAYS**



OFFICE OF CHIEF SIGNAL ENGINEER
 PHILA., PA., JUNE 7, 1925

NOT TO SCALE



Approved: *CH*
 Chief Signal Engineer

Approved: *J. D. Murray*
 Asst. Chief Engineer


TWO POSITION.



THREE POSITION.





TWO POSITION



MODEL 15 VANE LINE RELAY. U.S. & S. CO.

ANY COMBINATION OF CONTACTS, NOT EXCEEDING A TOTAL OF TWELVE (12), MAY BE PROCURED.

TWO POSITION.



STYLE 5V30 (SLOW ACTING) VANE. U.S. & S. CO.

ANY COMBINATION OF CONTACTS, NOT EXCEEDING A TOTAL OF TWELVE (12), OF WHICH NOT MORE THAN TEN (10) CAN BE FRONT, MAY BE PROCURED.

NOTE :-
STYLE T2LV14 RELAYS MAY BE USED UNTIL THE STOCK OF THIS TYPE IS EXHAUSTED. WHEN NECESSARY TO ORDER NEW "LIGHT-OUT" RELAYS, STANDARD MODEL 15 VANE, WITH 110V. LOCAL, SHALL BE ORDERED.

REVISIONS.

6-7-26. MODEL 15 VANE
FORMERLY ALSO USED AS A
TRACK & "30" RELAY, MODEL
16 INDUCTION TYPE ELIMINATED
AND CONTACT TERMINAL
POSTS RENUMBERED.
APPROVED: *[Signature]*
REDRAWN FROM SHTS. 18-3 OF
PLAN S-806, DATED 3-9-23.

SHEET 2 OF 2

S-806

THE PENNSYLVANIA RAILROAD
CONTACT ARRANGEMENT
OF ALTERNATING CURRENT RELAYS

OFFICE OF CHIEF SIGNAL ENGINEER
PHILA., PA., JUNE 7, 1926


Approved

Chief Signal Engineer

NOT TO SCALE

Approved

Chief Engineer



NOTE:-

1. BONDS BETWEEN PIPES, RAILS, PIPING SYSTEM AND RAILS, AND PIPING SYSTEM AND GROUND SHALL HAVE A COMBINED CONDUCTIVITY OF NOT LESS THAN A NO. 0 COPPER CABLE. THREE COPPER COVERED CABLES OR TWO COPPER CABLES (7 STRAND NO. 10 RWG, PLAN S-182) ARE EQUIVALENT TO ONE NO. 0 COPPER CABLE IN CONDUCTIVITY.
2. GROUNDING IN GENERAL SHALL BE IN ACCORDANCE WITH B.S.T. SPEC. 2001, USING GROUND ROD PER STORES CATALOGUE REF. 28-5228 AND CLAMP 28-4346.
3. THE DISCONNECTING SWITCH ARRANGEMENT REQUIRED MAY BE OBTAINED BY USING TWO DISCONNECTING, S.P.S.T., 15KV, 600 OR 1200 AMP, MANUALLY REMOTE CONTROLLED SWITCHES, ITEM 69 IN SPEC. P-230-7, EXCEPT BLADE IS TO BE GROUNDED WHEN IN OPEN POSITION; THE INSULATORS TO BE EQUAL TO LOCKE #23105. SWITCHES ARE TO BE MECHANICALLY CONNECTED TO OPERATE AS A DOUBLE-POLE UNIT, AND THE GROUNDING BLADE SOCKETS ARE TO BE ELECTRICALLY CONNECTED. WHERE SHORT CIRCUIT CURRENT FROM TROLLEYS WILL NOT EXCEED 25,000 AMPERES, A SWITCH OF 600 AMPERE RATING SHALL BE USED. WHERE SHORT CIRCUIT CURRENT FROM TROLLEYS IS ABOVE 25,000 AMPERES AND NOT EXCEEDING 50,000 AMPERES, A SWITCH OF 1200 AMPERE RATING SHALL BE USED.
4. THIS PLAN IS FOR USE IN CONNECTION WITH CURRENT ISSUE OF LETTER OF GENERAL PRACTICE NO. 140 FOR THE PREVENTION OF ELECTRIC SPARKS THAT MAY CAUSE FIRE DURING THE TRANSFER OF INFLAMMABLE LIQUIDS TO OR FROM RAIL EQUIPMENT.
5. IN A.C. ELECTRIFIED TERRITORY APPROVAL OF THE INDIVIDUAL CASE BY THE CHIEF ENGINEER AND CHIEF OF MOTIVE POWER SHALL BE OBTAINED PRIOR TO PLACING THE FACILITIES IN SERVICE.

REVISIONS:

STEAM ROAD TERRITORY
(OMIT DISCONNECT SWITCH, ITS CONNECTIONS, AND THE REQUIREMENTS OF NOTE 3)

A.C. ELECTRIC TRACTION TERRITORY

SHEET 1 OF 2



5-80

THE PENNSYLVANIA RAILROAD
TYPICAL
PROTECTION OF OIL SIDINGS FROM
ELECTRIC SPARKS

OFFICE OF CHIEF ENGINEER,
PHILADELPHIA, PA., JUNE 22, 1945.

APPROVED:


APPROVED:

NOT TO

APPROVED:

W. J. Starnes
ASST. CHIEF ENGINEER T.C.S.

J. Starnes
ELECTRICAL ENGINEER



NOTE:-

1. BONDS BETWEEN PIPES, RAILS, PIPING SYSTEM & RAILS AND PIPING SYSTEM & GROUND SHALL HAVE A COMBINED CONDUCTIVITY OF NOT LESS THAN A NO. 0 COPPER CABLE. THREE COPPER COVERED CABLES OR TWO COPPER CABLES (7 STRAND - NO. 10 AWG, PLAN S-182) ARE EQUIVALENT TO ONE NO. 0 COPPER CABLE IN CONDUCTIVITY.

2. GROUNDING IN GENERAL SHALL BE IN ACCORDANCE WITH G.S.T. SPEC. 2001, USING GROUND ROD PER STORES CATALOGUE REF. 55-5224 AND CLAMP 55-5346.

3. DISCONNECTING SWITCH SHALL BE IN ACCORDANCE WITH THE RAILWAY AND INDUSTRIAL ENGINEERING CO.'S. TYPE DTAU-AU SWITCH, DRAWING NO. 44246-F, OR EQUIVALENT.

WHERE SHORT CIRCUIT CURRENT FROM TROLLEYS WILL NOT EXCEED 25,000 AMPERES, A SWITCH OF 600 AMPERE RATING SHALL BE USED.

WHERE SHORT CIRCUIT CURRENT FROM TROLLEYS IS ABOVE 25,000 AMPERES AND NOT EXCEEDING 50,000 AMPERES A SWITCH OF 1200 AMPERE RATING SHALL BE USED.

4. THIS PLAN IS FOR USE IN CONNECTION WITH CURRENT ISSUE OF C.E. 10 "PRACTICE FOR THE PROTECTION OF TRACKS USED IN THE LOADING OR UNLOADING OF INFLAMMABLE LIQUIDS FROM THE DANGER OF FIRE CAUSED BY ELECTRIC SPARKS."

5. IN CASES WHERE IT IS UNDESIRABLE TO DEENERGIZE THE TROLLEY THE MATTER MUST BE REFERRED TO THE CHIEF ENGINEER AND CHIEF OF MOTIVE POWER.

REVISIONS.

7-15-35. Notes referring to wires connecting to disconnect switch changed. Note 5 added.

Approved: *Arthur H. H. H.* Chief Sig. Eng.

Approved: *Arthur H. H. H.* Elec. Eng.

A.C. ELECTRIC TRACTION TERRITORY

Sheet 1 of 2.

S-807



THE PENNSYLVANIA RAILROAD
TYPICAL
PROTECTION OF OIL SIDINGS FROM
ELECTRIC SPARKS

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., APRIL 11, 1935.


APPROVED:-

APPROVED:-

APPROVED:-

CHIEF SIGNAL ENGINEER. ELECTRICAL ENGINEER. CHIEF ENGINEER.

NOT TO SCALE.



NOTE:

1. BONDS BETWEEN PIPES, RAILS, PIPING SYSTEM AND PIPING SYSTEM AND GROUND SHALL HAVE A COMBINED CONDUCTIVITY OF NOT LESS THAN 250,000 C.M. COPPER CABLE.
2. GROUNDING IN GENERAL SHALL BE IN ACCORDANCE WITH U.S.T. SPEC. 2001, USING GROUND ROD PER STORES CATALOGUE REF. 55-5224 AND CLAMP 55-4346.
3. SPECIAL D.P.D.T. SWITCH - STORES CATALOGUE REF. 25-E-783049-L.
4. FOR DETAILS OF GROUNDING RESISTANCE AND MOUNTING, SEE CHIEF OF MOTIVE POWER DRAWING E-404775.
5. ELECTRICAL TESTS SHOULD BE MADE AT TIME OF BONDING TO INSURE THAT NO EXCESSIVE CURRENTS NOR OTHER UNDESIRABLE CONDITIONS DEVELOP.
6. THIS PLAN IS FOR USE IN CONNECTION WITH CURRENT ISSUE OF C.E. 10, "PRACTICE FOR THE PROTECTION OF TRACKS USED IN THE LOADING OR UNLOADING OF INFLAMMABLE LIQUIDS FROM DANGER OF FIRE CAUSED BY ELECTRIC SPARKS."

REVISIONS

DC. ELECTRIC TRACTION TERRITORY.

Sheet 2 of 2

5-807



THE PENNSYLVANIA RAILROAD
TYPICAL
PROTECTION OF OIL SIDINGS FROM
ELECTRIC SPARKS

Office of Chief Signal Engineer,
Phila., Pa., July 13, 1935.

Approved:

Arthur
Chief Signal Engineer

Approved:

H.C. Griffith
Electrical Engineer

Not to scale.
Approved:

W.H. White
Chief Engineer




FIG. 1.




FIG. 3.




FIG. 5.

NOTE:-
LETTERS 'A', 'B', 'C', ETC., INDICATE INDIVIDUAL TRACK CIRCUITS. DOTTED LINES INDICATE TRACK CIRCUIT CONNECTIONS WHICH SHALL BE IN ACCORDANCE WITH PENNA. R.R. SYSTEM STANDARD PLAN BASIC NO. S-182.
—*— INSULATING JOINTS.
INSULATING JOINTS MARKED * SHALL NOT BE LOCATED ON THE ARMS OF THE CROSSING FROGS, EXCEPT BY SPECIAL PERMISSION, NOR SHALL THEY BE LOCATED MORE THAN 33 FEET FROM THE ENDS OF THE ARMS.




FIG. 2.




FIG. 4.

ARRANGEMENTS SHOWN SHALL BE USED WHEN ANGLE OF CROSSING IS FROM 9°30' UP TO AND NOT INCLUDING 30°.




FIG. 6.

REVISIONS.

SHEET 1 OF 3

S-808

PENNSYLVANIA RAILROAD SYSTEM
TYPICAL TRACK CIRCUIT ARRANGEMENT
FOR CROSSING FROGS

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., SEPT. 4, 1924.

Approved: *Arthur J. ...*
Chief Signal Engineer

Approved: *...*
Engineer of Standards

NOT TO SCALE

MEMORANDA TO ACCOMPANY P.R.R. STANDARD MATERIAL PLANS

S-410-D, S-465-B, S-466-A, S-467-A, S-486-D,
S-487-D, S-497-D.

- S-410-D. Plan redrawn and revised. Dwarf signal changed to show double lamps, new optical arrangement, and new design of case. Pedestal Signal 4102 added.
- S-465-B. Plan redrawn and revised. Signs 4651 and 4652 changed to agree with A. R. A. Standard. Details of Adapter Clamp and Hook Bolt removed. New marker sign 4654 added.
- S-466-A. New plan showing details of Signs shown on S-465-B.
- S-467-A. New plan showing specifications for signs and reflector buttons shown on S-465-B.
- S-486-D. Revised. Frosting removed and gasket addres to Lens 4864. Cover Glass 4867 removed.
- S-487-D. Revised. Roundel 4877 added.
- S-497-D. Fibre duct shifted and wood trunking removed on 4972. Wood trunking also removed on 4974. No. 4975 is new foundation for pedestal signal; the former 4975 has been removed from plan, as 4974 is sufficient foundation for both high and low type position light signals. No. 4973 redesigned for the new shape dwarf signal.


A. H. RUDD
Chief Signal Engineer

MEMORANDA TO ACCOMPANY P.R.R. STANDARD
MATERIAL PLANS S-184-E & S-513-E


S-184-E Plan Revised. Parts 1844 & 1846 redesigned and material formerly brass. Parts 1845 & 1847 formerly brass only. Specifications for Bronze added. Order No. 18412 added for Parkway Outlet.

S-513-E Plan Revised. Bus strip 51312 added. Dimensions of 51311 changed.


A. H. RUDD
Chief Signal Engineer



Semi-Automatic Home
Signals on both roads.
FIG. 7.



Semi-Automatic Home
Signals on both roads.
FIG. 8.



Non-semiautomatic Signals on
Foreign Road. Where derails are
installed circuits shall be
arranged as shown, and locking
similar to that shown in Fig. 3, sh.1.
should be provided.
FIG. 9.




FIG. 10.




FIG. 11.




FIG. 12.

FOR GENERAL NOTES SEE SHEET NO.1.

REVISIONS.

SUPERSEDES PLAN S-808
DATED 2-26-21 FOR
ANGLES ABOVE 43°30'

S-808







SHEET 2 OF 3

PENNSYLVANIA RAILROAD SYSTEM
TYPICAL TRACK CIRCUIT ARRANGEMENT
FOR CROSSING FROGS

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., SEPT. 4, 1904.

Approved: *Arthur H. ...* Chief Signal Engineer
Approved: *W. B. ...* Engineer of Standards
Approved: *...* Chief Engineer

NOT TO SCALE



FOR GENERAL NOTES SEE
SHEET NO. 1

ARRANGEMENTS SHOWN
SHALL BE USED WHEN ANGLE
OF CROSSING IS FROM
60° TO 90°

REVISIONS.

SUPERSEDES PLAN S-800
DATED 2-26-21 FOR
ANGLES SHOWN.

SUPERSEDES PLAN S-808
DATED 2-26-21 FOR
ANGLES SHOWN.

SHEET 3 OF 5

S-808



PENNSYLVANIA RAILROAD SYSTEM TYPICAL TRACK CIRCUIT ARRANGEMENT FOR CROSSING FROGS

OFFICE OF CHIEF SIGNAL ENGINEER
PHILA., PA., SEPT. 4, 1924.

NOT TO SCALE

Approved Approve

Approve

Approve

A. H. Reed
Chief Signal Engineer

H. G. Lashin
Engineer of Standard


Chief Engineer

FOR NEUTRAL OR TWO POSITION TRACK RELAYS.

THE POLARITY OF ADJACENT TRACK SECTIONS SHALL BE OPPOSITE OR STAGGERED

FOR POLARIZED OR THREE POSITION TRACK RELAYS.

AT INTERLOCKINGS:-

THE POLARITY OF ADJACENT TRACK SECTIONS SHALL BE OPPOSITE OR STAGGERED EXCEPT AS FOLLOWS:

AT HOME SIGNALS WHEN THE POLE-CHANGER AT THE HOME SIGNAL LOCATION IS IN ITS NORMAL POSITION. IN CASE AN UNUSUAL ARRANGEMENT OF INSULATING JOINTS WOULD RESULT WITHIN THE INTERLOCKING IN ORDER TO SECURE LIKE POLARITIES AT THE HOME SIGNAL LOCATION, THE POLARITIES SHALL BE STAGGERED AND THE STANDARD ARRANGEMENT OF JOINTS PROVIDED WITHIN THE INTERLOCKING. SEE FIG. 1.

WHERE A SIGNAL LOCATED AT THE LEAVING END OF AN INTERLOCKING, IS DISTANT TO ANOTHER HOME SIGNAL, LIKE POLARITIES SHALL BE PROVIDED WHEN THE SIGNAL IS IN ITS NORMAL POSITION. SEE FIG. 2.

OUTSIDE OF INTERLOCKINGS:-

THE POLARITIES OF ADJACENT TRACK CIRCUITS SHALL BE OPPOSITE OR STAGGERED WHEN THE POLARITY OF THE TRACK SECTION BEYOND IS SUCH THAT THE RELAY FOR THAT SECTION IS IN ITS NORMAL OR CLEAR POSITION. SEE FIG. 3.

THE POLARITIES OF ADJACENT TRACK CIRCUITS AT CUT-SECTION LOCATION NEED NOT BE STAGGERED WHERE THE FEED FOR THE FIRST SECTION IS CONTROLLED OVER THE TRACK RELAY FOR THE SECTION BEYOND.

IN GENERAL, THE POLARITY IN POLARIZED TERRITORY SHOULD ALWAYS BE SO ARRANGED THAT, SHOULD THE INSULATING JOINTS BREAK DOWN WITH A TRAIN OR A BROKEN RAIL IN THE SECTION AHEAD THE POLARITY OF THE SECTION APPROACHING A SIGNAL WILL BE SUCH AS TO HOLD OR SHIFT THE CONTACTS OF THE RELAY FOR THE SECTION BEYOND TO THE REVERSE (APPROACH) POSITION.




FIGURE 1




FIGURE 2




FIGURE 3

REVISIONS

SUPERSEDES PLAN S-809,
DATED 12-13-20.

1 SHEET

S-809

THE PENNSYLVANIA RAILROAD
STANDARD

TRACK CIRCUIT POLARITY

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., APRIL 30, 1929.

NOT TO SCALE


Approved

Art. L. ...
Chief Signal Engineer

Approved

W. ...
Chief Engineer

9714



REVISIONS.
3-22-37. ADDITIONAL CENTER SECTIONALIZING SWITCH PROVIDED AND NOTE 4 ADDED.
APPROVED: <i>Arthur H. Hudd</i>
6-1-35. LINE TRANS. FIG. 1, FORMERLY LOCATED AT SIG. BRIDGES. FIG. 2 & NOTES 1 & 2 ADDED.
APPROVED: <i>Arthur H. Hudd</i>

1 SHEET


THE PENNSYLVANIA RAILROAD
TYPICAL
**110 VOLT A. C. POWER SUPPLY
FOR INTERLOCKINGS**

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., MAY 21, 1929.


Approved: *Arthur H. Hudd*
Chief Signal Engineer

NOT TO SCALE
Approved: *Arthur H. Hudd*
Chief Engineer


S-811




SLOW ACTING RELAY REPEATING 3 POSITION A.C. RELAY.




MODEL 13 SLOW-ACTING D.C. NEUTRAL RELAY.
500 OHMS, 4 FRONT-2 BACK CONTACTS-ROUND BASE.
FIG. 1.



MODEL 13 SLOW-ACTING D.C. NEUTRAL RELAY.
500 OHMS, 4 FRONT-4 BACK CONTACTS-SQUARE BASE.
FIG. 2.



SLOW ACTING RELAY REPEATING D.C. POLARIZED RELAY.



MODEL 13 SLOW-ACTING D.C. NEUTRAL RELAY
500 OHMS, 6 CONTACTS-SQUARE BASE.
FIG. 3

NOTE:-

1. RESISTANCE OF RESISTOR "X" SHALL BE DETERMINED BY CURVES, FIGURES 1, 2 & 3, THE RESISTOR SELECTED BEING OF SUCH VALUE THAT THE RETARDED PICK-UP FALLS ON THE CURVE BETWEEN 0.6 AND 1.4 SECONDS, AS INDICATED BY HEAVY LINE, ALLOWANCE BEING MADE FOR VOLTAGE VARIATION.
2. CIRCUITS SHALL BE ARRANGED AS SHOWN WHERE IT IS DESIRABLE TO RETARD THE PICK-UP OF THE RELAY.
3. WHERE A RETARDED PICK-UP IS NOT REQUIRED RELAY CONTACT "15A" AND RESISTOR "X" SHALL BE OMITTED.
4. RESISTOR TO BE MOUNTED ON STANDARD PORCELAIN TERMINAL BLOCK 5132, PLAN 5-513, AND SHALL HAVE THREE WATTS CONTINUOUS CAPACITY.

REVISIONS.

1 SHEET

S-812

THE PENNSYLVANIA RAILROAD
STANDARD
CONTROL CIRCUITS FOR
D. C. SLOW ACTING RELAYS

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., AUG. 4, 1929.

Approved


Chief Signal Engineer

Approved

NOT TO SCALE

Chief Engineer

J.P.H.



NOTE:-

G.E. CO.'S DISCHARGE RESISTOR NO. 91A12B39 (FOR STEAM
TERRITORY) SHALL BE USED.

SIMILAR ARRANGEMENT SHALL BE PROVIDED WHERE
A.C. TRACK CIRCUITS ARE USED.

REVISIONS

13 SHEET

S-8/3



THE PENNSYLVANIA RAILROAD
TYPICAL

LIGHTNING PROTECTION FOR SIGNAL CIRCUITS
IN STEAM TERRITORY

OFFICE OF CHIEF ENGINEER,
PHILA., PA., AUGUST 7, 1947.


APPROVED:

H. Griffith
ASST. CHIEF ENGINEER, T.C.S.

APPROVED:


H. Griffith
CHIEF ENGINEER.

NOT TO SCALE




FOR USE ON TRACK CIRCUITS BETWEEN 3000' & 6000'.

FIG. 1.




FOR USE ON TRACK CIRCUITS IN AUTOMATIC TERRITORY UP TO 3000'.

FIG. 2.




FOR USE ON INTERLOCKING TRACK CIRCUITS UP TO 2000' FOR USE ONLY WHEN SPEC. 1615 RELAYS ARE IN STOCK. WHEN NEW RELAYS MUST BE OBTAINED USE SPEC. 2197, FIG. 6.

FIG. 3.



FOR USE IN NEW YORK DIV. A.C.-D.C. PROPULSION TERRITORY WHERE LOW IMPEDANCE BONDS ARE USED ON SHORT INTERLOCKING TRACK CIRCUITS UP TO 500'.

FIG. 4.



FOR USE ON INTERLOCKING TRACK CIRCUITS UP TO 3500' FOR USE IN NEW YORK DIV. A.C.-D.C. PROPULSION TERRITORY ON TRACK CIRCUITS BETWEEN 500' & 3500'.

FIG. 5.





FIG. 6.



REVISIONS.	
1	MAY 18, 1950. NOTE AT RELAY END, FIG. 1 & 2, NOTE AT FEED END, FIG. 3, AND NOTE 1 CHANGED.
2	APPROVED: H. G. Salmonson
3	12-16-36. FUSES FORMERLY SHOWN 20 AMPS. NOTE IN FIG. 2 CHANGED, FIGS. 6 & 7 FORMERLY T-8, FIG. 8 BEING REMOVED.
4	APPROVED: A. H. Tied

NOTE:-

1. TRACK CIRCUIT POLARITIES ARE ARRANGED TO PROVIDE BROKEN DOWN INSULATING RAIL JOINT PROTECTION. TESTS SHALL BE MADE IN ACCORDANCE WITH PARAGRAPH 35, C.E. 232, TO INSURE THAT SUCH PROTECTION IS OBTAINED. WHERE RELAY INSTALLED IN ACCORDANCE WITH FIGURES 2 OR 3 FAILS TO COMPLY WITH THE TESTS, RELAY SPEC. 2197, FIG. 6, SHALL BE SUBSTITUTED TO OBTAIN COMPLIANCE.


2. UNLESS OTHERWISE SPECIFIED ARRANGEMENTS SHOWN ARE FOR A.C. PROPULSION TERRITORY ONLY.

1 SHEET

S-816

THE PENNSYLVANIA RAILROAD
STANDARD
APPLICATION OF CENTRIFUGAL TRACK RELAYS
ON DOUBLE RAIL TRACK CIRCUITS
OFFICE OF CHIEF SIGNAL ENGINEER.
PHILA., PA., OCT. 31, 1936.
APPROVED: [Signature]
CHIEF SIGNAL ENGINEER.

NOT TO SCALE
APPROVED: [Signature]
CHIEF ENGINEER.



RESISTANCE OF GROUND EQUALS AVERAGE READING OF VOLTMETER
DIVIDED BY AVERAGE READING OF AMMETER.

NOTE:- * CONNECTION TO RAIL MAY BE MADE BY MEANS OF A
CLAMP OR TO EXISTING FEED OR RELAY WIRES.

DO NOT USE EXCEPT WHEN RELAY IS PICKED UP AND
WHEN NO TRAIN IS APPROACHING SIGNAL. ALSO TRACK
CIRCUIT SHOULD BE AT LEAST 2000 FT. LONG TO INSURE
THAT RAIL BE OF LOW ENOUGH RESISTANCE TO BE SATISFACTORY.

REVISIONS

1 SHEET

S-817



THE PENNSYLVANIA RAILROAD

METHOD OF MEASURING RESISTANCE OF MADE GROUND

OFFICE OF ASST. CHIEF ENGINEER-SIGNALS
PHILA., PA., JULY 17, 1937

NOT TO SCALE

APPROVED






H.C. Brandon

ASST. CHIEF ENGINEER-SIGNALS

APPROVED

W. Duggan

CHIEF ENGINEER



LEGEND
 A = D. C. MILLI-AMMETER
 B = 1 DRY CELL (APPROX. $1\frac{1}{2}$ VOLTS)
 R = 4 TO 10 OHMS RESISTANCE (FOR LIMITING CURRENT FLOW IN CASE OF BROKEN DOWN INSULATION.)

NOTE:-

1. WHEN READINGS OBTAINED ARE .020 AMPERES OR HIGHER, INSULATION SHALL BE RENEWED, EXCEPT FOR INSULATING RAIL JOINTS.
2. ON INSULATING RAIL JOINTS, WHEN TOTAL READINGS, AS DETERMINED FROM NOTE 3, ARE .020 AMPERES OR HIGHER, THE INSULATING RAIL JOINT SHALL BE TAKEN APART AND RUST THOROUGHLY CLEANED WITH A WIRE BRUSH AND DEFECTIVE INSULATION AND INSULATING BUSHINGS RENEWED.
3. TO DETERMINE TOTAL READING ON INSULATING RAIL JOINT ADD THE HIGHER CURRENT READING OBTAINED FROM READING NO. 1 AND NO. 2 TO THE HIGHER CURRENT READING OBTAINED FROM READING NO. 3 AND NO. 4.
4. ON MECHANICALLY OPERATED SWITCHES - WHEN READINGS OBTAINED ARE .020 AMPERES OR HIGHER, PIPE LINE MUST BE DISCONNECTED FROM SWITCH AND FURTHER READINGS TAKEN.
5. FLEXIBLE METALLIC CONDUIT CONNECTED TO ANY GROUNDED APPARATUS, SUCH AS E.P. VALVES, SWITCH MECHANISMS ETC., SHALL BE FREE FROM METALLIC CONTACT WITH MECHANISM WHILE TEST IS BEING MADE.

REVISIONS

1 SHEET



S-818


THE PENNSYLVANIA RAILROAD

TRACK INSULATION TESTS









OFFICE OF ASSISTANT CHIEF ENGINEER-SIGNALS NOT TO SCALE
 PHILA., PA., JAN. 12, 1938.

Approved
N. L. Stanton
 Assistant Chief Engineer-Signals

Approved
W. D. Higgins
 Chief Engineer



INCLUDE ALL TRAP CIRCUITS ON OTHER ROAD AND TRACK CIRCUITS BACK TO HOLDING SIGNALS FOR CONFLICTING MOVEMENTS.



NOTE:-
 1. TRAP CIRCUITS SHALL BE PROVIDED WHERE LENGTH OF DEAD SECTION AT CROSSING EXCEEDS THIRTY FEET.
 2. STANDARD CIRCUIT CONTROLLER WITH LATCH (3SC) SHALL BE PROVIDED AND SEALED IN NORMAL POSITION OR A CLOCKWORK TIME RELEASE WITHOUT LATCH USED TO MANUALLY RESTORE STICK RELAYS 2RU AND 2LU. CIRCUIT CONTROLLER OR TIME RELEASE MUST NOT BE USED UNTIL OPERATOR HAS DETERMINED THAT CROSSING IS UNOCCUPIED.
 3. WHERE DERAILS ARE PROVIDED ARRANGE CIRCUITS FOR LEVER LOCK SIMILAR TO THOSE SHOWN FOR MASTER LEVER 3.
 4. WHERE ROUTE LOCKING IS REQUIRED CIRCUITS SHALL BE ARRANGED SO THAT ROUTE LOCKING IS EFFECTIVE WITH TRAIN ON "DEAD SECTION".

REVISIONS


S-819

1 SHEET




THE PENNSYLVANIA RAILROAD TYPICAL TRAP CIRCUITS


OFFICE OF CHIEF SIGNAL ENGINEER NOT TO SCALE
 PHILA., PA. MARCH 23, 1937
 Approved *A.H. Reed* Chief Signal Engineer
 Approved *W. Skjinn* Chief Engineer




ELECTRO-MECHANICAL (U.S. & S. CO.)
SEE PLAN S-821
FIG. 1




ELECTRO-PNEUMATIC MODEL 14 S & L MOVEMENT
WITH STYLE "C" VALVE
SEE PLAN S-822, SH. 2
FIG. 2




ELECTRO-PNEUMATIC MODEL 14 S & L MOVEMENT
WITH OLD STYLE VALVE
SEE PLAN S-822, SH. 3
FIG. 3



POLARIZED "SS" CONTROLS
SEE PLAN S-822, SHEETS 1, 4, 5 & 8.
" S-823, " 1 & 2.
FIG. 4



MECHANICAL
FIG. 5.



CONTROL CIRCUITS FOR
SWITCH LEVER REPEATING RELAYS
FIG. 6.

REVISIONS

1 SHEET

S-820




THE PENNSYLVANIA RAILROAD
TYPICAL
CIRCUITS FOR LEVER REPEATING RELAYS

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., MAY 19, 1933.


Approved *[Signature]*
Chief Signal Engineer

NOT TO SCALE

Approved *[Signature]*
Chief Engineer



TYPE "P" & "S-B" (U.S. & S. Co.)



MODEL "2B" (G.R.S. Co.)


NOTE:

THE "H" BATTERY MOST CONVENIENTLY LOCATED SHALL BE USED FOR EACH INDICATION CIRCUIT AND THE BATTERY USED SHALL BE INDICATED BY DETAIL CIRCUIT PLAN AT EACH

"OS" RELAY THIS:



* ON "S-B" LEVER, "A" & "R" CONTACTS SHALL BE DESIGNATED "NS" & "PS" AND SHALL BE SO ADJUSTED AS NOT TO BREAK WHILE THE LEVER IS MECHANICALLY LOCKED FORWARD OR REVERSED RESPECTIVELY BUT MUST BREAK BEFORE THE DETECTOR LOCKING "TOOTH" IS REACHED. WIRES MARKED "C(M)" & "C(H)" SHALL BE CONNECTED DIRECT TO THEIR RESPECTIVE MAIN COMMON BUS.



ADJUSTED

STANDARD TRANSMISSION
ADJUSTED COMMON BY U.S.A.
COS. FREIGHT, CHICAGO, AND
SUNSHINE, LOST CONTACTS
PROVIDED BY "2B" MAGNETS
NOT ADDED
APPROVED: C. H. H. H.
REDAINED FROM PLANS 3 BAY
S. 111111, DATED 3-21-20.

1 SHEET

STANDARD

PENNSYLVANIA RAILROAD SYSTEM

CIRCUITS FOR ELECTRO-MECHANICAL SWITCHES


OFFICE OF CHIEF SIGNAL ENGINEER
PHILA., PA. MAY 7, 1924

Approved: *Antonia*
Chief Signal Engineer


Approved: *[Signature]*
Chief Signal Engineer

NOT TO BE USED


S-11111



TYPE "P" & "S-8" (U.S. & S. Co.)



MODEL "2B" (G.R.S. Co.)



NOTE:-

THE "H" BATTERY MOST CONVENIENTLY LOCATED SHALL BE USED FOR EACH INDICATION CIRCUIT AND THE BATTERY USED SHALL BE INDICATED ON DETAIL CIRCUIT PLAN AT EACH

"SS" RELAY THUS: —



* ON "S-8" LEVERS "N" & "R" CONTACTS SHALL BE DESIGNATED "NS" & "RS" AND SHALL BE SO ADJUSTED AS NOT TO BREAK WHILE THE LEVER IS MECHANICALLY LOCKED NORMAL OR REVERSED RESPECTIVELY BUT MUST BREAK BEFORE THE DETECTOR LOCKING TOOTH IS REACHED.

WIRES MARKED "C(M)" & "C(H)" SHALL BE CONNECTED DIRECT TO THEIR RESPECTIVE MAIN COMMON BUS.

REVISIONS.

5-7-24. ARRANGEMENT OF MAGNET COMMONS ON U.S. & S. CO'S. MACHINE CHANGED AND SEPARATE LATCH CONTACTS PROVIDED ON "2B" MACHINE. NOTES ADDED. APPROVED: *Arthur*
REDRAWN FROM PLAN S-821, 5 SHEETS, DATED 4-23-20.

S-821

1 SHEET



PENNSYLVANIA RAILROAD SYSTEM
STANDARD

CIRCUITS FOR ELECTRO-MECHANICAL SWITCHES

OFFICE OF CHIEF SIGNAL ENGINEER
PHILA., PA., MAY 7, 1924.

Approved

Arthur


Chief Signal Engineer

Approved

Arthur

Chief Engineer

NOT TO SCALE



NOTE:

1. "BD" CONTACT SHALL BE OPEN WHEN MOVEMENT OF LEVER IS PREVENTED BY SWITCH LEVER DETECTOR LOCK.
2. SWITCH CONTROL BANDS SHALL BE PLACED ON LARGE SECTION OF ROLLER WHERE ANGULAR MOVEMENT OF ROLLER IS LESS THAN NINETY (90) DEGREES.
3. Q = QUICK SWITCH.
4. EACH SINGLE SWITCH, Crossover OR DOUBLE SLIP SWITCH OPERATED BY ONE LEVER, SHALL HAVE AN INDIVIDUAL COMMON CONNECTION TO COMMON BUS IN NEAREST INSTRUMENT CASE.
5. A TURNOUT AND DERAIL SHALL BE OPERATED THE SAME AS A Crossover.

FIG. 1A

SEGMENTS AND QUADRANTS SHALL BE IN ACCORDANCE WITH THOSE LISTED ON SHEET NO. 3.

LEVER-CONTROL AND INDICATION CIRCUITS
STYLE A1 OR A5 SWITCH & LOCK MOVEMENTS WITH STYLE G VALVES

REVISIONS

SUPERSEDES LEVER CONTROL AND INDICATION CIRCUITS FORMERLY SHOWN ON S-82Z, SKI DATED 7-18-28, SKI-B DATED 1-10-31 AND SNT'S 15, 16, 17, 18, 19 & 20, DATED 8-15-34.	

SHEET 1 OF 15

5-822

THE PENNSYLVANIA RAILROAD
STANDARD
CIRCUITS FOR ELECTRO-PNEUMATIC
SWITCHES


OFFICE OF CHIEF ENGINEER,
PHILA., PA., MAY 24, 1950.

APPROVED:

W. G. Salmonson
ASST. CHIEF ENGINEER- SIGNALS

APPROVED:

APPROVED:
J. H. Smith
CHIEF ENGINEER



MODEL 12 OR STYLE DP14 POLAR INDICATION RELAYS
DO NOT USE FOR NEW WORK OR RENEWALS.





TABLE INTERLOCKER - STYLE DP17 POLAR INDICATION RELAY
FIG. 2D

SEGMENTS AND QUADRANTS FOR NORMAL INDICATION (NM OR NK), REVERSE INDICATION (RM OR RK) AND DETECTOR LOCK (L OR DK) SHALL BE AS FOLLOWS:

SEGMENT		QUADRANT	TYPE OF MACHINE
INDICATION	NM OR NK - RM OR RK	DETECTOR L OR DK	
142 - 8316	138 - 8316	89 - 8349	MODEL 1A, TYPE F14 &
145 - 8316	137 - 8316	107 - 8349	STYLE 5B
143 - 8316	137 - 8316	54 - 8349	STYLE P3
159 - 8316	72 - 8316	6 - 8349	TYPE F & OLD STYLE 1
159 - 8316	72 - 8316	54 - 8349	STYLE P & 57
143 - 8316	137 - 8316	6 - 8349	TYPE F13 & MODEL 1



1000 OHM MODEL 12 OR DP-14 POLAR INDICATION RELAYS - DO NOT
USE FOR NEW WORK OR RENEWALS.
STYLE DP-17 POLAR INDICATION RELAYS - FOR ALL NEW
WORK AND RENEWALS, EXCEPT WHERE PLUG-IN RELAYS ARE PROVIDED.





TABLE INTERLOCKER - PN-50B BIASED NEUTRAL RELAYS
FIG. 2E

USE LATCH PCE. NO.54413, SH.23-8711 WITH SEGMENT 142-8316
 " " " " 49820, SH.19-8711 " SEGMENTS 143-8316 AND 165-8316
 " " " " 5608, SH.7-8711 " SEGMENT 159-8316



STYLE PN-50B BIASED NEUTRAL PLUG-IN TYPE INDICATION RELAYS
FIG. 2C

NOTE:
1. A.A.R. CIRCUIT NOMENCLATURE USED FOR DESIGNATING INSTRUMENTS IN FIGS. 2B AND 2D. FORMER P.R.R. CIRCUIT NOMENCLATURE AND WIRE NUMBERS SHOWN IN PARENTHESES.

LEVER-CONTROL AND INDICATION CIRCUITS

STYLE A1 OR A5 SWITCH AND LOCK MOVEMENTS
WITH STYLE CP VALVES (QUICK SWITCH OMITTED)
MAINTAINER'S RESET FOR POINT DETECTOR
OR WHERE NO POINT DETECTOR IS PROVIDED.

REVISIONS

FIGS. 2A, 2B & 2D SUPERSEDES
LEVER CONTROL & INDICATION
CIRCUITS FORMERLY SHOWN
ON 5-822, SH. 4 DATED 6-25-29
AND REVISED 9-27-48; SH. 5
DATED 10-30-29 AND REVISED
4-14-32, SH. 9 DATED 5-31-32 &
SH. 10, 11, 12 & 13 DATED 6-15-34.
FIGS. 2C & 2E ADDED.

SHEET 2 OF 15

S-822

THE PENNSYLVANIA RAILROAD
STANDARD
CIRCUITS FOR ELECTRO-PNEUMATIC
SWITCHES


OFFICE OF CHIEF ENGINEER,
PHILA., PA., MAY 24, 1950.

APPROVED:

W. G. Selmonson
ASST. CHIEF ENGINEER-SIGNALS


APPROVED

J. H. Bennett
CHIEF ENGINEER



USING DP-17 POLAR RELAYS

FIG. 3A



USING STYLE PN-50B PLUG-IN TYPE RELAYS.

FIG. 3B

- NOTE:
1. "BD" SHALL BE OPEN WHEN MOVEMENT OF LEVER IS PREVENTED BY SWITCH LEVER DETECTOR LOCK.
 2. A.A.R. CIRCUIT NOMENCLATURE USED FOR DESIGNATING INSTRUMENTS. FORMER P.R.R. CIRCUIT NOMENCLATURE AND WIRE NUMBERS SHOWN IN PARENTHESIS.

SEGMENTS AND QUADRANTS FOR NORMAL INDICATION (NM), REVERSE INDICATION (RM) AND DETECTOR LOCK (L) SHALL BE AS FOLLOWS:-

INDICATION (NM OR RM)	DETECTOR (L)	QUADRANT	TYPE OF MACHINE
151-8316	138-8316	89-8349	MODEL 1A, TYPE FA & STYLE P5
146-8316	137-8316	107-8349	STYLE S8
152-8316	137-8316	54-8349	STYLE R3
208-8316	72-8316	6-8349	TYPE F OR OLD STYLE E.R.
208-8316	72-8316	54-8349	STYLE P OR S7
152-8316	137-8316	6-8349	TYPE F13 & MODEL 13EP

REFERENCES 151-8316, 138-8316, 89-8349, ETC., ARE U.S.&S.CO. DRAWING NUMBERS.

USE LATCH PCE. NO. 54413, SH. 23-8711 WITH SEGMENT 151-8316
 " " " " 49820, SH. 19-8711 " SEGMENTS 132-8316 AND 166-8316
 " " " " 3996, SH. 1-8711 " SEGMENT 208-8316


LEVER - CONTROL AND INDICATION CIRCUITS
 FOR USE WHERE STYLE AS MOVEMENTS WITH CP VALVES ARE
 PROVIDED WITH LEVER RESTORE FOR POINT DETECTOR

SHEET 3 OF 15


THE PENNSYLVANIA RAILROAD
 STANDARD
 CIRCUITS FOR ELECTRO-PNEUMATIC
 SWITCHES

OFFICE OF CHIEF ENGINEER,
 PHILA., PA., MAY 24, 1950.
 APPROVED:
 H. G. Salmonson
 ASST. CHIEF ENGINEER-SIGNALS


APPROVED:
 [Signature]
 CHIEF ENGINEER




STYLE PN50B BIASED NEUTRAL PLUG-IN INDICATION RELAYS WHERE SWITCH IS CONTROLLED FROM C.T.C. FIELD STATION OR WHERE ALL RELAY DIRECT WIRE CONTROL IS PROVIDED.



FOR USE WHERE SWITCH IS CONTROLLED FROM CONVENTIONAL
TYPE MACHINE AND INDICATION MAGNETS ARE OMITTED.




FOR USE WHERE SWITCH IS CONTROLLED FROM
ROUTE TYPE MACHINE



STYLE DP-17 POLAR INDICATION RELAYS WHERE SWITCH IS CONTROLLED FROM C.T.C. FIELD STATION OR WHERE ALL RELAY DIRECT WIRE CONTROL IS PROVIDED.

NOTE:
A.A.R. CIRCUIT NOMENCLATURE USED FOR DESIGNATING
INSTRUMENTS. FORMER P.R.R. CIRCUIT NOMENCLATURE AND
WIRE NUMBERS SHOWN IN PARENTHESIS.



FOR USE WHERE WR RELAY CONTROLLED FROM CONVENTIONAL
TYPE MACHINE IS PROVIDED FOR CONTROL OF SWITCH VALVES.

FIG. 4E

LEVER-CONTROL AND INDICATION CIRCUITS
RELAY CONTROL FOR SWITCH VALVES
CONVENTIONAL MACHINE WHERE INDICATION MAGNETS ARE OMITTED.

[illegible]




FIG. 5A




FIG. 5B

FINGER TYPE INDICATION CONTROLLER




FIG. 5C




FIG. 5D




FIG. 5E

ROTARY TYPE INDICATION CONTROLLER
SEGMENT "X" MUST BE REMOVED FROM
CONTROLLER AT RELAY END.




FIG. 5F

CONTACT OPERATION FINGER TYPE INDICATION CONTROLLER:
CONTACTS 1 AND 7 OPEN AND 3 AND 9 CLOSE BEFORE SWITCH
IS UNLOCKED AT START OF SWITCH THROW.
CONTACTS 4 AND 10 CLOSE AND 6 AND 12 OPEN AFTER SWITCH
IS LOCKED AT END OF SWITCH THROW.
CONTACTS 15 AND 18 SHALL BE ADJUSTED TO MAKE JUST
BEFORE INDICATION CONTACTS BREAK.

SWITCH - CONTROL AND INDICATION CIRCUITS
STYLE A1 SWITCH & LOCK MOVEMENTS WITH STYLE C VALVES
WHERE 18', 20' OR 30' SWITCH POINTS ARE PROVIDED.

REVISIONS

SWITCH CONTROL AND INDICATION
CIRCUITS SUPERSEDE S-822,
S-821 DATED 7-18-28, S-820
DATED 1-10-31.

SHEET 5 OF 15

S-822

THE PENNSYLVANIA RAILROAD
STANDARD
CIRCUITS FOR ELECTRO-PNEUMATIC
SWITCHES

OFFICE OF CHIEF ENGINEER,
PHILA., PA., MAY 24, 1950.
APPROVED: *M. J. Salmonson*
ASST. CHIEF ENGINEER-SIGNALS
APPROVED: *J. H. Smith*
CHIEF ENGINEER




FIG. 6A

FINGER TYPE INDICATION CONTROLLER




FIG. 6B

CONTACT OPERATION FINGER TYPE INDICATION CONTROLLER:
CONTACTS 1 AND 7 OPEN AND 3 AND 9 CLOSE BEFORE SWITCH IS UNLOCKED AT START OF SWITCH THROW.
CONTACTS 4 AND 10 CLOSE AND 6 AND 12 OPEN AFTER SWITCH IS LOCKED AT END OF SWITCH THROW.
CONTACTS 15 AND 18 SHALL BE ADJUSTED TO MAKE JUST BEFORE INDICATION CONTACTS BREAK.

CONTACT OPERATION US SWITCH CIRCUIT CONTROLLER:
CONTACTS a ARE CLOSED WHEN SWITCH IS NORMAL.
CONTACTS b ARE OPEN WHEN SWITCH IS NORMAL.
CONTACTS c ARE CLOSED WHEN SWITCH IS REVERSE.
CONTACTS d ARE OPEN WHEN SWITCH IS REVERSE.
CONTACT x CLOSING BEFORE CONTACTS a OPEN.
CONTACT y CLOSING BEFORE CONTACTS c OPEN.

WHERE SWITCH AND LOCK MOVEMENT IS USED AT THE MID-POINT (PLAN S-222-A) CIRCUITS SHOWN DOTTED SHALL BE PROVIDED.




FIG. 6C

ROTARY TYPE INDICATION CONTROLLER
SEGMENT 'X' MUST BE REMOVED FROM CONTROLLER AT RELAY END.




FIG. 6D

SWITCH-CONTROL AND INDICATION CIRCUITS

STYLE A1 SWITCH AND LOCK MOVEMENTS WITH STYLE C VALVES WHERE 45° SWITCH POINTS ARE PROVIDED.

REVISIONS
SWITCH CONTROL AND INDICATION CIRCUITS SUPERSEDE S-822, SHTS. 17, 18, 19 & 20 DATED 8-15-34.

SHEET 6 OF 15

S-822

THE PENNSYLVANIA RAILROAD
STANDARD
CIRCUITS FOR ELECTRO-PNEUMATIC SWITCHES

OFFICE OF CHIEF ENGINEER,
PHILA., PA., MAY 24, 1950.

APPROVED:
H. E. Salmonson
ASST. CHIEF ENGINEER-SIGNALS

APPROVED:
J. H. Bennett
CHIEF ENGINEER




FIG. 7A

FINGER TYPE INDICATION CONTROLLER




FIG. 7B

CONTACT OPERATION FINGER TYPE INDICATION CONTROLLER
CONTACTS 1 AND 7 OPEN AND 3 AND 9 CLOSE BEFORE SWITCH
IS UNLOCKED AT START OF SWITCH THROW.
CONTACTS 4 AND 10 CLOSE AND 6 AND 12 OPEN AFTER SWITCH
IS LOCKED AT END OF SWITCH THROW.
CONTACTS 15 AND 18 SHALL BE ADJUSTED TO MAKE JUST
BEFORE INDICATION CONTACTS BREAK.

CONTACTS ♦ ARE OPERATED BY SWITCH VALVE.




FIG. 7C

ROTARY TYPE INDICATION CONTROLLER
SEGMENT "X" MUST BE REMOVED FROM CONTROLLER AT RELAY END.




FIG. 7D

SWITCH-CONTROL AND INDICATION CIRCUITS
STYLE A1 SWITCH AND LOCK MOVEMENTS WITH CP VALVES
WHERE 18', 20', OR 30' SWITCH POINTS ARE PROVIDED.

REVISIONS
SWITCH CONTROL AND INDICATION CIRCUIT SUPERSEDES S-822, S-824 DATED 6-25-29 AND REVISED 9-27-45 AND S.H.S. DATED 10-30-29 AND REVISED 4-14-32.

SHEET 7 OF 15


S-822

THE PENNSYLVANIA RAILROAD
STANDARD
CIRCUITS FOR ELECTRO-PNEUMATIC
SWITCHES

OFFICE OF CHIEF ENGINEER,
PHILA., PA., MAY 24, 1950.

APPROVED:
M. G. Salmonson
ASST. CHIEF ENGINEER-SIGNALS


APPROVED:
[Signature]
CHIEF ENGINEER



FOR CONNECTIONS TO VERTICAL TERMINAL BOARDS SEE FIG. 15A
FINGER TYPE INDICATION CONTROLLER
FIG. 8A

CONTACT OPERATION FINGER TYPE INDICATION CONTROLLER:
CONTACTS 1 AND 7 OPEN AND 3 AND 9 CLOSE BEFORE SWITCH
IS UNLOCKED AT START OF SWITCH THROW.
CONTACTS 4 AND 10 CLOSE AND 6 AND 12 OPEN AFTER SWITCH
IS LOCKED AT END OF SWITCH THROW.
CONTACTS 15 AND 18 SHALL BE ADJUSTED TO MAKE JUST
BEFORE INDICATION CONTACTS BREAK.

CONTACTS 4 ARE OPERATED BY SWITCH VALVE.



FOR CONNECTIONS TO VERTICAL TERMINAL BOARDS SEE FIG. 15B
ROTARY TYPE INDICATION CONTROLLER
SEGMENT 'X' MUST BE REMOVED FROM CONTROLLER AT RELAY END

FIG. 8B

SWITCH-CONTROL AND INDICATION CIRCUITS

STYLE A1 SWITCH AND LOCK
MOVEMENTS WITH STYLE CP
VALVES WHERE 18', 20', OR 30'
SWITCH POINTS ARE PROVIDED.

REVISIONS
SWITCH CONTROL AND INDICATION CIRCUIT SUPERSEDES S-822, SH. 4 DATED 6-25-29 AND REVISED 9-27-48 AND SH. 5 DATED 10-30-29 AND REVISED 4-14-32.

SHEET 8 OF 15

S-822


THE PENNSYLVANIA RAILROAD
 STANDARD
**CIRCUITS FOR ELECTRO-PNEUMATIC
 SWITCHES**



OFFICE OF CHIEF ENGINEER,
 PHILA., PA., MAY 24, 1950
 APPROVED:  ASST. CHIEF ENGINEER-SIGNALS
 APPROVED:  CHIEF ENGINEER

FIGURE 2A, 2B, 2C, 2D OR 2E



FOR CONNECTIONS TO VERTICAL TERMINAL BOARD SEE FIG. 14B

FIG. 9A

CONTACT OPERATION FINGER TYPE INDICATION CONTROLLER:
CONTACTS 1 AND 7 OPEN AND 3 AND 9 CLOSE BEFORE SWITCH IS UNLOCKED AT START OF SWITCH THROW.
CONTACTS 4 AND 10 CLOSE AND 6 AND 12 OPEN AFTER SWITCH IS LOCKED AT END OF SWITCH THROW.
CONTACTS 15 AND 18 SHALL BE ADJUSTED TO MAKE JUST BEFORE INDICATION CONTACTS BREAK.


CONTACT OPERATION US SWITCH CIRCUIT CONTROLLER:
CONTACTS a ARE CLOSED WHEN SWITCH IS NORMAL.
CONTACTS b ARE OPEN WHEN SWITCH IS NORMAL.
CONTACTS c ARE CLOSED WHEN SWITCH IS REVERSE.
CONTACTS d ARE OPEN WHEN SWITCH IS REVERSE.
CONTACT x CLOSING BEFORE CONTACTS a OPEN.
CONTACT y CLOSING BEFORE CONTACTS c OPEN.

WHERE SWITCH AND LOCK MOVEMENT IS USED AT THE MID-POINT (PLAN S-222-A) CIRCUITS SHOWN DOTTED SHALL BE PROVIDED.

CONTACTS 4 ARE OPERATED BY SWITCH VALVE

SWITCH-CONTROL AND INDICATION CIRCUITS
STYLE A1 SWITCH AND LOCK MOVEMENTS WITH CP VALVES
WHERE 4.5" SWITCH POINTS ARE PROVIDED.

FIGURE 2A, 2B, 2C, 2D OR 2E



FOR CONNECTIONS TO VERTICAL TERMINAL BOARDS SEE FIG. 14C

FIG. 9B

REVISIONS

SWITCH CONTROL AND INDICATION
CIRCUITS SUPERSEDE S-822,
SHTS. 12 AND 13 DATED
8-15-34.

SHEET 9 OF 15


S-822

THE PENNSYLVANIA RAILROAD
STANDARD
CIRCUITS FOR ELECTRO-PNEUMATIC
SWITCHES

OFFICE OF CHIEF ENGINEER,
PHILA., PA., MAY 24, 1950.

APPROVED:
H. S. Salmonson
ASST. CHIEF ENGINEER-SIGNALS


APPROVED:
J. H. Bennett
CHIEF ENGINEER



CONTACT OPERATION VS SWITCH CIRCUIT CONTROLLER

CONTACTS $\#$	ARE CLOSED WHEN SWITCH IS NORMAL.
CONTACTS $\#$	ARE OPEN WHEN SWITCH IS NORMAL.
CONTACTS c	ARE CLOSED WHEN SWITCH IS REVERSE.
CONTACTS c	ARE OPEN WHEN SWITCH IS REVERSE.
CONTACT x	CLOSES BEFORE CONTACTS $\#$ OPEN.
CONTACT y	CLOSES BEFORE CONTACTS c OPEN.

WHERE SWITCH AND LOCK MOVEMENT IS USED AT THE MID-POINT
(PLAN S-222-A) CIRCUITS SHOWN DOTTED SHALL BE PROVIDED.
SEGMENT "X" MUST BE REMOVED FROM CONTROLLER AT RELAY END.



SWITCH-CONTROL AND INDICATION CIRCUITS
STYLE A5 SWITCH AND LOCK MOVEMENTS WITH C VALVES
WHERE 45° SWITCH POINTS ARE PROVIDED

REVISIONS

SWITCH CONTROL AND INDICATION
CIRCUIT SUPERSEDES 5-822.
SHTS. 15 & 16 DATED 8-15-34.

SHEET 10 OF 15

5-822

SHEET NO. 1 OF 15



THE PENNSYLVANIA RAILROAD
STANDARD

S-622

CIRCUITS FOR ELECTRO-PNEUMATIC SWITCHES

OFFICE OF CHIEF ENGINEER,
PHILA., PA., MAY 24, 1950.
APPROVED:




APPROVED
H. G. Salmonson
ASST. CHIEF ENGINEER-SIGNALS

APPROVED:

CHIEF ENGINEER

ASST. CHIEF ENGINEER-SIGNALS

CHIEF ENGINEER



CONNECTIONS TO
VERTICAL TERMINAL BOARDS
FOR
STYLE "CP" VALVES

A.A.R. CIRCUIT NOMENCLATURE USED FOR
WIRE NUMBERS IN FIG. 13C. FORMER P.R.R.
WIRE NUMBERS SHOWN IN PARENTHESES.

REVISIONS

SUPERSEDES S-822, 5H. 7
DATED 9-28-46.

S-822

SHEET 13 OF 15

THE PENNSYLVANIA RAILROAD
STANDARD
CIRCUITS FOR ELECTRO-PNEUMATIC
SWITCHES



OFFICE OF CHIEF ENGINEER,
PHILA., PA., MAY 24, 1950.

APPROVED:

W. G. Salmonson
ASST. CHIEF ENGINEER-SIGNALS

APPROVED:

W. H. Bennett
CHIEF ENGINEER




WHEN WIRES 3L3, FIG. 14B OR 3L5 & 3L6 FIG. 14C ARE REQUIRED ARRANGE CONNECTIONS AS SHOWN DOTTED.

A.A.R. CIRCUIT NOMENCLATURE USED FOR WIRE NUMBERS. FORMER P.R.R. WIRE NUMBERS SHOWN IN PARENTHESIS.

9 CONDUCTOR CABLE TO CIRCUIT CONTROLLER AT MID-POINT OF 45 SWITCH POINTS


CONNECTIONS TO VERTICAL TERMINAL BOARDS FOR STYLE "CP" VALVES



CROSSOVER
CONNECTIONS FOR FIGS. 9B AND 12B
FIG. 14C

12 CONDUCTOR CABLE TO CIRCUIT CONTROLLER AT MID-POINT OF 45 SWITCH POINTS-RELAY END

12 CONDUCTOR CABLE TO CIRCUIT CONTROLLER AT MID-POINT OF 45 SWITCH POINTS-FAR END



REVISIONS

SUPERSEDES S-822, 3H.7
DATED 7-28-46.

SHEET 14 OF 15


5-822

THE PENNSYLVANIA RAILROAD
STANDARD
CIRCUITS FOR ELECTRO-PNEUMATIC
SWITCHES


OFFICE OF CHIEF ENGINEER,
PHILA., PA., MAY 24, 1950.

APPROVED:
H. E. Salmonson
ASST. CHIEF ENGINEER-SIGNALS

APPROVED:
J. H. Bennett
CHIEF ENGINEER





REVISIONS.



S-823

NOT TO SCALE

Approved *[Signature]*
Chief Engineer




THE PENNSYLVANIA RAILROAD
STANDARD
CIRCUITS FOR ELECTRIC SW.



OFFICE OF CHIEF ENGINEER
PHILA. PA.

APPROVED: *[Signature]*
CHIEF ENGINEER

APPROVED: *[Signature]*
CHIEF ELECTRICIAN



- NOTE:-
1. WHERE A.C. CONTROLLERS ARE USED BOTH ELEMENTS OF THE CONTROLLER MUST BE ENERGIZED FROM THE SAME SOURCE OF POWER.
 2. THE CONTROL OF A SINGLE SWITCH AND DERAIL SHALL BE THE SAME AS A CROSSOVER.
 3. WIRING AS SHOWN IS FOR MOVEMENT WHERE RIGHT HAND SWITCH POINT IS NORMALLY CLOSED.
 4. (A) 250 OHM RESISTORS SHALL BE USED FOR 100 CYCLE CONTROLLERS.
(B) 300 OHM RESISTORS SHALL BE USED FOR 60 CYCLE CONTROLLERS.
(C) WHERE A 100 CYCLE CONTROLLER IS OPERATED ON 60 CYCLES A 100 OHM-SWATT CAPACITY RESISTOR SHALL BE PLACED IN SERIES WITH THE 250 OHM RESISTOR.
 5. WHERE LEFT HAND POINT IS NORMALLY CLOSED OR FOR MOVABLE POINT FROG MOVEMENT INTERCHANGE LEADS TO B AND C.
 6. WHERE LEFT HAND POINT IS NORMALLY CLOSED INTERCHANGE LEADS TO 9 AND 10.
 7. -ARROW INDICATES DIRECTION OF NEXT ROTATION.



"OR" OVERLOAD RELAYS.
FOR EXISTING INSTALLATIONS, OVERLOAD RELAY MAY BE INSTALLED IN INSTRUMENT CASE IF LOCATED IN CLOSE PROXIMITY TO THE SWITCH MOVEMENT. IF NOT, A NEW CIRCUIT CONTROLLER BOX SHALL BE USED.

STYLE "M" MOVEMENT.
A.C. OPERATION
FOR EXISTING INSTALLATIONS.

REVISIONS.

MAR. 1, 1937. NOTE 1 & 2 FORMERLY SPECIFIED 500 OHM RESISTOR
APPROVED: *A.H. Russell*
SEPT. 1, 1934.
"OR" OVERLOAD RELAYS
ADDED IN LIEU OF THERMAL CUTOUTS.
APPROVED: *A.H. Russell*
REDRAWN FROM SHS 1 & 7 OF PLAN 3-823 DATED 12-8-33 & 10-26-36 RESPECTIVELY.


SHEET 3 OF 12

S-823


THE PENNSYLVANIA RAILROAD
STANDARD
CIRCUITS FOR ELECTRIC SWITCHES

OFFICE OF CHIEF ENGINEER,
PHILA., PA., JUNE 25, 1935.
Approved: *A.H. Russell*
Chief Signal Engineer

NOT TO SCALE
Approved: *W.H. Russell*



FOR GENERAL NOTES SEE SHEET NO. 3.



REVISIONS.

6-25-29. RESISTOR-RECTIFIER UNIT ADDED IN TYPE "F" CONTROLLER.

APPROVED: *C.M. Reed*

REDRAWN FROM SH. 2 & 3 OF PLAN S-823 DATED 12-8-23, SH. 3 LAST REVISED 12-27-24.

STYLE "M" MOVEMENT.
D.C. OPERATION
FOR EXISTING INSTALLATIONS.

SHEET 4 OF 6



S-823

THE PENNSYLVANIA RAILROAD
STANDARD
CIRCUITS FOR ELECTRIC SWITCHES

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., JUNE 26, 1929

Approved: *C.M. Reed*
Chief Signal Engineer

NOT TO SCALE
Approved: *W. H. Williams*
Chief Engineer



"OR" OVERLOAD RELAYS.
FOR EXISTING INSTALLATIONS, OVERLOAD RELAY MAY BE INSTALLED IN INSTRUMENT CASE IF LOCATED IN CLOSE PROXIMITY TO THE SWITCH MOVEMENT. IF NOT, A NEW CIRCUIT CONTROLLER BOX SHALL BE USED.

NOTE :-
1. WHERE LEFT HAND POINT IS NORMALLY CLOSED OR FOR MOVABLE POINT FROG MOVEMENT, INTERCHANGE LEADS TO B AND C.
2. WHERE LEFT HAND POINT IS NORMALLY CLOSED INTERCHANGE LEADS TO 5 AND 10.

FOR GENERAL NOTES SEE SHEET 3.

REVISIONS.

MAR 1, 1937. RESISTORS IN CONTROLLER CIRCUIT FORMERLY LOCATED AT "NR" RELAY.

APPROVED: *A.H. Hudd*

SEPT 1, 1934. "OR" OVERLOAD RELAYS ADDED IN LIEU OF THERMAL CUTOUTS.

APPROVED: *A.H. Hudd*


SHEET 5 OF 12

S 623


THE PENNSYLVANIA RAILROAD
STANDARD
CIRCUITS FOR ELECTRIC SWITCHES

APPROVED: *A.H. Hudd*
Chief Signal Engineer

APPROVED: *A.H. Hudd*
Chief Signal Engineer



- NOTE :-
- SWITCH MOVEMENT - M2, M20 OR M22 - CLASS B - 20 VOLT MEDIUM SPEED.
 - CONTACTS ON SWITCH INDICATION CIRCUIT CONTROLLER. - SEE NOTE L.
 - POLARIZED SWITCH CONTROL RELAY WITH 2F & 2B LOW VOLTAGE CONTACTS, 2F HIGH VOLTAGE CONTACTS AND 4N & 4R POLAR CONTACTS, THE HIGH VOLTAGE FRONT CONTACTS BEING ADJUSTED TO OPEN AFTER THE LOW VOLTAGE CONTACTS.
 - DUAL SELECTOR LEVER CONTACT ON M20 OR M22 MOVEMENT OR STICK CONTACT ACTUATED BY HAND CRANK OPERATION ON M2 MOVEMENT WHICH MUST BE MANUALLY RESET.
 - DUAL SELECTOR LEVER CONTACT ON M20 OR M22 MOVEMENT.
 - ORIO OVERLOAD RELAY (NON-STICK TYPE).
 - DUAL SELECTOR AND OVERLOAD STICK REPEATER DNII RELAY, ONCE OPENED CAN ONLY BE PICKED UP BY OPENING THE "WR" RELAY.
 - WHEN CONTROLLING AN M2 MOVEMENT OMIT CONTACT REFERRED TO IN NOTE E AND CONNECT AS SHOWN BY DOTTED LINE.
 - CONTROL CIRCUITS FOR "WR" RELAYS ARE TYPICAL. COMPLETE CIRCUITS FOR "WR" RELAYS SHALL BE SHOWN ON CIRCUIT PLAN FOR EACH INSTALLATION.
 - ARROW INDICATES DIRECTION OF NEXT ROTATION.
 - SWITCH MACHINE WIRING IS SHOWN FOR A MOVEMENT HAVING A R.H. POINT NORMALLY CLOSED. IF USED FOR A SWITCH HAVING A L.H. POINT NORMALLY CLOSED, INTERCHANGE LEADS TO TERMINALS B & C AND TO TERMINALS 5 & 10 ON MAIN TERMINAL BOARD IN SWITCH MACHINE, ALSO REVERSE THE INDICATION CIRCUIT CONTROLLER CAMS - NOTE B.



STYLE M2-M20-M22
LOW VOLTAGE MOVEMENTS
WITH ORIO OVERLOAD RELAY.

REVISIONS.

SUPERSEDES SH. 6 OF PLAN
S-823 DATED 6-25-22

SHEET 6 OF 12.

S-823

THE PENNSYLVANIA RAILROAD
STANDARD
CIRCUITS FOR ELECTRIC SWITCHES



OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., FEB. 9, 1937.

APPROVED: *D.H. Todd*
CHIEF SIGNAL ENGINEER

NOT TO SCALE

APPROVED: *W.H. King*
CHIEF ENGINEER.

UNIVERSAL CIRCUIT CONTROLLER
CONTACT a = CLOSED WHEN SW. IS NORMAL
" b = OPEN " " "
" c = CLOSED " " = REVERSE
" d = OPEN " " "



SIMILAR TO U.S. & S. CO'S. CATALOGUE PLATE L-1250.
(SPECIFY PIECE NO. AND REFERENCE)

NOTE:-

- NOTE:-
1. FOR GENERAL NOTES SEE SHEET NO.1.
2. CIRCUITS SHOWN IN DOTTED LINES SHALL BE PROVIDED WHERE "M2", "M20" OR "M22" MOVEMENTS ARE USED, CIRCUIT CONTROLLER BEING OPERATED BY SELECTOR LEVER IN "M20" OR "M22" AND BY CRANK IN "M2" MOVEMENTS.
3. SWITCH CIRCUIT CONTROLLER SHALL BE IN ACCORDANCE WITH U.S.C.S. CO.S. CATALOGUE PLATE 1-K01, PIECE 116478, REFERENCE 'B' USING CRANK REFERENCE 31, DATE J-101.
4. WHERE 45' SWITCH POINTS ARE LOCATED ON NEAR END OF CROSSOVER ONLY CIRCUIT CONTROLLER AND JUNCTION BOX MARKED 'A' SHALL BE PROVIDED AND WHERE 45' SWITCH POINTS ARE LOCATED ON FAR END OF CROSSOVER ONLY CIRCUIT CONTROLLER AND JUNCTION BOX MARKED 'B' SHALL BE PROVIDED.

STYLE M, M2, M20, M22 MOVEMENTS
SWITCH INDICATION AND
55' CONTROL CIRCUITS
(WITH QUICK SWITCH)
WHERE
45' SWITCH POINT
IS USED
ON ONE END ONLY
AND
UNIVERSAL CIRCUIT
CONTROLLER PROVIDED.

REVISIONS

SHEET 11 OF 12

S-823



THE PENNSYLVANIA RAILROAD
STANDARD
CIRCUITS FOR ELECTRIC SWITCHES

OFFICE OF CHIEF SIGNAL ENGINEER
PHILA, PA., SEPT. 5, 1935.
Approved: _____

NOT TO SCALE

Approved:



Approved:

A H Russ
Chief Signal Engineer


T. J. Skellman
Chief Engineer

W.C.
H.C.V.
G.L.B.
E.L.S.

UNIVERSAL CIRCUIT CONTROLLER
CONTACT 2 = CLOSED WHEN SW. IS NORMAL.
" b = OPEN " " "
" c = CLOSED " " REVERSE
" d = OPEN " " "



SIMILAR TO U.S. & S. CO'S. CATALOGUE PLATE L-1250
(SPECIFY PIECE NO. AND REFERENCE)



STYLE "M", "M2", "M20" "M22" MOVEMENTS
SWITCH INDICATION AND
"55" CONTROL CIRCUITS
(WITHOUT QUICK SWITCH)
WHERE
45' SWITCH POINT
IS USED
ON ONE END ONLY
AND
UNIVERSAL CIRCUIT
CONTROLLERS PROVIDED

NOTES:-

1. NO CONTACTS ON TYPE "F" CONTROLLER.
2. FOR GENERAL NOTES SEE SHEET NO.1.
3. CIRCUITS SHOWN IN DOTTED LINES SHALL BE PROVIDED WHERE "M2", "M20" OR "M22" MOVEMENTS ARE USED, CIRCUIT CONTROLLER BEING OPERATED BY SELECTOR LEVER IN "M20" OR "M22" AND BY CRANK IN "M2" MOVEMENTS.
4. SWITCH CIRCUIT CONTROLLER SHALL BE IN ACCORDANCE WITH U.S. & CO.'S CATALOGUE PLATE J-1001, PIECE 116478, REFERENCE "B" USING CRANK REFERENCE 31, PLATE J-1010.
5. WHERE 45° SWITCH POINTS ARE LOCATED ON NEAR END OF CROSSOVER ONLY CIRCUIT CONTROLLER AND JUNCTION BOX MARKED "A" SHALL BE PROVIDED AND WHERE 45° SWITCH POINTS ARE LOCATED ON FAR END OF CROSSOVER ONLY CIRCUIT CONTROLLER AND JUNCTION BOX MARKED "B" SHALL BE PROVIDED.

SHEET 12 OF 12

S-823

THE PENNSYLVANIA RAILROAD
STANDARD
CIRCUITS FOR ELECTRIC SWITCHES

OFFICE OF CHIEF SIGNAL ENGINEER
PHILA., PA., SEPT. 5, 1935.
Approved: 

NOT TO SCALE

Approved:

Chief Signal Engineer

T. J. Skelton
Chief Engineer

	MODEL 14 POWER MACHINE (ELECTRO-PNEU. OR ELECTRIC) OR STYLE "P5" ELECTRO-MECHANICAL	STYLE "5-8" STYLE "P-3" OLD STYLE TYPE "F"	STYLE "5-7" OLD STYLE ELECTRO-PNEU. STYLE "P"	STYLE "P-4"	
SIGNAL LEVER (NORMAL IN CENTER) TRAFFIC LEVER SWITCH DETECTOR SEGMENT FOR POWER SWITCH	 SH. 138-8316 1A	 SH. 137-8316 1B	 SH. 72-8316 1C	 SH. 185-8316 1D	NOTE: 1. WHERE SEGMENT WITH FORCED DOWN FEATURE IS PROVIDED A LATCH WITH LOWER FACE BEVELED SHALL BE PROVIDED. 2. QUADRANTS MUST BE SELECTED WITH NOTCHES ARRANGED IN ACCORDANCE WITH THE CUT OF THE SEGMENT WITH PROPER CONSIDERATION FOR THE LATCH CIRCUIT CONTROLLER, IF PROVIDED. 3. SEGMENTS SHOWN ARE FOR INTERLOCKING MACHINES MANUFACTURED BY THE UNION SWITCH & SIGNAL CO. 4. SH. 138-8316, 156-8316, ETC. REFERS TO THE UNION SWITCH & SIGNAL CO'S. DRAWING NUMBERS.
SIGNAL LEVER (NORMAL IN-EXTREME END POSITION) OR INDICATION FOR ELECTRIC SW. LOCK WHERE LEVER IS NOR- MAL IN EXTREME POSITION.	 SH. 156-8316 2A	 SH. 169-8316 2B	 SH. 158-8316 2C	 SH. 193-8316 2D	
SWITCH INDICATION SEGMENT FOR POWER SWITCH (WHERE QUICK SWITCH IS PROVIDED)	 SH. 151-8316 3A		 SH. 1-8316 3C	 SH. 172-8316 3D	
SWITCH INDICATION LEVER (ELECTRO-MECHANICAL SWITCH)	 SH. 108-8316 4A	 SH. 50-8316 4B	 SH. 43-8316 4C	 SH. 64-8316 4D	
SWITCH INDICATION SEGMENT FOR POWER SWITCH (WITHOUT QUICK SWITCH)	 SH. 142-8316 5A		 SH. 159-8316 5C	 SH. 159-8316 5D	
SWITCH DETECTOR SEGMENT (ELECTRO-MECHANICAL SWITCH)	 SH. 141-8316 6A	 SH. 129-8316 6B	 SH. 170-8316 6C	 SH. 187-8316 6D	
SEGMENT TO PREVENT LEVER FROM BEING MOVED TO LEFT OR RIGHT.	 SH. 162-8316 7A	 SH. 181-8316 7B	 SH. 181-8316 7C	 SH. 181-8316 7D	

INTERLOCKING MACHINE

REVISIONS.

12-14-28-SW DETECTOR SEG-
MENTS 1A, 1B, 1C & 1D FORM-
ERLY SHOWN AS 5A, 5B, 5C
& 5D. SEGMENTS 5A, 5B,
5C AND 5D ADDED.

APPROVED *[Signature]* 12/24/28
NEW

SHEET 1 OF 2


S-824

THE PENNSYLVANIA RAILROAD
STANDARD
SEGMENTS

OFFICE OF CHIEF SIGNAL ENGINEER
PHILA., PA., JULY 19, 1928.


Approved *[Signature]*
Chief Signal Engineer

NOT TO SCALE
Approved *[Signature]*
Chief Engineer




SIGNAL LEVER
(NORMAL IN CENTER)
OR
TRAFFIC LEVER
U.S. & S. CO. SH. 2-12592
G. R. S. CO. 13174-7.

FIG. 8




SIGNAL LEVER
(NORMAL IN LEFT POSITION)
U.S. & S. CO. SH. 4-12592
" " 7-12592 - USED WITH
3 POSITION DEVICE.
G. R. S. CO. 13174-19.

FIG. 9



SIGNAL LEVER
(NORMAL IN RIGHT POSITION)
U.S. & S. CO. SH. 5-12592
" " 8-12592 - USED WITH
3 POSITION DEVICE.
G. R. S. CO. 13174-18

FIG. 10



SWITCH LEVER
U.S. & S. CO. SH. 3-12592
G. R. S. CO. 13174-16.

FIG. 11

REVISIONS

TABLE INTERLOCKER

SHEET 2 OF 2

S-824




THE PENNSYLVANIA RAILROAD
STANDARD
SEGMENTS

OFFICE OF CHIEF SIGNAL ENGINEER
PHILA., PA., JULY 15, 1928.

Approved *att. R. S.*
Chief Signal Engineer

Approved *[Signature]*
Chief Engineer

NOT TO SCALE



NOTE:-

CIRCUIT FOR CLEAR CONTROL RELAY FOR SIG. A" SHALL BREAK OVER FRONT CONTACT OF RELAY "B133".
CIRCUIT CONTROLLER "B" SHALL BE EQUIPPED WITH A DEVICE TO STOP THE LEVER AT MID-STROKE, IN GOING FROM NORMAL TO REVERSE, IN ACCORDANCE WITH PLAN 3-854.

WITH DISTANT SIGNALS:- SIGNALS NORMALLY LIGHTED.

REVISIONS.

12-21-33. RELAY "DCRM"
FORMERLY CONTROLLED
OVER CONTACT ON "IA".
APPROVED: [Signature]

SHEET 1 OF 3

THE PENNSYLVANIA RAILROAD
TYPICAL

CONTROL CIRCUITS FOR REMOTE CONTROL OF MANUAL BLOCK SIGNAL

OFFICE OF CHIEF SIGNAL ENGINEER
PHILA. PA., MARCH 8, 1908.



Approved _____

[Signature]
Chief Signal Engineer

Abstract

NOT TO SCALE

Chas. E. ...



- NOTE:
1. 10VOLT, 40 WATT LAMPS SHALL BE USED IN FLASHING LIGHT TRAIN ORDER SIGNALS. VOLTAGE AT LAMPS SHALL BE BETWEEN 9.0 AND 9.5 VOLTS.
 2. FLASHER RELAYS SHALL BE ADJUSTED TO APPROXIMATELY 30 FLASHES PER MINUTE.
 3. CONTROL SWITCHES SHALL BE TWO POSITION, DOUBLE POLE, SIMILAR TO W.R.S. CO. PLATE M30, REF. 2, PCE NO. 0300-102.

REVISIONS

SUPERSEDES PLAN S-830
DATED 4-14-43

S-830

1 SHEET






THE PENNSYLVANIA RAILROAD TYPICAL CONTROL CIRCUITS FOR FLASHING LIGHT TRAIN ORDER SIGNAL

OFFICE OF CHIEF ENGINEER,
PHILA., PA., APRIL 25, 1930.

APPROVED:
H. G. Salmonson
ASST. CHIEF ENGINEER-SIGNALS

NOT TO SCALE
APPROVED:
W. H. Smith
CHIEF ENGINEER





TO SIG 403
SEE PLAN S-857

TO SIG 412
SEE PLAN S-861

TO SIG 425
SEE PLAN S-861

FOR SQUARED LOCATIONS.

APPROVED: *[Signature]*

SHEET 3 OF 4

S-845

THE PENNSYLVANIA RAILROAD
TYPICAL


**CIRCUITS FOR ABSOLUTE PERMISSIVE
BLOCK SIGNAL SYSTEM**


DESIGNED BY: *[Signature]*



APPROVED: *[Signature]*

DATE: 10-1-57

BY: *[Signature]*







REVISIONS

FIG. 1 REDRAWN FROM 3H. 5 AND
FIG. 2 REDRAWN FROM 3H. 2 OF
FORMER LINES EAST PLAN NO.
1234, 3H. 5 DATED 5-29-12
AND 3H. 2 DATED 5-24-12.
LAST REVISION 12-17-19.

S-847

SHEET 7 OF 3

**THE PENNSYLVANIA RAILROAD
CONTROL CIRCUITS FOR 110 V. A.C.
"T2" MOTOR SIGNALS**

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA. PA. DEC. 14, 1928.



Approved

A. N. Prasad
Chief Signal Engineer

NOT TO SCALE

Approved


Chief Engineer



ARRANGEMENT OF LIGHTING CIRCUITS

REVISIONS

FIG. 5 REDRAWN FROM SH. 6 OF
FORMER LINES EAST PLAN NO.
1234, DATED 5-27-1912.
LAST REVISION 12-17-1919.

SHEET 3 OF 3

S-847



**THE PENNSYLVANIA RAILROAD
CONTROL CIRCUITS FOR 110 V. A.C.
"T2" MOTOR SIGNALS**

OFFICE OF CHIEF SIGNAL ENGINEER,
PMMA, PA, DEC. 14 1926.





Approved

Chief Signal Engineer

NOT TO SCALE

Approved: 

Chief Engineer



FROM OTHER CONTROLLING APPARATUS. SEE PENNSYLVANIA RAILROAD SYSTEM TYPICAL PLAN S-862.

SEE PENNSYLVANIA RAILROAD SYSTEM TYPICAL PLAN S-862 FOR ARRANGEMENT OF CIRCUIT WHERE "LIGHT-OUT" RELAY IS USED.



REVISIONS.
6-12-24. ALL SIGNALS FORMERLY SEMAPHORE TYPE
APPROVED: <i>Art. Reddy</i>
REDRAWN FROM PLAN S-851 DATED 5-12-20.

1 SHEET
S-851

PENNSYLVANIA RAILROAD SYSTEM
TYPICAL HOME SIGNAL CONTROL CIRCUITS
BETWEEN MACHINE AND SIGNALS

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., JUNE 12, 1924.
Approved: *Art. Reddy*
Chief Signal Engineer

NOT TO SCALE
Approved: *[Signature]*
Chief Engineer



NOTE:
FOR CONTROL OF SWITCH REPEATING RELAYS SEE
PLAN S-821.
FOR OTHER CONTROLLING APPARATUS SEE
PLAN S-862-SH.1.

SPECIAL MECHANICAL LOCKING

1	LOCKS	17
5	"	9-21
13	"	17
24L	"	5
24R	"	17

D.C. NEUTRAL SWITCH REPEATING RELAYS ELECTRO-MECHANICAL MACHINE

REVISIONS

REDRAWN FROM APPROVED PLAN
S-852-SH.1, DATED 12-6-20, LAST
REVISED 12-15-20.

SHEET 1 OF 2

S-852



PENNSYLVANIA RAILROAD SYSTEM TYPICAL "SS" PROTECTION

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., DEC. 27, 1924.


Approved *at Road*

Chief Signal Engineer

Approved

NOT TO SCALE

Chief Engineer



NOTE:-
 FOR CONTROL OF SWITCH REPEATING RELAYS SEE
 PLAN S-822.
 FOR OTHER CONTROLLING APPARATUS SEE
 PLAN S-862-SH.1.

SPECIAL MECHANICAL LOCKING
 1 LOCKS 9
 3 " 7-11
 5 " 9
 8L " 3
 8R " 9

D.C. POLARIZED SWITCH REPEATING RELAYS.
 ELECTRO-PNEU. MACHINE.

REVISIONS.
 12-27-24. POLAR CONTACTS ON
 "SS" RELAYS FORMERLY NORMAL
 TO THE RIGHT.
 APPROVED: *A.H. Kudd*
 REDRAWN FROM APPROVED PLAN
 S-852-SH.3, DATED 12-6-20.

SHEET 2 OF 2

S-852


PENNSYLVANIA RAILROAD SYSTEM
TYPICAL "SS" PROTECTION

OFFICE OF CHIEF SIGNAL ENGINEER,
 PHILA., PA., DEC. 27, 1924

Approved: *A.H. Kudd*
 Chief Signal Engineer


NOT TO SCALE
 Approved: *[Signature]*
 Chief Engineer

REC
 1007
 C. A.



DIST. SIG. AT CLEAR WHEN 4L IS OR


FIG. 1



DIST. SIG. AT APPROACH RESTRICTING WHEN 4L IS OR

DIST. SIG. AT CLEAR WHEN 4L IS

FIG. 2.



DIST. SIG. AT APPROACH RESTRICTING WHEN 4L IS OR

DIST. SIG. AT CLEAR WHEN 4L IS OR

FIG. 3.

- NOTE:-
1. WHERE SLOW RELEASING RELAY IS NOT PROVIDED IN THE CONTROL CIRCUITS FOR THE "H" RELAYS, RESISTOR AND CONTACT IN RELAY 2DJ1A SHALL BE OMITTED FROM ITS CONTROL.
 2. ALL NON-INTERLOCKED CROSSOVERS, TURNOUTS AND DERAILS BETWEEN HOME AND DISTANT SIGNALS SHALL BE IN ACCORDANCE WITH BASIC PLANS S-228 TO S-233 INCLUSIVE AND SHALL BE INSULATED AND BONDED IN ACCORDANCE WITH STANDARD PLAN S-803.
 3. WHERE DIRECT CURRENT TRACK CIRCUITS ARE PROVIDED NEUTRAL D.C. TRACK RELAY SHALL BE USED.



REVISIONS

SUPERSEDES PLAN S-853
DATED 3-3-25, LAST REVISED 3-5-25


SHEET 1 OF 2

S-853

THE PENNSYLVANIA RAILROAD
TYPICAL
CONTROL CIRCUITS FOR
CLEAR CONTROL OF DISTANT SIGNALS
OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., FEB. 21, 1933.
Approved Chief Signal Engineer.
Approved Chief Engineer.



NOTE: BLOCK SIGNALS SHALL BE CONTROLLED OVER DIVERGING SWITCHES (OR DERAILS) LOCATED IN THE TRACK APPROACHING AND WITHIN 750' OF THE SIGNAL AND THOSE UP TO 1000' MAY BE CONSIDERED.



- NOTE- AM

 - 1.- BLOCK SIGNALS IN PERMISSIVE BLOCK TERRITORY SHALL BE CONTROLLED BY:
 - A. A TABLE CIRCUIT CONTROLLER EQUIPPED WITH A DEVICE TO STOP THE LEVER AT MID-STROKE, IN GOING FROM NORMAL TO REVERSE, REQUIRING A DISTINCT MOVEMENT BY THE OPERATOR TO MOVE LEVER PAST THE MID-STROKE POSITION.
 - B. WHERE TOP ARM OF HOME INTERLOCKING SIGNAL IS ALSO A BLOCK SIGNAL IT SHALL BE CONTROLLED AS FOLLOWS:
 - (a) WHERE U.S. & C.O.'S. POWER OR ELECTRO-MECHANICAL MACHINE IS IN SERVICE, ONE LEVER, EQUIPPED WITH THREE POSITION DEVICE, SHALL BE USED TO CONTROL THE TOP ARM OF THE HOME SIGNAL AND A SECOND LEVER SHALL BE USED TO CONTROL OTHER SIGNALS USUALLY CONTROLLED BY THE ONE LEVER.
 - (b) WHERE G.R.S. C.O.'S. POWER OR ELECTRO-MECHANICAL MACHINE IS IN SERVICE A SEPARATE LEVER SHALL BE USED TO CONTROL THE CLEAR POSITION OF THE BLOCK SIGNAL.
 - C. A BLOCK SIGNAL AT AN INTERLOCKING MAY BE CONTROLLED FROM THE INTERLOCKING MACHINE AS FOLLOWS:
 - (a) WHERE U.S. & C.O.'S. POWER OR ELECTRO-MECHANICAL MACHINE IS IN SERVICE, BY A LEVER EQUIPPED WITH A THREE POSITION DEVICE.
 - (b) WHERE G.R.S. C.O.'S. POWER OR ELECTRO-MECHANICAL MACHINE IS IN SERVICE, BY TWO LEVERS, ONE FOR THE PERMISSIVE AND THE OTHER FOR THE CLEAR BLOCK INDICATION.
 - 2.- WHERE THE SWITCH (OR DERAIL) IS CONTROLLED BY A LEVER IN THE MACHINE, THE CONTROL CIRCUITS FOR THE SIGNAL RELAYS SHALL BE BROKEN OVER A CONTACT ON THE SWITCH LEVER (SEE PLAN 3-862, SH.1) EXCEPT WHERE THERE IS AN ADDITIONAL TRACK SECTION BETWEEN THE SWITCH AND ADVANCE SIGNAL, WHERE ARRANGEMENT SIMILAR TO THAT SHOWN IN FIG. 2 SHALL BE USED.
 - 3.- WHERE BOTH THE BLOCK SIGNAL AND THE SWITCH (OR DERAIL) ARE CONTROLLED BY LEVERS IN THE MACHINE, THE SIGNAL LEVER SHALL MECHANICALLY LOCK THE SWITCH LEVER AND THE SWITCH REPEATING RELAY (AM) SHALL BE OMITTED.
 - 4.- WHERE A FACING POINT SWITCH IS LOCATED NOT MORE THAN 6000' BEYOND THE MANUAL BLOCK. SIGNAL ARRANGE CIRCUITS AS FOLLOWS:-
 - A. PERMISSIVE BLOCK TERRITORY. WHERE TRAFFIC CONDITIONS ARE SUCH THAT NO MATERIAL DELAY WILL RESULT FROM HOLDING THE SIGNAL AT "STOP" WITH THE TRACK OCCUPIED BETWEEN THE SIGNAL AND THE SWITCH, EXTEND TRACK SECTION "A1" TO INCLUDE THE SWITCH OMITTING THE LINE (CM) RELAY. IF THIS ARRANGEMENT WILL RESULT IN EXCESSIVE DELAY THE LINE (SWITCH REPEATING) RELAY (CM) SHOULD BE PROVIDED. *
 - B. ABSOLUTE BLOCK TERRITORY. EXTEND TRACK SECTION "A1" TO INCLUDE THE SWITCH, OMITTING THE LINE (CM) RELAY. *
 - * ALL NON-INTERLOCKED SWITCHES PROTECTED BY THE BLOCK SIGNAL SHALL BE IN ACCORDANCE WITH STANDARD PLANS BASIC NO'S. 3-228 TO 3-235 INCLUSIVE AND THOSE IN TRACK CIRCUIT TERRITORY SHALL BE INSULATED AND BONDED IN ACCORDANCE WITH PLAN 3-803.

REVISIONS

2-17-26. CIRCUITS FOR SIG.
"B" AND NOTE A, FIGURE 3
CHANGED. TITLE FORMERLY
"TYPICAL CONTROL CIRCUITS FOR
ADVANCE SIGNALS."

APPROVED: *AK* 102

4-13-26. RELAYS W/HHH FORMERLY
CONTROLLED OVER N & R CONTACTS
RESPECTIVELY. FIG. 182. AUXILIARY
CIRCUIT CONTROLLED FORMERLY
PROVIDED FOR CLEAR CONTROL OF
SIGNAL B'S. FIG. 183 OMITTED

APPROVED: *AK* 103

REDRAWN FROM PLAN
5-854 DATED 12-7-20.

NOTE:-

For index of aspects, see Sheet No. 2.

For arrangement of terminals in terminal box, see Pennsylvania Railroad System Standard Plan No. S-858.

A separate pair of wires (positive and negative) shall be run from the relay location to each signal mast.

Lighting circuits shall be so adjusted as to have uniform voltage at the lamps. The voltage shall be between the following limits:

	Maximum	Minimum	Recommended
High Signals - -	11.5 V.	11.0 V.	-
Dwarf Signals- -	5.0 V.	4.0 V.	4.2 V. or 4.3 V.

Lamps shall be in accordance with Pennsylvania Railroad System Standard Plan Basic No. S-483.


Signal wires and control relays have been numbered from arbitrary signal numbers and correct number of the signal controlled shall be substituted.

Complete control of all relays shall be shown on circuit plan of interlocking. For typical control circuits for signal controlling relays, see Pennsylvania Railroad System Typical Circuit Plan No. S-862.

Where D.C. lighting circuits are installed, arrange "Light-out" (EM) relay thus:-

For Primary Battery:

Approach Lighting Relay



For Storage Batteries circuits shall be similarly arranged except that approach lighting relay shall be omitted.

Where no "light-out" (2^aEM) relay is used circuits shall be arranged as shown by dotted lines.

For typical arrangement for lighting position-light home and advance signals when normal power fails, see Pennsylvania Railroad System Typical Circuit Plan No. S-805. Where this arrangement is used, circuits shall be modified accordingly and shown in detail on circuit plan to be prepared for each interlocking or block signal installation.

REVISIONS.

REWRITTEN FROM SHEET 1 OF
PLAN S-855 DATED 10-18-21,
LAST REVISED 11-9-23.

SHEET 1 OF 9

S-855



PENNSYLVANIA RAILROAD SYSTEM
STANDARD

LIGHTING CIRCUITS FOR POSITION LIGHT
HOME INTERLOCKING & BLOCK SIGNALS

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., JAN. 26, 1925.

Approved

A. H. Reed
Chief Signal Engineer

Approved

NOT TO SCALE
[Signature]
Chief Engineer

TOP ARM.				BOTTOM ARM.								DWARF SIGNAL.	
ASPECT	FIGURE NUMBER	ASPECT	FIGURE NUMBER	ASPECT	FIGURE NUMBER	ASPECT	FIGURE NUMBER	ASPECT	FIGURE NUMBER	ASPECT	FIGURE NUMBER	ASPECT	FIGURE NUMBER
	1		7		11		17		23				31
				AUTOMATIC BLOCK TERRITORY.		AUTOMATIC BLOCK TERRITORY.		AUTOMATIC BLOCK TERRITORY.					
	2		8		12		18		24				32
				MANUAL OR CONTROLLED MANUAL BLOCK TERRITORY.		AUTOMATIC BLOCK TERRITORY.		AUTOMATIC BLOCK TERRITORY.					
	3				13		19		25		30		33
				MANUAL OR CONTROLLED MANUAL BLOCK TERRITORY.		MANUAL OR CONTROLLED MANUAL BLOCK TERRITORY.		MANUAL OR CONTROLLED MANUAL BLOCK TERRITORY.		TAKE SIDING INDICATOR.			
	4				14		20		26				34
				AUTOMATIC BLOCK TERRITORY.		AUTOMATIC BLOCK TERRITORY.		AUTOMATIC, MANUAL OR CONTROLLED MANUAL BLOCK TERRITORY.					
	5				15		21		27				35
				MANUAL OR CONTROLLED MANUAL BLOCK TERRITORY.		MANUAL OR CONTROLLED MANUAL BLOCK TERRITORY.		AUTOMATIC BLOCK TERRITORY.					
	6				16		22	NOTE:- SEE FIGURES 1, 3 & 5 FOR SIMILAR ARRANGEMENT IN MANUAL OR CONTROLLED MANUAL BLOCK TERRITORY.					
				MANUAL OR CONTROLLED MANUAL BLOCK TERRITORY.		MANUAL OR CONTROLLED MANUAL BLOCK TERRITORY.							

REVISIONS.

INDEX.

REDRAWN FROM SHEET 2 OF PLAN S-855 DATED 10-18-21, LAST
REVISED 5-18-22.

SHEET 2 OF 2

S-855



PENNSYLVANIA RAILROAD SYSTEM STANDARD LIGHTING CIRCUITS FOR POSITION LIGHT HOME INTERLOCKING & BLOCK SIGNALS

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., JAN. 28, 1922

Approved

Arthur H. ...
Chief Signal Engineer

Approved

...
Chief Engineer

NOT TO SCALE




FIGURE 1.




FIGURE 2.




FIGURE 3.




FIGURE 4.




FIGURE 5.

NOTE:-
IN MANUAL OR CONTROLLED MANUAL BLOCK TERRITORY WHERE ONLY THE MARKER LIGHT IS USED IN ADDITION TO THE TOP ARM, THE "LIGHT-OUT" RELAY SHALL NOT BE USED AND CIRCUITS SHALL BE ARRANGED AS SHOWN IN DOTTED LINES.

FOR GENERAL NOTES SEE SHEET NO. 1.

TOP ARM.

REVISIONS.
1-26-25. CIRCUITS FOR MARKER LIGHT IN MANUAL OR CONTROLLED MANUAL BLOCK TERRITORY ADDED.
APPROVED: <i>Ant</i>
REDRAWN FROM TOP ARM CONTROL OF SHEETS 370-18 INC. OF PLAN 5-855 DATED 11-18-21, SH. 3, 4, 6, 7, 8, 9, 12, 13, 15 & 16 LAST REVISED 11-9-23.

SHEET 3 OF 9

PENNSYLVANIA RAILROAD SYSTEM
STANDARD
LIGHTING CIRCUITS FOR POSITION LIGHT
HOME INTERLOCKING & BLOCK SIGNALS




OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., JAN. 26, 1925.

Approved *Ant*
Chief Signal Engineer

Approved *Ant*
Chief Engineer

NOT TO SCALE

S-855



FOR GENERAL NOTES SEE SHEET NO.1.

TOP ARM.

REVISIONS.

REDRAWN FROM TOP ARM CONTROL
OF SHEETS 197023 INC. OF PLAN
S-855 DATED 11-18-21, SH3. 13, 20, 21,
24, 25, 27, 28 & 29 LAST REVISED 11-9-22.

REDRAWN FROM TOP ARM CONTROL
OF SHEETS 19 TO 29 INC. OF PLAN
S-855 DATED 10-18-71, SH3, 19, 20, 21,
24, 25, 27, 28 & 29 LAST REVISED 11-9-71.

SHEET 4 OF 8

S-855

**PENNSYLVANIA RAILROAD SYSTEM
STANDARD
LIGHTING CIRCUITS FOR POSITION LIGHT
HOME INTERLOCKING & BLOCK SIGNALS**

OFFICE OF CHIEF SIGNAL ENGINEER
PHILA., PA., JAN. 20, 1925


Approved

Chief Signal Engineer


Approved

NOT TO SCALE


Chief Engineer




AUTOMATIC BLOCK TERRITORY.
FIGURE 11.




MANUAL OR CONTROLLED MANUAL BLOCK TERRITORY.
FIGURE 12.



MANUAL OR CONTROLLED MANUAL BLOCK TERRITORY.
FIGURE 13.



AUTOMATIC BLOCK TERRITORY.
FIGURE 14.



MANUAL OR CONTROLLED MANUAL BLOCK TERRITORY.
FIGURE 15.

FOR GENERAL NOTES SEE SHEET NO. 1.

BOTTOM ARM.

REVISIONS.

SHEET 5 OF 9

S-855




PENNSYLVANIA RAILROAD SYSTEM
STANDARD
LIGHTING CIRCUITS FOR POSITION LIGHT
HOME INTERLOCKING & BLOCK SIGNALS

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., JAN. 20, 1926.


Approved *A. H. Reed*
Chief Signal Engineer

Approved *[Signature]*
Chief Engineer


NOT TO SCALE




MANUAL OR CONTROLLED MANUAL BLOCK TERRITORY.
FIGURE 16.




AUTOMATIC BLOCK TERRITORY.
FIGURE 17.



AUTOMATIC BLOCK TERRITORY.
FIGURE 18.



MANUAL OR CONTROLLED MANUAL BLOCK TERRITORY.
FIGURE 19.



AUTOMATIC BLOCK TERRITORY.
FIGURE 20.

FOR GENERAL NOTES SEE SHEET NO.1.

BOTTOM ARM.

REVISIONS.

1-26-25. FIGURES 16, 19 AND 20 ADDED.
APPROVED: *[Signature]*
REDRAWN FROM BOTTOM ARM CONTROL OF SHEETS 36, 7, 8, 12, 15, 18, 24 & 27 OF PLAN S-855 DATED 10-18-21, LAST REVISED 11-9-23.

S-855

SHEET 6 OF 9



PENNSYLVANIA RAILROAD SYSTEM
STANDARD






LIGHTING CIRCUITS FOR POSITION LIGHT
HOME INTERLOCKING & BLOCK SIGNALS

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., JAN. 20, 1925.

Approved: *[Signature]*
Chief Signal Engineer

NOT TO SCALE

Approved: *[Signature]*
Chief Engineer



FOR GENERAL NOTES SEE SHEET NO.1.

BOTTOM ARM.

REVISIONS.

1-26-25. FIGURES 21, 22, 24
AND 25 ADDED.

APPROVED:- *A. H. Reed*

REDRAWN FROM BOTTOM ARM
CONTROL OF SHEETS 9, 21 AND 28
OF PLAN S-855- DATED 10-18-21.
LAST REVISED 11-9-23.

5-855

SHEET 7 OF 9


PENNSYLVANIA RAILROAD SYSTEM STANDARD LIGHTING CIRCUITS FOR POSITION LIGHT HOME INTERLOCKING & BLOCK SIGNALS

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., JAN. 26, 1925.


Approved 
Chief Signal Engineer

OT TO SCALE


Approved _____
Chief Engineer



AUTOMATIC, MANUAL OR CONTROLLED MANUAL BLOCK TERRITORY.
FIGURE 26.



AUTOMATIC BLOCK TERRITORY.
FIGURE 27.
NOTE:—SEE SHEET 3 FOR SIMILAR ARRANGEMENT IN
MANUAL OR CONTROLLED MANUAL BLOCK TERRITORY.



TAKE SIDING INDICATOR.
FIGURE 30.

FOR GENERAL NOTES SEE SHEET NO.1.

BOTTOM ARM &
TAKE SIDING INDICATOR.

REVISIONS.

1-26-25. FIGURE 26 ADDED.
APPROVED: *AND*
REDRAWN FROM BOTTOM ARM
CONTROL OF SHEETS 10, 22 & 34
OF PLAN S-855 DATED 10-10-21.

S-855

SHEET 8 OF 9



PENNSYLVANIA RAILROAD SYSTEM
STANDARD
LIGHTING CIRCUITS FOR POSITION LIGHT
HOME INTERLOCKING & BLOCK SIGNALS

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., JAN. 20, 1925

Approved

A. H. Rusk
Chief Signal Engineer

Approved


[Signature]
Chief Engineer

NOT TO SCALE

INDEX	
ASPECT	SHEET NUMBER
	2 THREE BLOCK INDICATION
	3 TWO BLOCK INDICATION
	4
	5
	6
	7
	8
	9
	10
	11 DIST SWITCH SIGNAL

NOTE:-

1. ARRANGEMENTS SHOWN IN FIGURES 3, 6, 9, 12 AND 15 COVER EXISTING INSTALLATIONS AND SHALL BE USED FOR NEW WORK AND RENEWALS WHERE THERE IS LITTLE OR NO PROBABILITY OF CAB SIGNALS OR TRAIN CONTROL BEING PROVIDED.
2. WHERE D.C. SLOW ACTING RELAYS ARE SUBSTITUTED FOR A.C. SLOW ACTING RELAYS MARKED Ø THEY SHALL HAVE A RETARDED-PICK UP AND A RETARDED DROP-AWAY OF NOT LESS THAN 0.5 SECONDS AND SHALL BE CONTROLLED DIRECT FROM A RECTIFIER OR BATTERY AT THE SIGNAL LOCATION. WHERE POLARIZED TRACK CIRCUITS ARE USED THE POLE-CHANGING CIRCUITS SHALL BE SIMILAR TO THOSE WHERE SV-30 OR SV-32 RELAYS ARE USED.
3. FOR ARRANGEMENT OF TERMINALS IN TERMINAL BOX SEE STANDARD PLAN S-858.
4. EACH MAST SHALL HAVE SEPARATE POSITIVE AND NEGATIVE WIRES.
5. LIGHTING CIRCUITS SHALL BE SO ADJUSTED AS TO HAVE UNIFORM VOLTAGE AT THE LAMPS. THE VOLTAGE SHALL BE BETWEEN THE FOLLOWING LIMITS:- MAXIMUM 115V; MINIMUM 110V, KEEPING IT AS NEAR THE MAXIMUM AS PRACTICABLE.
6. LAMPS SHALL BE IN ACCORDANCE WITH STANDARD PLAN BASIC NO. S-463.
7. ALL CROSSEOVERS, TURNOUTS AND DERAILS BETWEEN HOME AND DISTANT SIGNALS SHALL BE IN ACCORDANCE WITH STANDARD PLANS BASIC NOS. S-228 TO S-233 INCLUSIVE, AND SHALL BE INSULATED AND BONDED IN ACCORDANCE WITH STANDARD PLAN S-803.
8. SIGNAL WIRES AND CONTROL RELAYS HAVE BEEN NUMBERED FROM ARBITRARY TRACK NUMBER AND CORRECT NUMBER FOR THE TRACK OVER WHICH SIGNAL GOVERNS SHOULD BE SUBSTITUTED.
9. CONTROL OF DISTANT SIGNAL RELAYS (IDJ^a, IDJ^b, IDJ, ETC.) SHALL BE SHOWN ON CIRCUIT PLAN OF INTERLOCKING. FOR TYPICAL ARRANGEMENT SEE TYPICAL CIRCUIT PLAN S-853.
10. TRACK CIRCUITS SHOWN ARE TYPICAL. DETAIL ARRANGEMENT OF TRACK CIRCUITS SHOULD BE MADE FOR EACH INSTALLATION TO SUIT LOCAL CONDITIONS AND REQUIREMENTS.
11. WHERE NO "LIGHT-OUT" (IDEM) RELAY IS USED CIRCUITS SHALL BE ARRANGED AS SHOWN BY DOTTED LINES.
12. WHERE DISTANT SIGNAL IS ALSO THE ADVANCE SIGNAL FOR ANOTHER INTERLOCKING THE POLARIZED TRACK FEED FOR SECTION IN THE REAR OF THE SIGNAL SHALL BE OMITTED AND THE PRIMARY SIDE OF THE TRACK TRANSFORMER SHALL BE CONNECTED DIRECT TO THE 110 V. BUS.
13. WHERE DIRECTION OF TRAFFIC IS NORTH AND SOUTH SUBSTITUTE LETTER "N" FOR "E" AND "S" FOR "W" IN LINE CONTROL CIRCUITS.
14. FOR D.C. TRACK CIRCUITS, TRACK BATTERY SHALL CONSIST OF NOT LESS THAN TWO GRAVITY CELLS OR CAUSTIC-SODA CELLS OF EQUIVALENT VOLTAGE. CAUSTIC-SODA BATTERIES SHALL BE IN ACCORDANCE WITH STANDARD PLAN BASIC NO. S-500, AND SHALL HAVE RESISTANCE (NOT LESS THAN TWO-TENTHS OHMS) BETWEEN BATTERY AND TRACK, ADJUSTED TO SUIT LOCAL CONDITIONS.



ARRANGEMENT OF CIRCUIT WHICH SHALL BE PROVIDED WHERE A.C. SLOW ACTING RELAYS OTHER THAN STYLE SV-30 OR SV-32 ARE USED. WHERE D.C. SLOW ACTING RELAYS ARE USED SEE NOTE 2.

SKETCH "A"

REVISIONS.

2-16-27 NOTES 1 & 2 AND SKETCH "A" ADDED.
APPROVED: *[Signature]*
REDRAWN FROM SHEET 1 AND 2 OF PLAN S-856, SH. 1 DATED 12-27-24, LAST REVISED 12-27-24, SHEET 2 DATED 10-7-21.

SHEET 1 OF 11


S-856

THE PENNSYLVANIA RAILROAD STANDARD LIGHTING CIRCUITS FOR POSITION LIGHT DISTANT SIGNALS

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., FEB. 10, 1927

Approved: *[Signature]*
Chief Signal Engineer

NOT TO SCALE
Approved: *[Signature]*
Chief Engineer




NOTE:-


* A. 10V-FOR STYLE T2LV14 RELAY.
110V-FOR MODEL 15 VANE RELAY.


B. WHERE A.C. SLOW ACTING RELAYS OTHER THAN SV-30 OR SV-32 ARE USED CIRCUITS MARKED * SHALL BE ARRANGED AS SHOWN IN SKETCH "A", SHEET NO. 1.


C. WHERE D.C. SLOW ACTING RELAYS ARE SUBSTITUTED FOR RELAYS MARKED * SEE NOTE 2, SHEET NO. 1.



FOR GENERAL NOTES SEE SHEET NO. 1.








TO SECONDARY OF LINE TRANS.



STEAM ROAD
FIGURE 8.

[illegible]

REVISIONS

2-16-27 FIG. 8 ADDED, SINGLE
SECONDARY TRACK AND
SEPARATE LIGHTING TRANS.
PROVIDED IN FIG. 7 AND
POLE. CHANGING CIRC. IN
FIG. 9 CHANGED.
APPROVED: *W. H. H. H.*
FIG. 7 REDRAWN FROM JNL
AND FIG. 9 FROM JNL. OF
PLAN 3-288 DATED 10-7-21
LAST REVISED 3-27-22.

TO SECONDARY OF LINE TRANS.




ELECTRIC ROAD (A.C. PROPULSION)
FIGURE 10.


NOTE:-
* A. 10 V. FOR STYLE T2LV14 RELAY.
110 V. FOR MODEL 15 VANE RELAY.
B. WHERE A.C. SLOW ACTING RELAYS OTHER THAN SV-30 OR SV-32 ARE USED CIRCUITS MARKED $\emptyset$ SHALL BE ARRANGED AS SHOWN IN SKETCH "A", SHEET NO.1
C. WHERE D.C. SLOW ACTING RELAYS ARE SUBSTITUTED FOR RELAYS MARKED $\emptyset$ SEE NOTE 2, SHEET NO.1.

FOR GENERAL NOTES SEE SHEET NO.1.

TO SECONDARY OF LINE TRANS.




STEAM ROAD
FIGURE 11.



FOR FIGURES 11 & 12.

TO SECONDARY OF LINE TRANS.



STEAM ROAD.
FIGURE 12.

REVISIONS.

E-16-ET.FIG. 11 ADDED. SINGLE SECONDARY TRAC TRANS. AND SEPARATE LIGHTING TRANS. PROVIDED IN FIG. 10 AND POLE-CHANGING CIRC. IN FIG. 12 CHANGED.
APPROVED: *[Signature]*
FIG. 10 REDRAWN FROM SH. 9 AND FIG. 12 FROM SH. 10 OF PLAY S-856 DATED 10-7-21, LAST REVISED 11-9-25.

SHEET 5 OF 11

S-856


THE PENNSYLVANIA RAILROAD
STANDARD
LIGHTING CIRCUITS FOR
POSITION LIGHT DISTANT SIGNALS

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., FEB. 10, 1927




Approved *[Signature]*
Chief Signal Engineer

Approved *[Signature]*
Chief Engineer

NOT TO SCALE



FOR GENERAL NOTES SEE SHEET NO.1.




REVISIONS.

2-16-27. FIG. 14 ADDED. SINGLE SECONDARY TRINCH TRANS. AND SEPARATE LIGHTING TRANS. PROVIDED IN FIG. 13 AND POLE-CHANGING CIRC. IN FIG. 15 CHANGED.

APPROVED- *W. H. Kelly*

FIG. 13 REDRAWN FROM SH. 11 AND FIG. 15 FROM SH. 12 OF PLIN 3-456 DATED 0-7-29, LAST REVISED 3-27-22.



A.C. TRACK - A.C. LIGHTING
FIGURE 16. (NOTE B)





FIGURE 16A. (NOTE C)



D.C. TRACK - A.C. LIGHTING
FIGURE 17. (NOTE B)





FIGURE 17A. (NOTE C)



D.C. TRACK - APPROACH LIGHTING
FIGURE 18. (NOTE B)




FIGURE 18A. (NOTE C)

NOTE:
A. WHERE D.C. SLOW ACTING RELAYS ARE SUBSTITUTED FOR RELAYS MARKED $\emptyset$ SEE NOTE 2, SHEET NO. 1.
B. WHERE POLARIZED TRACK AND NEUTRAL LINE CIRCUITS ARE USED SEE FIGS. 16, 17 & 18.
C. WHERE NEUTRAL TRACK AND POLARIZED LINE CIRCUITS ARE USED SEE FIGS. 16A, 17A & 18A.

REVISIONS.

3-2-35 LIGHT-OUT RELAYS
REMOVED & FIGS. 16A, 17A & 18A
ADDED.
APPROVED: *[Signature]*
REDRAWN FROM PLAN 3-056,
SH. 7. DATED 2-16-27.

S-856

SHEET 7 OF 11

THE PENNSYLVANIA RAILROAD STANDARD LIGHTING CIRCUITS FOR POSITION LIGHT DISTANT SIGNALS


OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA. PA., MARCH 2, 1933.

Approved: *[Signature]*
Chief Signal Engineer.

Approved: *[Signature]*
Chief Engineer.

NOT TO SCALE


TO SECONDARY OF LINE TRANS.



A.C. TRACK - A.C. LIGHTING.
FIGURE 22.


NOTE:-
* A. 10 V.-FOR STYLE T2LV14 RELAY.
110 V.-FOR MODEL 15 VANE RELAY.
B. WHERE D.C. SLOW ACTING RELAYS ARE SUBSTITUTED
FOR RELAYS MARKED Ø SEE NOTE 2, SHEET NO.1.

TO SECONDARY OF LINE TRANS.



D.C. TRACK - A.C. LIGHTING.
FIGURE 23.

FOR GENERAL NOTES SEE SHEET NO.1.



FOR VOLTAGE SEE NOTE 5, SHEET 1.
D.C. TRACK-APPROACH LIGHTING.
FIGURE 24

REVISIONS.

FIG. 22 REDRAWN FROM SH. 19, FIG. 23 FROM SH. 21 OF PLAN 5-856 DATED 10-7-21, SH. 19 & 20 LAST REVISED 11-9-23 SH. 21 LAST REVISED 12-27-24

S-856

SHEET 9 OF 11

THE PENNSYLVANIA RAILROAD
STANDARD
LIGHTING CIRCUITS FOR
POSITION LIGHT DISTANT SIGNALS


OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., FEB 18, 1927

Approved: *[Signature]*
Chief Signal Engineer

Approved: *[Signature]*
Chief Engineer


NOT TO SCALE

TO SECONDARY OF LINE TRANS.




A.C. TRACK - A.C. LIGHTING.
FIGURE 25.

TO SECONDARY OF LINE TRANS.



D.C. TRACK - A.C. LIGHTING.
FIGURE 26.



D.C. TRACK - APPROACH LIGHTING.
FIGURE 27.

FOR GENERAL NOTES SEE SHEET NO.1.

REVISIONS.

FIG. 25 REDRAWN FROM SH. 22, FIG. 26 FROM SH. 23 AND FIG. 27 FROM SH. 24 OF PLAN S-856 DATED 10-7-21, LAST REVISED 3-27-22.

SHEET 10 OF 11

S-856



THE PENNSYLVANIA RAILROAD
STANDARD
LIGHTING CIRCUITS FOR
POSITION LIGHT DISTANT SIGNALS

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., FEB. 10, 1927

Approved *Arthur H. ...*
Chief Signal Engineer





Approved *William ...*
Chief Engineer

NOT TO SCALE


TO SECONDARY OF LINE TRANS.

TO SECONDARY OF LINE TRANS.


TO SECONDARY OF LINE TRANS.



A. C. TRACK - A. C. LIGHTING.
FIGURE 28.



D. C. TRACK - A. C. LIGHTING
FIGURE 29.



FOR VOLTAGE SEE NOTE 5, SHEET 1.

D. C. TRACK - APPROACH LIGHTING.
FIGURE 30.

REVISIONS.

FIG. 28 REDRAWN FROM S.H. 25 FIG. 29 FROM S.H. 26 AND FIG. 30 FROM S.H. 27 OF PLAN S-856 DATED 10-7-21, LAST REVISED 3-27-22.

SHEET 11 OF 11

S-856

FOR GENERAL NOTES SEE SHEET NO. 1.



THE PENNSYLVANIA RAILROAD
STANDARD
LIGHTING CIRCUITS FOR
POSITION LIGHT DISTANT SIGNALS

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., FEB. 18, 1927

Approved *[Signature]*
Chief Signal Engineer

NOT TO SCALE

Approved *[Signature]*
Chief Engineer

NOTE:-

1- FOR ARRANGEMENT OF TERMINALS IN TERMINAL BOX SEE STANDARD PLAN NO. S-858.

2- EACH MAST SHALL HAVE A SEPARATE POSITIVE AND A SEPARATE NEGATIVE WIRE.

3- LIGHTING CIRCUITS SHALL BE SO ADJUSTED AS TO HAVE UNIFORM VOLTAGE AT THE LAMPS. THE VOLTAGE SHALL BE BETWEEN THE FOLLOWING LIMITS:- MAXIMUM-11.5 VOLTS, MINIMUM-11.0 VOLTS, KEEPING IT AS NEAR THE MAXIMUM AS PRACTICABLE.

4- LAMPS SHALL BE IN ACCORDANCE WITH STANDARD PLAN BASIC NO. S-483.


5- ALL NON-INTERLOCKED CROSSEOVERS, TURNOUTS AND DERAILS IN AUTOMATIC SIGNAL TERRITORY SHALL BE IN ACCORDANCE WITH STANDARD PLANS BASIC NOS. S-228 TO S-233 INCLUSIVE AND SHALL BE INSULATED AND BONDED IN ACCORDANCE WITH STANDARD PLAN S-803.

6- SIGNAL WIRES AND CONTROL RELAYS HAVE BEEN NUMBERED FROM ARBITRARY TRACK NUMBER AND CORRECT NUMBER FOR THE TRACK WHICH SIGNAL GOVERNS SHALL BE SUBSTITUTED.


7- WHERE NO "LIGHT-OUT" (IEM) RELAY IS USED CIRCUITS SHALL BE ARRANGED AS SHOWN BY DOTTED LINES.

8- WHERE THE TRACK SECTION APPROACHING AN AUTOMATIC SIGNAL IS NOT POLARIZED, THE POLARIZED TRACK FEED FOR SUCH SECTION SHALL BE OMITTED AND THE TRACK TRANSFORMER CONNECTED DIRECT TO THE 110V. BUS. SEE FIGURES 4, 5 AND 6.

9- WHERE DIRECTION OF TRAFFIC IS NORTH AND SOUTH SUBSTITUTE THE LETTER "N" FOR "E" AND "S" FOR "W" IN THE LINE CONTROL CIRCUITS.



ARRANGEMENT WHICH SHALL BE USED FOR SUPPLYING ENERGY TO D.C. APPARATUS.
SKETCH "A"



ARRANGEMENT OF CIRCUIT WHICH SHALL BE PROVIDED WHERE A.C. SLOW ACTING RELAYS OTHER THAN STYLE S.V. 30 OR S.V. 32 ARE USED.

WHERE A D.C. SLOW ACTING RELAY IS SUBSTITUTED FOR THE A.C. SLOW ACTING RELAY IT SHALL HAVE A RETARDED PICK-UP AND A RETARDED DROP-AWAY OF NOT LESS THAN 0.5 SECONDS AND POLE-CHANGING CIRCUITS SHALL BE ARRANGED SIMILAR TO THOSE WHERE S.V. 30 OR S.V. 32 RELAYS ARE USED.

SKETCH "B"

REVISIONS

2-14-27 SKETCHES
ADDED
APPROVED: *Arthur*
DERIVATION FROM SH. 1 OF PLAN
S-857 DATED 10-18-21
LAST REVISED 11-3-23.

S-857

SHEET 1 OF 4


**THE PENNSYLVANIA RAILROAD
STANDARD
CIRCUITS FOR POSITION LIGHT
AUTOMATIC SIGNALS**

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., FEB. 14, 1927

Approved: *Arthur*
Chief Signal Engineer

Approved: *Arthur*
Chief Engineer

NOT TO SCALE

[illegible]

STEAM ROAD
FIGURE 2.

2-14-27, SINGLE SECONDARY
TRACK TRANSFORMERS AND
POLARIZED LINE CIRCUIT
PROVIDED IN FIG. 1. NO. 2
ADDED.

APPROVED: *A. H. Reed*

FIG. 1 REDRAWN FROM SH. 2.
OF PLAN 3-857, DATED
10-18-21, LAST REVISED 11-9-23


S-857

OFFICE OF CHIEF SIGNAL ENGINEER,
PMAA, PA, FEB 14, 1967
Approved *[Signature]*
Chief Signal Engineer


NOT TO SCALE

Approved  Chief Engineer



TO SECONDARY OF LINE TRANS.




TO SECONDARY OF LINE TRANS.



TO SECONDARY OF LINE TRANS.



STEAM ROAD.
FIGURE 5.



STEAM ROAD.
FIGURE 6.

NOTE:-

A- * 10K FOR STYLE TZLVIA RELAY.
110K FOR MODEL 15 VANE RELAY.

B- ARRANGEMENTS SHOWN IN FIGURES 5 AND 6 COVER EXISTING INSTALLATIONS AND SHALL BE USED FOR NEW WORK AND RENEWALS WHERE THERE IS LITTLE OR NO PROBABILITY OF CAB SIGNALS OR TRAIN CONTROL BEING PROVIDED.

C- WHERE D.C. RELAYS ARE SUBSTITUTED FOR RELAYS MARKED Ø D.C. ENERGY SHALL BE SUPPLIED AS SHOWN IN SKETCH "A", SHEET NO. 1.

D- WHERE A.C. SLOW ACTING RELAYS OTHER THAN SY-30 OR SY-32 ARE USED CIRCUITS MARKED Ø SHALL BE ARRANGED AS SHOWN IN SKETCH "B", SHEET NO. 1.

FOR GENERAL NOTES SEE SHEET NO. 1.

REVISIONS

REDRAWN FROM SHEETS 3-8-5
OF PLAN 3-857 DATED 10-13-21
SHEET 3 LAST REVISED 11-9-23
SHEET 5 LAST REVISED 3-27-22.



S-867

SHEET 4 OF 4

THE PENNSYLVANIA RAILROAD STANDARD CIRCUITS FOR POSITION LIGHT AUTOMATIC SIGNALS

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., FEB. 4, 1927
Approved *[Signature]*
Chief Signal Engineer

NOT TO SCALE
Approved *[Signature]*
Chief Engineer



N = NEUTRAL LAMP.
 0-1 = STOP LAMPS.
 45-46 = APPROACH LAMPS.
 450-460 = { PERMISSIVE LAMPS - FIG'S. 1-2-6-7-10 & 17.
 CAUTION LAMPS - FIG'S. 8-9-13-18 & 19.
 90-91 = CLEAR LAMPS.
 M = MARKER LAMP

(M)

TOP ARM (WITH MARKER LIGHT,
 WHERE BOTTOM ARM
 IS NOT USED.)

FIGURE NUMBER	WHEN SIGNAL IS	THESE TERMINALS ARE SPARE	FIGURE NUMBER	WHEN SIGNAL IS	THESE TERMINALS ARE SPARE	FIGURE NUMBER	WHEN SIGNAL IS	THESE TERMINALS ARE SPARE	FIGURE NUMBER	WHEN SIGNAL IS	THESE TERMINALS ARE SPARE
1		M ₁ -M ₂	7		M ₁ -M ₂ -M ₃ - 45-46	13		M ₁ -M ₃ -0-1- 45-46	19		M ₁ -M ₂ -M ₃ - 0-1-90-91.
2		M ₁ -M ₂ -M ₃	8		M ₁ -M ₃ -0-1	14		M ₁ -M ₃ -90-91- 450-460.	20		M ₁ -M ₃ -45-46- 90-91-450-460.
3		M ₁ -M ₃ -450-460	9		M ₁ -M ₂ -M ₃ - 0-1	15		M ₂ -M ₃ -90-91- 450-460.	21		M ₁ -M ₂ -M ₃ -45- 46-90-91-450-460.
4		M ₂ -M ₃ -450-460	10		M ₁ -M ₂ -M ₃ - 90-91	16		M ₁ -M ₂ -M ₃ - 90-91-450-460.	NOTE: WHERE NO "LIGHT-OUT" RELAY IS USED "B OR ACB" TO TERMINAL "N" SHALL BE OMITTED AND "N" SHALL BE CONNECTED TO TERMINAL "0-1."		
5		M ₁ -M ₂ -M ₃ - 450-460	11		M ₁ -M ₂ -45-46- 450-460.	17		M ₁ -M ₂ -M ₃ - 45-46-90-91			
6		M ₁ -M ₂ -45-46	12		M ₁ -M ₂ -M ₃ - 45-46-450-460	18		M ₁ -M ₃ -0-1- 90-91.			

REVISIONS.

3-3-25. FIGURES 1, 6,
 11 & 20 ADDED.
 APPROVED:
 REDRAWN FROM SHEETS 12, 3,
 & 4 OF PLAN S-858 DATED 8-1-23.
 SH.1 LAST REVISED 11-9-23.

SHEET 1 OF 2

S-858


PENNSYLVANIA RAILROAD SYSTEM
 STANDARD
**ARRANGEMENT OF TERMINALS IN TERMINAL
 BOX OF POSITION LIGHT SIGNAL**

OFFICE OF CHIEF SIGNAL ENGINEER,
 PHILA., PA., MAR. 3, 1925

Approved Chief Signal Engineer

Approved NOT TO SCALE
 Chief Engineer

460 91 46
N
45 90 450




N = NEUTRAL LAMP.
45-46 = SLOW SPEED LAMPS.
450-460 = CAUTION SLOW SPEED LAMPS.
90-91 = RESTRICTING LAMPS.

BOTTOM ARM.

BOTTOM ARM.						DWARF SIGNAL.					
FIGURE NUMBER	WHEN SIGNAL IS	THESE TERMINALS ARE SPARE	FIGURE NUMBER	WHEN SIGNAL IS	THESE TERMINALS ARE SPARE	FIGURE NUMBER	WHEN SIGNAL IS	THESE TERMINALS ARE SPARE	FIGURE NUMBER	WHEN SIGNAL IS	THESE TERMINALS ARE SPARE
24		—	30		90-91				42		—
25		—	31		90-91				43		—
26		45-46	32		90-91-450-460				44		—
27		45-46	33		45-46-90-91				45		90
28		450-460	34		N-45-46-90-91. WIRE "N" SHALL BE CONNECTED TO TERMINAL 450-460.				46		45
29		45-46-450-460									

90 45
0 1



0-1 = STOP LAMPS.
0-45 = SLOW SPEED LAMPS.
0-90 = CLEAR SLOW SPEED LAMPS.
1-90 = CAUTION SLOW SPEED LAMPS.

DWARF SIGNAL.

REVISIONS.

3-3-25. FIGURES 25, 26, 30, 31 & 33 ADDED.
APPROVED: *Att. Road*
REDRAWN FROM SHEETS 5 & 7 OF PLAN S-858 DATED 8-12-21 AND SHEET 8 DATED 7-3-22. SHEET 6 MADE OBSOLETE.

SHEET 2 OF 2

S-858




PENNSYLVANIA RAILROAD SYSTEM STANDARD ARRANGEMENT OF TERMINALS IN TERMINAL BOX OF POSITION LIGHT SIGNAL

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., MAR. 8, 1925

Approved *Att. Road*
Chief Signal Engineer

NOT TO SCALE
Approved *J. J. Murray*
Asst. Chief Engineer



SPRING PUSH BUTTON - NOT TO BE OPERATED EXCEPT WHEN CLOSING STATION. SHALL BE INSTALLED IN VERTICAL POS.

NOTE:-
IN CLOSING INTERLOCKING SWITCH LEVERS SHALL BE PLACED IN NORMAL POSITION AND LEVERS CONTROLLING HIGH SIGNALS REVERSED AND PUSH BUTTON 2-12 OPERATED.

WHERE POLARIZED "SS" CIRCUITS IN ACCORDANCE WITH PLAN S-852, SH. 2 ARE PROVIDED, SIGNAL CONTROL CIRCUITS SHALL BE ARRANGED AS SHOWN ABOVE.

REVISIONS

1 SHEET
S-859

THE PENNSYLVANIA RAILROAD
TYPICAL
**CIRCUITS FOR INTERLOCKING
OPERATED PART TIME**



OFFICE OF CHIEF SIGNAL ENGINEER
PHILA., PA., NOV. 30, 1935.

Approved *[Signature]*
Chief Signal Engineer

NOT TO SCALE.

Approved *[Signature]*
Acting Chief Engineer

SEE
SHEET
12

[illegible]

NOTE:
AUTHORIZED SPEED OVER CROSSING - 15 M.P.H.

CROSSING SIGNALS - POSITION LIGHT TYPE
DWARF SIGNALS MOUNTED NOT LESS THAN 3 FEET
ABOVE TOP OF RAIL.

WHERE RELIABLE A.C. POWER IS NOT AVAILABLE
AND CONDITIONS WARRANT D.C. POWER MAY BE
PROVIDED.

FOR LINES OF
LIGHT TRAFFIC

REVISIONS



THE PENNSYLVANIA RAILROAD
TYPICAL
CIRCUITS FOR AUTOMATIC INTERLOCKING
AT RAILROAD GRADE CROSSING

OFFICE OF CHIEF ENGINEER,
PHILA., PA., NOVEMBER 4, 1948.


APPROVED:
H. C. Griffith
ASST. CHIEF ENGINEER - T.C.S.

APPROVED:
J. H. Smith
CHIEF ENGINEER

Fig. 1A


CL1+ CL1-
CL2+ CL2-
EACH BATTERY SHALL CONSIST OF TWENTY (20) TYPE HA-1000 CELLS. WHERE FIG. 2A IS USED AND MORE THAN 8 LAMPS ARE PROVIDED TYPE HA-1302 CELLS SHALL BE USED. (SEE NOTE 12)
PRIMARY BATTERY OPERATION WHERE A.C. POWER IS NOT AVAILABLE.

FIGURE 1A




PRIMARY BATTERY SHALL CONSIST OF TWENTY (20) TYPE HA CELLS. WHERE NOT MORE THAN 8 LAMPS ARE PROVIDED USE TYPE HA-1000 CELLS. WHERE MORE THAN 8 LAMPS ARE PROVIDED USE HA-1302 CELLS. (SEE NOTE 12)
FOR USE WHERE A.C. SUPPLY IS AVAILABLE AND PRIMARY BATTERY STANDBY IS PROVIDED.

FIGURE 1B




WHERE CONDITIONS WARRANT TWO RATE CHARGE RELAY, AS SHOWN IN FIG. 1D, MAY BE PROVIDED.
FOR USE WHERE A.C. SUPPLY IS AVAILABLE AND STORAGE BATTERY STANDBY IS PROVIDED.

FIGURE 1C



FOR USE WHERE AUTOMATIC CROSSING GATES ARE PROVIDED. WHERE MORE THAN TWO GATE MECHANISMS ARE REQUIRED ARRANGEMENT SHOWN ABOVE MAY BE PROVIDED FOR CONTROL OF GATE MECHANISMS AND A SEPARATE BATTERY PROVIDED FOR OTHER D.C. APPARATUS AND FLASHING LIGHT SIGNALS.

FIGURE 1D



BATTERY CHARGING ARRANGEMENT WHICH MAY BE USED IN LIEU OF ARRANGEMENT SHOWN FOR CHARGING BATTERIES IN FIGURES 1C & 1D.

FIGURE 1E

REF. 2A-3376 FOR NF FLASHERS. RECTIFIERS ARE FURNISHED AS STANDARD EQUIPMENT WITH FNIG & FNIGA RELAYS.

APPLICATION OF RECTIFIER FOR ELIMINATION OF RADIO INTERFERENCE.

FIGURE 1F

TWO RATE CHARGE RELAY. DNL-46L FOR LEAD CELLS. REF. 2A-3336. DNL-46E FOR NICKEL-IRON CELLS. U.S. & S. CO. PLATE E5078, REF. B8, PGE. 214-415.

NOTES:-

- FLASHING LIGHT CROSSING SIGNALS SHALL BE INSTALLED IN ACCORDANCE WITH PLAN S-463.
- AUTOMATIC CROSSING GATES SHALL BE INSTALLED IN ACCORDANCE WITH PLAN S-462.
- TRACK CIRCUITS SHOWN ARE TYPICAL. DETAIL ARRANGEMENT OF TRACK CIRCUITS MUST BE MADE FOR EACH INSTALLATION TO SUIT LOCAL CONDITIONS AND REQUIREMENTS.
- A SHORT TRACK CIRCUIT SHALL BE PROVIDED OVER HIGHWAY CROSSINGS TO OPERATE SIGNALS (AND GATES) WHEN TRAIN BLOCKS CROSSING:
 - IN SINGLE TRACK TERRITORY.
 - IN TERRITORY WHERE RULE 261 IS IN EFFECT.
- TO COMPLY WITH STATE OR LOCAL REQUIREMENTS.
- WHERE WARRANTED BY NUMBER OF REVERSE MOVEMENTS WITH TRAIN ORDERS.
- AT OTHER LOCATIONS (EXCEPT WHERE AUTOMATIC GATES ARE INSTALLED) SHORT TRACK CIRCUITS MAY BE OMITTED AND INSULATING RAIL JOINTS SHALL BE LOCATED EAST (OR NORTH) OF CROSSING FOR EASTWARD (OR NORTHWARD) TRACKS AND WEST (OR SOUTH) OF CROSSING FOR WESTWARD (OR SOUTHWARD) TRACKS.

5. (a) THE LOCATION OF INSULATING JOINTS, ESTABLISHING TRACK CIRCUITS FOR INITIATING THE OPERATION OF HIGHWAY CROSSING PROTECTION, SHOULD BE ESTABLISHED, INSOFAR AS PRACTICABLE, TO PROVIDE A STARTING TIME OF 30 SECONDS BUT NOT TO EXCEED 50 SECONDS.

(b) THE STARTING TIME OF 30 SECONDS SHOULD BE BASED ON A MAXIMUM SPEED AS OUTLINED IN THE FOLLOWING:-

1. WHERE SPEEDS OF 100 MILES PER HOUR MAY BE ATTAINED AND IT IS ANTICIPATED SUCH SPEEDS WILL BE ATTAINED - MAXIMUM SPEED: 100 MILES PER HOUR.

2. WHERE SPEED UNDER (1) IS NOT CONTEMPLATED - MAXIMUM AUTHORIZED SPEED.

(c) IN ESTABLISHING STARTING SECTIONS EXISTING CUT-SECTIONS AND SIGNAL LOCATIONS SHALL BE UTILIZED WHEREVER PRACTICABLE AND, IN ORDER TO TAKE ADVANTAGE OF THESE LOCATIONS, THE MINIMUM STARTING TIME OF 30 SECONDS MAY BE REDUCED TO NOT EXCEEDING 10%.

1. WHERE THE DISTANCE FROM THE MOST REMOTE CROSSING SIGNAL TO CLEARANCE OF THE FARTHEST TRACK, AS MEASURED PARALLEL TO THE CENTER LINE OF THE HIGHWAY, IS MORE THAN 35 FEET THE MINIMUM TIME SHALL BE INCREASED BY ONE SECOND FOR EACH ADDITIONAL 5 FEET.

(d) WHERE TRACK CIRCUIT LOCATIONS ARE ESTABLISHED OR WHERE EXISTING TRACK CIRCUIT LOCATIONS ARE UTILIZED FOR OBTAINING A STARTING TIME FOR CONTEMPLATED INCREASE OF MAXIMUM AUTHORIZED SPEEDS, STARTING TIME FOR THE MAXIMUM AUTHORIZED SPEED IN EFFECT IS TO BE OBTAINED BY THE USE OF APPROVED RETARDING DEVICE OR DEVICES.

(e) ANY EXCEPTION, TO THE ABOVE, AS MAY BE REQUIRED TO MEET STATE OR LOCAL AUTHORITIES, SHOULD BE AGREED TO ONLY AFTER FULL DELIBERATION AND COMPLETE RECORD OF NEGOTIATIONS SHOULD BE KEPT IN FILE INDICATING REASONS FOR NOT

ACCEPTING STANDARDS PRESCRIBED.
6. WHERE SHORT TRACK CIRCUIT IS PROVIDED OVER CROSSING INSULATING RAIL JOINTS SHALL BE LOCATED PREFERABLY TO FEET EACH SIDE OF CROSSING BUT NOT IN EXCESS OF 100 FEET. WHERE DUE TO LOCAL CONDITIONS, INSULATING JOINTS SHOULD BE LOCATED A GREATER DISTANCE, APPROVAL OF THE CHIEF ENGINEER SHOULD BE OBTAINED.

7. INSULATING RAIL JOINTS SHALL BE PLACED IN ACCORDANCE WITH CURRENT ISSUE OF C.E. 78.

8. CIRCUITS FOR OPERATION OF AUTOMATIC CROSSING GATES SHALL BE SO ARRANGED THAT GATES WILL START TO ASSUME HORIZONTAL POSITION BETWEEN 3 AND 5 SECONDS AFTER FLASHING LIGHT SIGNALS START TO OPERATE.

9. EACH SIGNAL SHALL BE PROVIDED WITH TWO RETURN WIRES. WIRES BETWEEN INSTRUMENT CASE AND SIGNALS SHALL BE NO. 9 A.W.G.

10. WHERE LINE WIRES ARE REQUIRED FOR CONTROL OF CROSSING SIGNALS, TWO WIRE DOUBLE BREAK CIRCUITS SHALL BE PROVIDED.

11. TYPE AND CAPACITY OF STORAGE BATTERIES SHALL BE IN ACCORDANCE WITH LETTER OF GENERAL PRACTICE NO. 220-C.

12. BATTERIES SHALL BE HOUSED, IN INSULATED BATTERY BOXES, IN CONCRETE BOXES BELOW GROUND OR IN HEATED BUILDINGS.

13. RECOMMENDED VOLTAGE AT LAMPS APPROXIMATELY 12.0V, MINIMUM 11.5V, MAXIMUM 13.0V, AND CIRCUITS ADJUSTED TO GIVE THE SAME VOLTAGE FOR LAMPS ON EACH SIGNAL.

14. TEST SWITCHES SHALL BE PROVIDED WHERE DESIGNATED EMPLOYEES ARE AUTHORIZED TO TEST CROSSING SIGNALS AND SHALL BE ACCESSIBLE TO ONLY SUCH EMPLOYEES. SWITCHES SHALL NOT BE LOCATED IN INSTRUMENT CASES AND MUST BE INSTALLED SO THAT SWITCH IS CLOSED WHEN DOOR OF HOUSING IS CLOSED.

15. A POWER-OFF INDICATION LAMP SHALL BE LOCATED ON INSTRUMENT CASE AT HIGHWAY CROSSING LOCATIONS, WHERE A.C. POWER IS AVAILABLE USE LAMP 4837, REF. 25E-4322. WHERE FIG. 1A IS PROVIDED USE LAMP 4832, REF. 25E-4211, WITH ADAPTOR, OMITTING 200 OHM RESISTOR. LAMPS SHALL BE PLACED IN U.S. & S. CO. HP-10 PILOT-LIGHT, PLATE K-137, REF. A, OMITTING LENS SHIELD FIG. 3 AND TO BE EQUIPPED WITH WHITE LENS.

16. OVERLOAD CIRCUIT BREAKERS OF APPROVED TYPE MAY BE USED IN PLACE OF FUSES MARKED *. IF COMMERCIAL CO'S. FUSES ARE PROVIDED WHERE CONNECTION IS MADE, FUSES MARKED * SHALL BE OMITTED.

17. SIGNALS SHALL NOT BE LIGHTED EXCEPT FOR APPROACHING TRAINS WHEN RED LIGHTS FLASHING ALTERNATELY (30 TO 45 TIMES PER MINUTE) SHALL BE DISPLAYED.

POWER SUPPLY & NOTES.

SHEET 1 OF 7



THE PENNSYLVANIA RAILROAD
TYPICAL
CIRCUITS FOR AUTOMATIC HIGHWAY
CROSSING SIGNALS AND GATES

OFFICE OF CHIEF ENGINEER, PHILA., PA., DEC. 30, 1948. NOT TO SCALE



APPROVED:


[Signature]
ASST. CHIEF ENGINEER, T.C.-3.


APPROVED:

[Signature]
CHIEF ENGINEER

S-860








WIRING FOR GATE MECHANISM 3564
CLEAR DRIVE ONLY

FIGURE 4A


CIRCUIT CONTROLLER FUNCTIONS - FIGURES 4A & 4B			
SPACE NUMBER	USE OF CONTROLLER	CONTACT OPERATION	CAM DRIVES CONTACT
0	TO OPEN MOTOR CIRCUIT DOWN (FIG. 4B)	46° TO 93°	OPEN
1	SPARE	86° TO 93°	CLOSED
2	TO CONTROL OF RELAY GTNR	86° TO 93°	CLOSED
3	TO PULL UP SLOT MAGNET	86° TO 93°	CLOSED
4	TO CUT OFF MOTOR AFTER GATE HAS CLEARED	0° TO 83° UP 83° TO 0° DOWN	CLOSED
5	TO CLOSE HEAVY SNUB CIRCUIT AS GATE ARM APPROACHES HORIZONTAL	0° TO 10°	CLOSED
6	TO OPEN BELL CIRCUIT WHEN GATE IS HORIZONTAL	10° TO 93°	OPEN
7	SPARE	0° TO 10°	CLOSED
8	SPARE	0° TO 89°	OPEN
9	SPARE	0° TO 89°	OPEN



WIRING FOR GATE MECHANISM 3564
CLEAR DRIVE AND DOWN DRIVE

FIGURE 4B

WIRING FOR TYPE 3564
GATE MECHANISMS
AND
TYPE 3561-216L INDEPENDENT
SIDEWALK GATE MECHANISMS



WIRING FOR INDEPENDENT SIDEWALK GATE MECHANISM 3561-216L
CLEAR DRIVE ONLY

FIGURE 4C

NOTE:-
WIRES BETWEEN BATTERY AND GATE MOTOR
SHALL NOT BE SMALLER THAN NO. 9 A.W.G.
WHERE TOTAL LENGTH OF WIRE IN CIRCUIT,
BATTERY AND COMMON SIDE, EXCEEDS 120',
USE NO. 6 A.W.G. OR EQUIVALENT UP TO 240'.
THE FOLLOWING NUMBER OF CELLS ARE
RECOMMENDED:-

GATE ARM LENGTH IN FEET	NO. OF LEAD TYPE CELLS	NO. OF NICKEL-IRON TYPE CELLS
UP TO 24	6	10
25 TO 36	7	11
37 TO 40	8	12

REVISIONS

SHEET 4 OF 7

S-860


THE PENNSYLVANIA RAILROAD
TYPICAL
CIRCUITS FOR AUTOMATIC HIGHWAY
CROSSING SIGNALS AND GATES

OFFICE OF CHIEF ENGINEER,
PHILA., PA., DEC. 30, 1948

NOT TO SCALE


APPROVED:
A. C. Griffith
ASST. CHIEF ENGINEER, T.C.S.

APPROVED:
J. H. ...
CHIEF ENGINEER




DIRECTIONAL CONTROL WHERE SHORT TRACK SECTION OVER CROSSING IS PROVIDED
SEE NOTE 4, SHEET 1

FIGURE 5A




DIRECTIONAL CONTROL WHERE NO SHORT TRACK SECTION OVER CROSSING IS PROVIDED.
SEE NOTE 26, SHEET 1.

FIGURE 5B



MAY BE USED IN STEAM TERRITORY WHERE FIXED SIGNALS ARE NOT CONTROLLED OVER TRACK SECTIONS AIT & BIT.

FIGURE 5C



WHERE MOVEMENTS ON SIDE TRACK ARE SUFFICIENTLY FREQUENT TO GIVE GOOD SHUNTING SENSITIVITY, A 4 OHM DN-11 TRACK RELAY WITH A 10 OHM RESISTOR IN SERIES, FED FROM 1 CELL LEAD STORAGE OR EQUIVALENT IN VOLTAGE, MAY BE USED.

FIGURE 5D




FIGURE 5E

REVISIONS

DIRECTIONAL CONTROLS
AND
SPECIAL TRACK CIRCUITS

SHEET 5 OF 7

S-860

THE PENNSYLVANIA RAILROAD
TYPICAL
CIRCUITS FOR AUTOMATIC HIGHWAY
CROSSING SIGNALS AND GATES

OFFICE OF CHIEF ENGINEER.
PHILA., PA., DEC. 30, 1948.






NOT TO SCALE

APPROVED:

ASST. CHIEF ENGINEER, T-C-5.

APPROVED:

CHIEF ENGINEER



**MISCELLANEOUS
CONTROL CIRCUITS**

REVISIONS

SHEET 6 OF 7

S-860

THE PENNSYLVANIA RAILROAD
TYPICAL
CIRCUITS FOR AUTOMATIC HIGHWAY
CROSSING SIGNALS AND GATES

OFFICE OF CHIEF ENGINEER,
PHILA. PA. DEC. 30, 1948


NOT TO SCALE

APPROVED:

W. C. Griffith
ASST. CHIEF ENGINEER, T-C-3.

APPROVED:

J. Bennett
CHIEF ENGINEER



TIME DELAY CIRCUIT TO PERMIT USE OF EXISTING SIGNAL LOCATIONS OR CUT-SECTIONS FOR STARTING POINTS.

FIGURE 7A




FIGURE 7C
WIRING OF TERMINALS IN JUNCTION BOX ON CROSSARMS

TIME DELAY CIRCUIT AND JUNCTION BOX WIRING

SHEET 7 OF 7

S-860



THE PENNSYLVANIA RAILROAD
TYPICAL
CIRCUITS FOR AUTOMATIC HIGHWAY
CROSSING SIGNALS AND GATES

OFFICE OF CHIEF ENGINEER,
PHILA., PA., DEC. 30, 1948



NOT TO SCALE

APPROVED:

W. C. Griffith
ASST. CHIEF ENGINEER, T.-C.-S.

APPROVED:

W. C. Griffith
CHIEF ENGINEER



NOTE:-
IN AUTOMATIC TERRITORY WHEN SECOND ARM OF HIGH SIGNAL IS DISPLAYED AT 45° L. Q. THE TRACK INDICATING RELAY SHALL INCLUDE ONLY THE FIRST SECTION IN ADVANCE OF THE HOME SIGNAL.
ADDITIONAL TRACK SECTIONS MAY BE INSTALLED WHERE LOCAL TRAFFIC CONDITIONS REQUIRE QUICKER RELEASE OF SWITCHES.
TRACKS ARE ARBITRARILY NUMBERED.
IT SHOULD BE NOTED THAT THE INDICATING RELAY CONTROL IS CARRIED THROUGH ALL TRACK SECTIONS TO THE HOLDING SIGNAL FOR A CONFLICTING MOVEMENT WHERE HIGH OR RESTRICTED SPEED SIGNALS ARE INVOLVED. FOR ILLUSTRATION COMPARE THE CONTROL CIRCUIT FOR RELAY 1A WITH THAT FOR 4A.
WHERE A CROSSOVER MOVEMENT CAN BE MADE ONLY ON A SLOW SPEED SIGNAL (SEMI-AUTOMATIC) THE CONTROL NEED NOT BE TAKEN BEYOND THE SECTION THAT INCLUDES THE FAULTING POINT.
ENERGY FOR REPEATING RELAYS SHALL BE TAKEN FROM BATTERY M2 WHEN INSTRUMENT REPEATED IS LOCATED INSIDE THE CABIN AND FROM NEAREST H BATTERY WHEN INSTRUMENT REPEATED IS LOCATED OUTSIDE THE CABIN. WHEN INSTRUMENT REPEATED IS LOCATED INSIDE OF CABIN, THE REPEATING RELAY SHALL GO DIRECT TO COMMON AS SHOWN DOTTED.
REPEATING INDICATOR OR INDICATION LIGHT MAY BE PROVIDED TO REPEAT RELAYS AZM & A3M IF SO DESIRED.

FOR POSITION LIGHT SIGNALS.

REVISIONS.



1-24-25. LOWER QUADRANT ADDED TO SIGNALS 2R, 4R, 24R, 26R.
APPROVED: *[Signature]*
PREPARED FROM PLAN S-861, SN. 1
DATED 12-13-24.

SHEET 1 OF 2
S-861

PENNSYLVANIA RAILROAD SYSTEM
TYPICAL CONTROL CIRCUITS
FOR TRACK INDICATING RELAYS

OFFICE OF CHIEF SIGNAL ENGINEER
PHILA., PA., JAN. 20, 1925.
Approved: *[Signature]*
Chief Signal Engineer

NOT TO SCALE
Approved: *[Signature]*
Chief Engineer




NOTE: REPEATING INDICATOR OR INDICATION LIGHT MAY BE PROVIDED TO REPEAT RELAYS AIM, A2M, A3M & A4M IF SO DESIRED.
ADDITIONAL TRACK SECTIONS MAY BE INSTALLED WHERE LOCAL TRAFFIC CONDITIONS REQUIRE QUICKER RELEASE OF SWITCHES.

TRACKS ARE ARBITRARILY NUMBERED.
IT SHOULD BE NOTED THAT THE INDICATING RELAY CONTROL IS CARRIED THROUGH ALL TRACK SECTIONS TO THE HOLDING SIGNAL FOR A CONFLICTING MOVEMENT WHERE HIGH OR RESTRICTED SPEED SIGNALS ARE INVOLVED. FOR ILLUSTRATION COMPARE THE CONTROL CIRCUIT FOR RELAY 1A WITH THAT FOR 4A.

WHERE A CROSSOVER MOVEMENT CAN BE MADE ONLY ON A SLOW SPEED SIGNAL (SEMI-AUTOMATIC) THE CONTROL NEED NOT BE TAKEN BEYOND THE SECTION THAT INCLUDES THE FOULING POINT.

ENERGY FOR REPEATING RELAYS SHALL BE TAKEN FROM BATTERY M2 WHEN INSTRUMENT REPEATED IS LOCATED INSIDE THE CABIN AND FROM NEAREST H BATTERY WHEN INSTRUMENT REPEATED IS LOCATED OUTSIDE THE CABIN. WHEN INSTRUMENT REPEATED IS LOCATED INSIDE THE CABIN, THE REPEATING RELAY SHALL GO DIRECT TO COMMON AS SHOWN DOTTED.

WHERE POWER IS OBTAINED FROM PRIMARY OR PORTABLE STORAGE BATTERIES.



WHERE POWER IS OBTAINED FROM SOURCE OTHER THAN PRIMARY OR PORTABLE STORAGE BATTERIES.

SPECIAL MECHANICAL LOCKING

1	LOCKS	17
5	"	9-21
13	"	17
24L	"	5
24R	"	17

FOR MOTOR SIGNALS.

SHEET 2 OF 2

PENNSYLVANIA RAILROAD SYSTEM
TYPICAL CONTROL CIRCUITS
FOR TRACK INDICATING RELAYS

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., JAN. 20, 1925



Approved: *A. H. Reed*
Chief Signal Engineer

NOT TO SCALE


Approved: *[Signature]*
Chief Engineer

REDRAWN FROM PLAN S-861, SH. 2
DATED 12-13-24, LAST REVISED 5-22-29.

S-861



NOTE:-
 1. TRACKS ARE ARBITRARILY NUMBERED.
 2. THE PROVISION OF INDICATORS IAM^a, ZAM^b OR INDICATION LIGHTS 2REL^b AND 12LEL^b IS OPTIONAL.



WHERE POWER IS OBTAINED FROM PRIMARY OR PORTABLE STORAGE BATTERIES.

WHERE POWER IS OBTAINED FROM SOURCE OTHER THAN PRIMARY OR PORTABLE STORAGE BATTERIES.

FOR ARRANGEMENT WHERE AUTOMATIC BLOCK SIGNAL IS LOCATED BEYOND INTERLOCKING LIMITS.

REVISIONS
4-21-28. 1A & 2A FORMERLY CONTROLLED OVER C1 & B2M RESPECTIVELY AND 1AM ^b , 2AM ^b , 2REL ^b & 12LEL ^b ADDED.
APPROVED: <i>[Signature]</i>
REDRAWN FROM PLAN S-861, 3H.3, DATED 9-9-26.

SHEETS OF 3

THE PENNSYLVANIA RAILROAD
 TYPICAL
CONTROL CIRCUITS FOR TRACK INDICATING RELAYS

OFFICE OF CHIEF SIGNAL ENGINEER,
 PHILA., PA., APRIL 21, 1928.

Approved: *[Signature]* Chief Signal Engineer


NOT TO SCALE

Approved: *[Signature]* Chief Engineer

S-861

9 P 4

AUTOMATIC BLOCK NO 1, 3 & 4 TRACK
MANUAL BLOCK NO 2 TRACK.



NOTES:

1. WHERE A FACING POINT SWITCH IS LOCATED WITHIN APPROXIMATELY 600' OF THE ADVANCE SIGNAL "B" CIRCUITS SHALL BE ARRANGED AS SPECIFIED IN NOTE 4 PLAN S-854.
2. BLOCK SIGNALS IN MANUAL BLOCK TERRITORY SHALL BE CONTROLLED IN ACCORDANCE WITH PENNSYLVANIA RAILROAD SYSTEM TYPICAL CIRCUIT PLAN S-854.

SPECIAL MECHANICAL LOCKING

1 LOCKS 17
5 " 9 & 21
13 " 17
24 " 5
24R " 17

SHOULD SIG "B" BE CONTROLLED FROM INTERLOCKING MACHINE, IT SHOULD LOCK SWITCH 2 NORMAL AND THE "B" CONTACT OMITTED IN "B" CONTROL.

REVISIONS

SUPERSEDES SH.1. OF PLAN S-862 DATED 4-10-25. LAST REVISED 6-2-27.

S-862

SHEET 1 OF 2


THE PENNSYLVANIA RAILROAD
TYPICAL CONTROL CIRCUITS
FOR HOME SIGNALS

OFFICE OF CHIEF SIGNAL ENGINEER
PHILA., PA., JANUARY 11, 1926.

Approved: *[Signature]*
Chief Signal Engineer

NOT TO SCALE

Approved: *[Signature]*
Acting Chief Engineer



NOTE:-
 * - CONTACTS SHALL BE OMITTED WHERE NO "LIGHT-OUT" RELAY IS USED.
 WHERE NOT SUFFICIENT CONTACTS ON LEVER OR RELAY, OMIT THOSE MARKED ⊕
 ⊗ - FROM OTHER CONTROLLING APPARATUS (SEE PLAN NO S-862, SHEET 1.)

SPECIAL MECHANICAL LOCKING
 1 LOCKS 17
 5 " 9-21
 6 " 17
 13 " 17
 22 " 5

90° CONTROL CIRCUITS
 (THREE BLOCK INDICATION)

SHEET 3 OF 3

S-862

PENNSYLVANIA RAILROAD SYSTEM
 TYPICAL CONTROL CIRCUITS
 FOR HOME SIGNALS

OFFICE OF CHIEF SIGNAL ENGINEER,
 PHILA. PA., DEC. 13, 1923

Approved: *Ant. K.*
 Chief Signal Engineer

NOT TO SCALE

Approved: *Ant. K.*
 Chief Engineer


REVISIONS

4-13-25. LOWER QUADRANT ASPECTS ADDED TO SIG. P. 4 AND CIRCUITS FOR CLEAR CONTROL RELAYS CHANGED.
 Approved: *Ant. K.*

12-13-23. Note regarding contacts on "Light-out" relays added.
 Approved: *Ant. K.*

Redrawn from Plan S-862, Sheet 3, dated 12-13-20

U.S. & S. CO. - TYPE "T2"
LOW VOLTAGE




CIRCUIT BREAKER OPERATION U.S. & S. CO. - TYPE "T2"					
CONTACT SPACE NUMBER	GOING TO CLEAR		GOING TO STOP		REMARKS
	CLOSES	OPENS	CLOSES	OPENS	
1					POLE CHANGER OPERATES AT 85°
2					
3		5°	2°		INDICATION.
4		50°	47°		
5	40°		37°		CLEAR CONTROL RELAY.
6	40°	50°	47°		45° HOLDING.
7	40°		37°		DISTANT SIGNAL CONTROL.
8	40°	5°	2°		CALLING-ON CONTROL.
9	40°		37°		DISTANT SIGNAL CONTROL.
10	40°		37°		DISTANT SIGNAL RETURN.
11	40°		37°		45° OPERATING.
12	40°		37°		90° OPERATING.

NOTE:-
FOR WIRING 2 POSITION SIGNALS - 0° - 45°, OMIT WIRES "2J" AND "2JB."
FOR WIRING 2 POSITION SIGNALS - 0° - 90°, OMIT WIRES "2J" AND "2JB."
CONNECT WIRE "2H" TO UPPER LEFT HAND TERMINAL OF CONTACT 5 AND TAKE BATTERY (H) DIRECT ON BOTH RIGHT HAND SPRINGS OF SEGMENT 8.
CIRCUIT CONTROLLER SHAFT MOVES 3 TIMES THE SPEED OF THE SEMAPHORE IN THE OPPOSITE DIRECTION; HENCE, 90° OF SEMAPHORE IS EQUIVALENT TO 270° MOVEMENT OF CIRCUIT CONTROLLER SEGMENT.
* = 20 OHMS FOR HIGH SIGNALS. 7 OHMS FOR DWARF SIGNALS.
GOING TO CLEAR - CLOSES AT 40° - OPENS AT 75°.
GOING TO STOP - CLOSES AT 72° - OPENS AT 37°.

CIRCUIT BREAKER OPERATION G. R. S. CO. - TYPE "2A"					
CONTACT SPACE NUMBER	GOING TO CLEAR		GOING TO STOP		REMARKS
	CLOSES	OPENS	CLOSES	OPENS	
1					SNAP.
3	40°		40°		CLEAR CONTROL RELAY.
5		45°	45°		45° OPERATING.
7	40°	88°	88°	40°	90° OPERATING.
9		47°	47°		45° HOLDING.
11		5°	5°		SLIP CONTACT SHUNT.
13					OPENS AFTER 2° ROTATION. CLOSES AFTER 2° ROTATION. SLIP CONTACT - SHUNTS HIGH RESISTANCE COIL.
2					POLE CHANGER OPERATES AT 85° SNAP.
4	85°		85°		DISTANT SIGNAL CONTROL.
6	40°		40°		DISTANT SIGNAL RETURN.
8	40°		40°		DISTANT SIGNAL CONTROL.
10		5°	5°		INDICATION.
12		5°	5°		CALLING-ON CONTROL.
14	55°	30°	30°	55°	SNUB CONTACT.

NOTE:-
FOR WIRING 2 POSITION SIGNALS - 0° - 45°, OMIT WIRES "2J" AND "2JB."
FOR WIRING 2 POSITION SIGNALS - 0° - 90°, OMIT WIRES "2J" AND "2JB."
CONNECT WIRE "2H" TO LOWER CONTACT SPRING AND CONNECT BATTERY (H) DIRECT TO BOTH UPPER CONTACT SPRINGS 5 AND 7.
X = SNUB RESISTANCE - 3 OHMS.
GOING TO CLEAR - CLOSES AT 40° - OPENS AT 75°.
GOING TO STOP - CLOSES AT 75° - OPENS AT 40°.




REVISIONS

1. 2. 3. 4. 5. 6. 7. 8. 9. 10. 11. 12. 13. 14. 15. 16. 17. 18. 19. 20. 21. 22. 23. 24. 25. 26. 27. 28. 29. 30. 31. 32. 33. 34. 35. 36. 37. 38. 39. 40. 41. 42. 43. 44. 45. 46. 47. 48. 49. 50. 51. 52. 53. 54. 55. 56. 57. 58. 59. 60. 61. 62. 63. 64. 65. 66. 67. 68. 69. 70. 71. 72. 73. 74. 75. 76. 77. 78. 79. 80. 81. 82. 83. 84. 85. 86. 87. 88. 89. 90. 91. 92. 93. 94. 95. 96. 97. 98. 99. 100. 101. 102. 103. 104. 105. 106. 107. 108. 109. 110. 111. 112. 113. 114. 115. 116. 117. 118. 119. 120. 121. 122. 123. 124. 125. 126. 127. 128. 129. 130. 131. 132. 133. 134. 135. 136. 137. 138. 139. 140. 141. 142. 143. 144. 145. 146. 147. 148. 149. 150. 151. 152. 153. 154. 155. 156. 157. 158. 159. 160. 161. 162. 163. 164. 165. 166. 167. 168. 169. 170. 171. 172. 173. 174. 175. 176. 177. 178. 179. 180. 181. 182. 183. 184. 185. 186. 187. 188. 189. 190. 191. 192. 193. 194. 195. 196. 197. 198. 199. 200. 201. 202. 203. 204. 205. 206. 207. 208. 209. 210. 211. 212. 213. 214. 215. 216. 217. 218. 219. 220. 221. 222. 223. 224. 225. 226. 227. 228. 229. 230. 231. 232. 233. 234. 235. 236. 237. 238. 239. 240. 241. 242. 243. 244. 245. 246. 247. 248. 249. 250. 251. 252. 253. 254. 255. 256. 257. 258. 259. 260. 261. 262. 263. 264. 265. 266. 267. 268. 269. 270. 271. 272. 273. 274. 275. 276. 277. 278. 279. 280. 281. 282. 283. 284. 285. 286. 287. 288. 289. 290. 291. 292. 293. 294. 295. 296. 297. 298. 299. 300. 301. 302. 303. 304. 305. 306. 307. 308. 309. 310. 311. 312. 313. 314. 315. 316. 317. 318. 319. 320. 321. 322. 323. 324. 325. 326. 327. 328. 329. 330. 331. 332. 333. 334. 335. 336. 337. 338. 339. 340. 341. 342. 343. 344. 345. 346. 347. 348. 349. 350. 351. 352. 353. 354. 355. 356. 357. 358. 359. 360. 361. 362. 363. 364. 365. 366. 367. 368. 369. 370. 371. 372. 373. 374. 375. 376. 377. 378. 379. 380. 381. 382. 383. 384. 385. 386. 387. 388. 389. 390. 391. 392. 393. 394. 395. 396. 397. 398. 399. 400. 401. 402. 403. 404. 405. 406. 407. 408. 409. 410. 411. 412. 413. 414. 415. 416. 417. 418. 419. 420. 421. 422. 423. 424. 425. 426. 427. 428. 429. 430. 431. 432. 433. 434. 435. 436. 437. 438. 439. 440. 441. 442. 443. 444. 445. 446. 447. 448. 449. 450. 451. 452. 453. 454. 455. 456. 457. 458. 459. 460. 461. 462. 463. 464. 465. 466. 467. 468. 469. 470. 471. 472. 473. 474. 475. 476. 477. 478. 479. 480. 481. 482. 483. 484. 485. 486. 487. 488. 489. 490. 491. 492. 493. 494. 495. 496. 497. 498. 499. 500. 501. 502. 503. 504. 505. 506. 507. 508. 509. 510. 511. 512. 513. 514. 515. 516. 517. 518. 519. 520. 521. 522. 523. 524. 525. 526. 527. 528. 529. 530. 531. 532. 533. 534. 535. 536. 537. 538. 539. 540. 541. 542. 543. 544. 545. 546. 547. 548. 549. 550. 551. 552. 553. 554. 555. 556. 557. 558. 559. 560. 561. 562. 563. 564. 565. 566. 567. 568. 569. 570. 571. 572. 573. 574. 575. 576. 577. 578. 579. 580. 581. 582. 583. 584. 585. 586. 587. 588. 589. 590. 591. 592. 593. 594. 595. 596. 597. 598. 599. 600. 601. 602. 603. 604. 605. 606. 607. 608. 609. 610. 611. 612. 613. 614. 615. 616. 617. 618. 619. 620. 621. 622. 623. 624. 625. 626. 627. 628. 629. 630. 631. 632. 633. 634. 635. 636. 637. 638. 639. 640. 641. 642. 643. 644. 645. 646. 647. 648. 649. 650. 651. 652. 653. 654. 655. 656. 657. 658. 659. 660. 661. 662. 663. 664. 665. 666. 667. 668. 669. 670. 671. 672. 673. 674. 675. 676. 677. 678. 679. 680. 681. 682. 683. 684. 685. 686. 687. 688. 689. 690. 691. 692. 693. 694. 695. 696. 697. 698. 699. 700. 701. 702. 703. 704. 705. 706. 707. 708. 709. 710. 711. 712. 713. 714. 715. 716. 717. 718. 719. 720. 721. 722. 723. 724. 725. 726. 727. 728. 729. 730. 731. 732. 733. 734. 735. 736. 737. 738. 739. 740. 741. 742. 743. 744. 745. 746. 747. 748. 749. 750. 751. 752. 753. 754. 755. 756. 757. 758. 759. 760. 761. 762. 763. 764. 765. 766. 767. 768. 769. 770. 771. 772. 773. 774. 775. 776. 777. 778. 779. 780. 781. 782. 783. 784. 785. 786. 787. 788. 789. 790. 791. 792. 793. 794. 795. 796. 797. 798. 799. 800. 801. 802. 803. 804. 805. 806. 807. 808. 809. 810. 811. 812. 813. 814. 815. 816. 817. 818. 819. 820. 821. 822. 823. 824. 825. 826. 827. 828. 829. 830. 831. 832. 833. 834. 835. 836. 837. 838. 839. 840. 841. 842. 843. 844. 845. 846. 847. 848. 849. 850. 851. 852. 853. 854. 855. 856. 857. 858. 859. 860. 861. 862. 863. 864. 865. 866. 867. 868. 869. 870. 871. 872. 873. 874. 875. 876. 877. 878. 879. 880. 881. 882. 883. 884. 885. 886. 887. 888. 889. 890. 891. 892. 893. 894. 895. 896. 897. 898. 899. 900. 901. 902. 903. 904. 905. 906. 907. 908. 909. 910. 911. 912. 913. 914. 915. 916. 917. 918. 919. 920. 921. 922. 923. 924. 925. 926. 927. 928. 929. 930. 931. 932. 933. 934. 935. 936. 937. 938. 939. 940. 941. 942. 943. 944. 945. 946. 947. 948. 949. 950. 951. 952. 953. 954. 955. 956. 957. 958. 959. 960. 961. 962. 963. 964. 965. 966. 967. 968. 969. 970. 971. 972. 973. 974. 975. 976. 977. 978. 979. 980. 981. 982. 983. 984. 985. 986. 987. 988. 989. 990. 991. 992. 993. 994. 995. 996. 997. 998. 999. 1000. 1001. 1002. 1003. 1004. 1005. 1006. 1007. 1008. 1009. 1010. 1011. 1012. 1013. 1014. 1015. 1016. 1017. 1018. 1019. 1020. 1021. 1022. 1023. 1024. 1025. 1026. 1027. 1028. 1029. 1030. 1031. 1032. 1033. 1034. 1035. 1036. 1037. 1038. 1039. 1040. 1041. 1042. 1043. 1044. 1045. 1046. 1047. 1048. 1049. 1050. 1051. 1052. 1053. 1054. 1055. 1056. 1057. 1058. 1059. 1060. 1061. 1062. 1063. 1064. 1065. 1066. 1067. 1068. 1069. 1070. 1071. 1072. 1073. 1074. 1075. 1076. 1077. 1078. 1079. 1080. 1081. 1082. 1083. 1084. 1085. 1086. 1087. 1088. 1089. 1090. 1091. 1092. 1093. 1094. 1095. 1096. 1097. 1098. 1099. 1100. 1101. 1102. 1103. 1104. 1105. 1106. 1107. 1108. 1109. 1110. 1111. 1112. 1113. 1114. 1115. 1116. 1117. 1118. 1119. 1120. 1121. 1122. 1123. 1124. 1125. 1126. 1127. 1128. 1129. 1130. 1131. 1132. 1133. 1134. 1135. 1136. 1137. 1138. 1139. 1140. 1141. 1142. 1143. 1144. 1145. 1146. 1147. 1148. 1149. 1150. 1151. 1152. 1153. 1154. 1155. 1156. 1157. 1158. 1159. 1160. 1161. 1162. 1163. 1164. 1165. 1166. 1167. 1168. 1169. 1170. 1171. 1172. 1173. 1174. 1175. 1176. 1177. 1178. 1179. 1180. 1181. 1182. 1183. 1184. 1185. 1186. 1187. 1188. 1189. 1190. 1191. 1192. 1193. 1194. 1195. 1196. 1197. 1198. 1199. 1200. 1201. 1202. 1203. 1204. 1205. 1206. 1207. 1208. 1209. 1210. 1211. 1212. 1213. 1214. 1215. 1216. 1217. 1218. 1219. 1220. 1221. 1222. 1223. 1224. 1225. 1226. 1227. 1228. 1229. 1230. 1231. 1232. 1233. 1234. 1235. 1236. 1237. 1238. 1239. 1240. 1241. 1242. 1243. 1244. 1245. 1246. 1247. 1248. 1249. 1250. 1251. 1252. 1253. 1254. 1255. 1256. 1257. 1258. 1259. 1260. 1261. 1262. 1263. 1264. 1265. 1266. 1267. 1268. 1269. 1270. 1271. 1272. 1273. 1274. 1275. 1276. 1277. 1278. 1279. 1280. 1281. 1282. 1283. 1284. 1285. 1286. 1287. 1288. 1289. 1290. 1291. 1292. 1293. 1294. 1295. 1296. 1297. 1298. 1299. 1300. 1301. 1302. 1303. 1304. 1305. 1306. 1307. 1308. 1309. 1310. 1311. 1312. 1313. 1314. 1315. 1316. 1317. 1318. 1319. 1320. 1321. 1322. 1323. 1324. 1325. 1326. 1327. 1328. 1329. 1330. 1331. 1332. 1333. 1334. 1335. 1336. 1337. 1338. 1339. 1340. 1341. 1342. 1343. 1344. 1345. 1346. 1347. 1348. 1349. 1350. 1351. 1352. 1353. 1354. 1355. 1356. 1357. 1358. 1359. 1360. 1361. 1362. 1363. 1364. 1365. 1366. 1367. 1368. 1369. 1370. 1371. 1372. 1373. 1374. 1375. 1376. 1377. 1378. 1379. 1380. 1381. 1382. 1383. 1384. 1385. 1386. 1387. 1388. 1389. 1390. 1391. 1392. 1393. 1394. 1395. 1396. 1397. 1398. 1399. 1400. 1401. 1402. 1403. 1404. 1405. 1406. 1407. 1408. 1409. 1410. 1411. 1412. 1413. 1414. 1415. 1416. 1417. 1418. 1419. 1420. 1421. 1422. 1423. 1424. 1425. 1426. 1427. 1428. 1429. 1430. 1431. 1432. 1433. 1434. 1435. 1436. 1437. 1438. 1439. 1440. 1441. 1442. 1443. 1444. 1445. 1446. 1447. 1448. 1449. 1450. 1451. 1452. 1453. 1454. 1455. 1456. 1457. 1458. 1459. 1460. 1461. 1462. 1463. 1464. 1465. 1466. 1467. 1468. 1469. 1470. 1471. 1472. 1473. 1474. 1475. 1476. 1477. 1478. 1479. 1480. 1481. 1482. 1483. 1484. 1485. 1486. 1487. 1488. 1489. 1490. 1491. 1492. 1493. 1494. 1495. 1496. 1497. 1498. 1499. 1500. 1501. 1502. 1503. 1504. 1505. 1506. 1507. 1508. 1509. 1510. 1511. 1512. 1513. 1514. 1515. 1516. 1517. 1518. 1519. 1520. 1521. 1522. 1523. 1524. 1525. 1526. 1527. 1528. 1529. 1530. 1531. 1532. 1533. 1534. 1535. 1536. 1537. 1538. 1539. 1540. 1541. 1542. 1543. 1544. 1545. 1546. 1547. 1548. 1549. 1550. 1551. 1552. 1553. 1554. 1555. 1556. 1557. 1558. 1559. 1560. 1561. 1562. 1563. 1564. 1565. 1566. 1567. 1568. 1569. 1570. 1571. 1572. 1573. 1574. 1575. 1576. 1577. 1578. 1579. 1580. 1581. 1582. 1583. 1584. 1585. 1586. 1587. 1588. 1589. 1590. 1591. 1592. 1593. 1594. 1595. 1596. 1597. 1598. 1599. 1600. 1601. 1602. 1603. 1604. 1605. 1606. 1607. 1608. 1609. 1610. 1611. 1612. 1613. 1614. 1615. 1616. 1617. 1618. 1619. 1620. 1621. 1622. 1623. 1624. 1625. 1626. 1627. 1628. 1629. 1630. 1631. 1632. 1633. 1634. 1635. 1636. 1637. 1638. 1639. 1640. 1641. 1642. 1643. 1644. 1645. 1646. 1647. 1648. 1649. 1650. 1651. 1652. 1653. 1654. 1655. 1656. 1657. 1658. 1659. 1660. 1661. 1662. 1663. 1664. 1665. 1666. 1667. 1668. 1669. 1670. 1671. 1672. 1673. 1674. 1675. 1676. 1677. 1678. 1679. 1680. 1681. 1682. 1683. 1684. 1685. 1686. 1687. 1688. 1689. 1690. 1691. 1692. 1693. 1694. 1695. 1696. 1697. 1698. 1699. 1700. 1701. 1702. 1703. 1704. 1705. 1706. 1707. 1708. 1709. 1710. 1711. 1712. 1713. 1714. 1715. 1716. 1717. 1718. 1719. 1720. 1721. 1722. 1723. 1724. 1725. 1726. 1727. 1728. 1729. 1730. 1731. 1732. 1733. 1734. 1735. 1736. 1737. 1738. 1739. 1740. 1741. 1742. 1743. 1744. 1745. 1746. 1747. 1748. 1749. 1750. 1751. 1752. 1753. 1754. 1755. 1756. 1757. 1758. 1759. 1760. 1761. 1762. 1763. 1764. 1

U.S. & S. CO. - TYPE "T2"

LOW VOLTAGE



| CONTACT SPACE NUMBER | GOING TO CLEAR | | GOING TO CAUTION | | REMARKS |
|----------------------|----------------|-------|------------------|-------|----------------------------------|
| | CLOSES | OPENS | CLOSES | OPENS | |
| 1 | | | | | |
| 2 | | | | | |
| 3 | | 50° | 47° | | INDICATION. |
| 4 TOP | | | | | |
| 4 BOTTOM | | | | | |
| 5 TOP | | | | | |
| 5 BOTTOM | | | | | |
| 6 PX | | | | | |
| 6 WY | | | | | |
| 7 | | 50° | 47° | | ON TOP ARM (SECOND ARM CONTROL). |
| 8 VW | | | | | |
| 8 XY | | 88° | 85° | | 90° OPERATING. |

NOTE:-
CIRCUIT CONTROLLER SHAFT MOVES 3 TIMES THE SPEED OF THE SEMAPHORE IN THE OPPOSITE DIRECTION; HENCE, 90° OF SEMAPHORE IS EQUIVALENT TO 270° MOVEMENT OF CIRCUIT CONTROLLER SEGMENT.
FOR TYPICAL ARRANGEMENT OF CONTROL CIRCUITS SEE PENNSYLVANIA RAILROAD TYPICAL CIRCUIT PLAN S-853. A COMPLETE ARRANGEMENT OF CIRCUITS SHOULD BE SHOWN ON THE DETAIL CIRCUIT PLAN FOR EACH INSTALLATION.


* 2 OHMS RESISTANCE.

| CONTACT SPACE NUMBER | GOING TO CLEAR | | GOING TO CAUTION | | REMARKS |
|----------------------|-------------------------|-------|--------------------------|-------|---|
| | CLOSES | OPENS | CLOSES | OPENS | |
| 1 | | | | | |
| 3 | | | | | |
| 5 | | | | | |
| 7 | | 88° | 88° | | 90° OPERATING. |
| 9 | | | | | |
| 11 | | 50° | 50° | | SLIP CONTACT SHUNT. |
| 13 | OPENS AFTER 2° ROTATION | | CLOSES AFTER 2° ROTATION | | SLIP CONTACT - SHUNTS HIGH RESISTANCE COIL. |
| 2 | | | | | |
| 4 | | 50° | 50° | | ON TOP ARM (SECOND ARM CONTROL). |
| 6 | | | | | |
| 8 | | | | | |
| 10 | | 50° | 50° | | INDICATION. |
| 12 | | | | | |
| 14 | | | | | |

NOTE:-
FOR TYPICAL ARRANGEMENT OF CONTROL CIRCUITS SEE PENNSYLVANIA RAILROAD TYPICAL CIRCUIT PLAN S-853. A COMPLETE ARRANGEMENT OF CIRCUITS SHOULD BE SHOWN ON THE DETAIL CIRCUIT PLAN FOR EACH INSTALLATION.
* SNUB RESISTANCE - 3 OHMS.

G.R.S. CO. - TYPE "2A"

LOW VOLTAGE



REVISIONS

REDRAWN FROM SHEETS 1 & 2 OF PLAN S-864. DATED 7-7-21.

S-864

1 SHEET


THE PENNSYLVANIA RAILROAD
STANDARD
LOCAL CIRCUITS FOR MOTOR
DISTANT SIGNALS

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., MAY 19, 1927

Approved: *A. H. Hurd*
Chief Signal Engineer


Approved: *[Signature]*
Chief Engineer

NOT TO SCALE




NORMALLY DEENERGIZED "V" RELAYS.
100 CYCLE CODE
100 CYCLE TRACK
SEE PLAN S-883, FIGS. 2 & 4.
S-884, SH. 2.

FOR USE WHERE SPARE DEPENDENT FRONT & BACK CONTACT IS NOT AVAILABLE ON SLOW ACTING RELAYS, SHALL ALSO BE USED IN ALL CASES WHERE SEPARATE LIGHTING TRANSFORMER IS PROVIDED.



NORMALLY DEENERGIZED "V" RELAYS.
100 CYCLE CODE
100 CYCLE TRACK.

SEE PLAN S-883, FIGS. 1, 2, 3 & 4.
S-884, SHS. 1 & 2.
FOR USE WHERE SPARE DEPENDENT FRONT & BACK CONTACT IS AVAILABLE ON SLOW ACTING RELAYS WHERE CIRCUITS ARE IN ACCORDANCE WITH S-883, FIGS. 2 & 4. AND S-884, SH. 2. - SEE SKETCH "A".




NORMALLY ENERGIZED "V" RELAYS.
100 CYCLE CODE
100 CYCLE CODERS
60 CYCLE TRACK
SEE PLAN S-883, FIGS. 11, 12, 13 & 14. SEE SKETCH "B".
S-884, SHS. 10, 11, 12, 15, 16 & 18.

FIG. 3.

NOTE:-


1. WHERE MORE THAN ONE TRACK IS SIGNALLED IN A GIVEN DIRECTION ALL HIGH SIGNALS GOVERNING IN THAT DIRECTION SHALL BE APPROACH LIGHTED SIMULTANEOUSLY.
2. INTERLOCKING SIGNALS SHALL NOT BE APPROACH LIGHTED.

TWO TRACK ROAD.




NORMALLY DEENERGIZED "V" RELAYS.
100 CYCLE CODE
100 CYCLE TRACK
SEE PLAN S-883, FIGS. 1, 2, 3 & 4.
S-884, SHS. 1 & 2.

FIG. 4.





NORMALLY DEENERGIZED "V" RELAYS.
100 CYCLE CODE
60 CYCLE CODERS
60 CYCLE TRACK.
SEE PLAN S-883, FIGS. 5, 6, 7 & 8.
S-884, SHS. 4 & 6.

FIG. 5.




NORMALLY ENERGIZED "V" RELAYS.
100 CYCLE CODE
100 CYCLE CODERS
60 CYCLE TRACK
SEE PLAN S-883, FIGS. 11, 12, 13 & 14. SEE SKETCH "B".
S-884, SHS. 10, 11 & 12.

FIG. 6.




NORMALLY ENERGIZED "V" RELAYS.
100 CYCLE CODE
100 CYCLE TRACK (ELECTRIFIED TERRITORY)
SEE PLAN S-884, SHS. 15, 16 & 18.

FIG. 7.



NORMALLY DEENERGIZED "V" RELAYS.
POLE-CHANGING CIRCUIT WHERE FIG. 2 IS USED.

SKETCH "A"



NORMALLY ENERGIZED "V" RELAYS.
POLE-CHANGING CIRCUIT WHERE FIG. 3 OR 6 IS USED.

SKETCH "B"

FOR USE IN CODED TRACK
CIRCUIT TERRITORY.

REVISIONS.

5-11-37, SIGNALS LIGHTED WHEN BLOCK BEYOND SIGNAL IS OCCUPIED.

APPROVED: *A. H. Russell* *W. J. L. S.*

SUPERSEDES PLAN S-865, SHEETS 1 TO 7, DATED 2-21-24.

5-865

15 SHEET



THE PENNSYLVANIA RAILROAD
STANDARD
APPROACH LIGHTING CIRCUITS.

OFFICE OF ASST. CHIEF ENGINEER - SIGNALS
PHILA., PA., AUG. 17, 1932.

Approved

A. H. Russell
Chief Signal Engineer

Approved

W. J. L. S.
Chief Engineer

NOT TO SCALE.

FOUR TRACK ROAD.

NOTE:-

Approach Lighting may be used only:

For signals on single track lines and on double track lines where such double tracks are signaled for Eastward (or Northward) movements on one track and Westward (or Southward) movements on the other, and then only where tracks are occupied not more than one-fourth of the time if primary battery is used.

Approach lighting shall not be used for high signals on adjacent parallel tracks in the same direction.

For arrangement of terminals in terminal box, see Pennsylvania Railroad System Standard Plan No. S-858.

Each mast shall have separate negative wires.

Lighting circuits shall be so adjusted as to have uniform voltage at the lamps. The voltage shall be between the following limits:

| | <u>Maximum</u> | <u>Minimum</u> | <u>Recommended</u> |
|------------------|----------------|----------------|--------------------|
| High Signals - - | 11.5 V.: | 11.0 V.: | - |
| Dwarf Signals- - | 5.0 V.: | 4.0 V.: | 4.2 V. or 4.3 V. |

Lamps shall be in accordance with Pennsylvania Railroad System Standard Plan Basic No. S-483.

Signal wires and control relays have been numbered from arbitrary track number and correct number for the track which the signal governs shall be substituted. Where direction of traffic is North and South, substitute the letter "N" for "E" and "S" for "W" in line control circuits.

Control of distant signal relays (1DJ^a and 1DJ^b) shall be shown on the circuit plan of the interlocking. For typical arrangement, see Pennsylvania Railroad System Typical Circuit Plan No. S-853.

All crossovers, turnouts and derails between home and distant signals or between automatic signal and next signal in advance, shall be in accordance with Pennsylvania Railroad System Standard Plan Basic No. S-228, S-229, S-230, S-231, S-232 or S-233, and shall be insulated and bonded in accordance with Pennsylvania Railroad System Standard Plan No. S-803.

SHEET 1 OF 7

S-865



**PENNSYLVANIA RAILROAD SYSTEM
TYPICAL APPROACH LIGHTING CIRCUITS**

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., FEB. 27, 1924.


Approved

A. H. Russell
Chief Signal Engineer

NOT TO SCALE

Approved

[Signature]
Chief Engineer



Note:-
For Lighting Circuits for Position Light Interlocking and Block Signals see Pennsylvania Railroad System Standard Plan S-855.

For General Notes see Sheet No.1.

SHEET 2 OF 2

S-865

PENNSYLVANIA RAILROAD SYSTEM TYPICAL APPROACH LIGHTING CIRCUITS

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., FEB. 27, 1924.

NOT TO SCALE

Approved

A. H. Read
Chief Signal Engineer

Approved

[Signature]
Chief Engineer

REC.
H.A.H.




FIGURE 1.




FIGURE 2.

Note:

The control circuit for relay "2LR" shall be as shown in FIGURE 2 where either 90° position on second arm of Home Signal is dependent on "Light-out" relay, or where Approach Locking is installed. Where neither is used it shall be as shown in FIGURE 1.

For lighting circuits for Position Light Interlocking and Block signals see Pennsylvania Railroad System Standard Plan S-855.

For lighting circuits for Position Light Distant Signals see Pennsylvania Railroad System Standard Plan S-856.

For General Notes see Sheet 1.

SHEET 3 OF 7

S-865



PENNSYLVANIA RAILROAD SYSTEM TYPICAL APPROACH LIGHTING CIRCUITS

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., FEB. 27, 1924.


Approved

A. H. Rued
Chief Signal Engineer

NOT TO SCALE

Approved

[Signature]
Chief Engineer



SHEET 4 OF 7

S-865



PENNSYLVANIA RAILROAD SYSTEM TYPICAL APPROACH LIGHTING CIRCUITS

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., FEB. 27, 1924.


NOT TO SCALE


Approved





Art. Rood
Chief Signal Engineer

Approved

[Signature]
Chief Engineer







NOTE:-

- 1.- THE CIRCUITS SHOWN APPLY TO TERMINAL TERRITORY, OUTSIDE OF WHICH BUT FEW FOUR POSITION DWARF SIGNALS ARE USED.
- 2.- WHERE "SS" PROTECTION OR TIME LOCKING IS INSTALLED THE SIGNAL CONTROL CIRCUITS SHALL BE MODIFIED, FOLLOWING THE ARRANGEMENT SHOWN ON TYPICAL PLAN S-862.
- 3.- SIGNAL LIGHTING CIRCUITS SHALL BE IN ACCORDANCE WITH STANDARD PLAN S-855.
- 4.- @ = MECHANICAL STICK PUSH BUTTON.

REVISIONS

REDRAWN FROM PLAN S-867 DATED 8-3-22.

S-867

1 SHEET

THE PENNSYLVANIA RAILROAD
TYPICAL
CONTROL CIRCUITS FOR POSITION
LIGHT DWARF SIGNALS

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., SEPT. 20, 1922
Approved *A. H. Russell*
Chief Signal Engineer

NOT TO SCALE
Approved *[Signature]*
Chief Engineer

| ASPECT | SHEET No. | ASPECT | SHEET No. |
|--------|---|--------|--------------------------------------|
| | 2
ELECTRIC ROAD A.C. PROPULSION 2 BLOCK TERRITORY. | | 10
ELECTRIC ROAD A.C. PROPULSION. |
| | 3
2 BLOCK TERRITORY. | | 11 |
| | 4
ELECTRIC ROAD A.C. PROPULSION. DISTANT SIGNAL. | | |
| | 5
DISTANT SIGNAL. | | |
| | 6
ELECTRIC ROAD A.C. PROPULSION. AUTOMATIC SIGNAL. | | |
| | 7
AUTOMATIC SIGNAL. | | |
| | 8
ELECTRIC ROAD A.C. PROPULSION. | | |
| | 9 | | |

Note:-

Light wires shall not be smaller than indicated as follows:-
No. 9-A.W.G.- Between control relays and signal terminals.
No. 14-A.W.G.- Between signal terminals and lamps.

For arrangement of terminals in terminal box see Pennsylvania System Standard Plan S-858.

Each mast shall have separate positive & negative wires. Lighting circuits shall be so adjusted as to have uniform voltage at the lamps. The voltage shall be between the following limits:- Maximum-115V, Minimum-110V. Lamps shall be in accordance with Pennsylvania System Standard Plan Basic No. S-483.

All crossovers, turnouts & details between Home and Distant Signal or between automatic signal and the next signal in advance shall be equipped and operated in accordance with Pennsylvania System Standard Plan Basic No. S-228, S-230 or S-232 and shall be insulated and bonded in accordance with Pennsylvania System Standard Plan S-803.

Signal wires and control relays have been numbered from arbitrary track number and correct number for the track which signal governs shall be substituted.

Control of Distant Signal relays (IDJ^a, IDJ^b, &c) shall be shown on circuit plan of interlocking. For typical arrangement see Pennsylvania System Typical Circuit Plan S-853.

Track circuits shown between Home and Distant Signals are typical. Detail arrangement of track circuits should be made for each installation to suit local conditions and requirements.

Where no "Light-out" (IDEM) relay is used circuits shall be arranged as shown in dotted lines.

All circuits are for steam road unless otherwise noted.

Where distant signal is also the advance signal for another interlocking or where automatic signal is the advance signal at an interlocking:-

Polarized track feed for section in the rear of the signal shall be omitted and the primary side of the Lighting Transformer shall be connected direct to the 110V. Bus.

For Typical Arrangement for Lighting Position Light Home & Advance Signals When Normal Power Fails see Pennsylvania System Typical Circuit

PEC
H.A.H.

Plan S-805. Where this arrangement is used circuits shall be modified accordingly and shown in detail on circuit plan to be prepared for each interlocking or block signal installation.

Where direction of traffic is north and south substitute letter 'N' for 'E' and 'S' for 'W' in line control circuits.

REVISIONS.

11-9-23. Circuit arrangement where no "Light-out" relay is used and voltage for Model 15 Vane "Light-out" relay formerly not shown. Sheets 1, 2, 3, 8 and 9 changed.
Approved:

A. H. Russ
Chief Signal Engineer

PEC
H.A.H.

SHEET 1 OF 11

S-868

PENNSYLVANIA SYSTEM



STANDARD LIGHTING CIRCUITS FOR POSITION LIGHT GRADE SIGNALS

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., MARCH 28, 1922.


Correct

A. H. Russ
Chief Signal Engineer

Approved


NOT TO SCALE
Chief Engineer

To Secondary of Line Trans.




10V.-For Style T2LV14 Relay.
110V.-For Model 15Vane Relay.

Distant to Home.



To Secondary of Line Trans.



Note:-

Where switches occur between Home and Distant Signal, local of track relay shall be controlled in accordance with Pennsylvania System Standard Circuit Plan S-803.

ELECTRIC ROAD (A.C. PROPULSION).
Two BLOCK INDICATION.

For General Notes see Sheet No. 1.

11-9-23.

Revised.

S-868

SHEET 2 OF 11

PENNSYLVANIA SYSTEM



STANDARD
LIGHTING CIRCUITS FOR POSITION LIGHT
GRADE SIGNALS

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., MARCH 28, 1922.


Correct

A. H. Reed
Chief Signal Engineer


Approved

NOT TO SCALE

Chief Engineer



TWO BLOCK TERRITORY.
For General Notes see Sheet No. 1.



11-9-23.
Revised.
S-868

SHEET 3 OF 11

PENNSYLVANIA SYSTEM



STANDARD
LIGHTING CIRCUITS FOR POSITION LIGHT
GRADE SIGNALS

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., MARCH 28, 1922.

Correct


A. H. Reed
Chief Signal Engineer

NOT TO SCALE


Approved
Chief Engineer

REC
H.A.H.

To Secondary of Line Trans.




Distant to Home.



To Clear Control Relay of next Signal in the rear. See Sh. 6.

LEP
H.A.H.

To Secondary of Line Trans.



Home Signal Location.

Note:-

Where switches occur between Home and Distant Signal, local of track relay shall be controlled in accordance with Pennsylvania System Standard Circuit Plan S-803.

ELECTRIC ROAD (A.C. PROPULSION).

For General Notes see Sheet No. 1.

SHEET 4 OF 11

S-868

PENNSYLVANIA SYSTEM



STANDARD
LIGHTING CIRCUITS FOR POSITION LIGHT
GRADE SIGNALS

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., MARCH 28, 1922.

NOT TO SCALE



Correct

A. H. Hurd
Chief Signal Engineer


Approved

[Signature]
Chief Engineer


To Secondary of Line Trans.



Distant to Home



To Secondary of Line Trans.




To Pole Changing Device.

From Pole Changing Device.

Home Signal Location.

For General Notes see Sheet No. 1.



SHEET 5 OF 11

S-868

PENNSYLVANIA SYSTEM

STANDARD

LIGHTING CIRCUITS FOR POSITION LIGHT
GRADE SIGNALS

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., MARCH 28, 1922.

Correct


Chief Signal Engineer

Approved

NOT TO SCALE

Chief Engineer

To Secondary of Line Trans.



No. 1 Track


Note:-

Where switches occur between automatic signal and next signal in advance, the local of the track relay shall be controlled in accordance with Pennsylvania System Standard Circuit Plan S-803.


ELECTRIC ROAD (A.C. PROPULSION).

For General Notes see Sheet No. 1.

To Secondary of Line Trans.




To "B" To "A" R



From next signal in advance.

From Secondary "Y"

From + Secondary "X"



From Secondary "X"

To Secondary "X"

To Clear Control Relay of next signal in the rear.

SHEET 6 OF 11

S-868

PENNSYLVANIA SYSTEM

STANDARD

LIGHTING CIRCUITS FOR POSITION LIGHT GRADE SIGNALS

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., MARCH 28, 1922.

Correct

Chief Signal Engineer




Approved

NOT TO SCALE

Chief Engineer

REC
H.A.H.

To Secondary of Line Trans.



For General Notes see Sheet No. 1.

SHEET 7 OF 11

S-868

PENNSYLVANIA SYSTEM



STANDARD
LIGHTING CIRCUITS FOR POSITION LIGHT
GRADE SIGNALS

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., MARCH 28, 1922.


Correct

A. H. Reed
Chief Signal Engineer


NOT TO SCALE
Approved

[Signature]
Chief Engineer


To Secondary of Line Trans.



To Secondary of Line Trans.



10V. For Style T2LV14 Relay.
110V. For Model 15 Vane Relay.
15V.



Note:-

Where switches occur between Home and Distant Signal, local of track relay shall be controlled in accordance with Pennsylvania System Standard Circuit Plan S-803.

ELECTRIC ROAD (A.C. PROPULSION).

For General Notes see Sheet No. 1.

11-9-23.

Revised.

S-868

SHEET 8 OF 11

PENNSYLVANIA SYSTEM



STANDARD
LIGHTING CIRCUITS FOR POSITION LIGHT
GRADE SIGNALS

OFFICE OF CHIEF SIGNAL-ENGINEER,
PHILA., PA., MARCH 28, 1922.

NOT TO SCALE



Correct

Chief Signal Engineer

Approved




Chief Engineer

To Secondary of Line Trans.




10V. - For Style T2LV14 Relay.
110V. - For Model 15 Vane Relay.

Distant to Home.




For General Notes see Sheet No. 1.

To Secondary of Line Trans.



To Pole Changing Device



Home Signal Location.

11-9-23.

Revised.

S-868

SHEET 9 OF 11

PENNSYLVANIA SYSTEM

STANDARD

LIGHTING CIRCUITS FOR POSITION LIGHT
GRADE SIGNALS

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., MARCH 28, 1922.

Correct



Chief Signal Engineer

Approved


NOT TO SCALE

Chief Engineer

To Secondary of Line Trans.



To Secondary of Line Trans.



Note:-

Where switches occur between Home and Distant Signal, local of track relay shall be controlled in accordance with Pennsylvania System Standard Circuit Plan S-803.

ELECTRIC ROAD (A.C. PROPULSION).

For General Notes see Sheet No. 1.

SHEET 10 OF 11

S-868

PENNSYLVANIA SYSTEM



STANDARD
LIGHTING CIRCUITS FOR POSITION LIGHT
GRADE SIGNALS

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., MARCH 28, 1922.



Correct

Ant. Hood
Chief Signal Engineer


NOT TO SCALE
Approved

[Signature]
Chief Engineer


To Secondary of Line Trans.



Distant to Home





To Secondary of Line Trans.



To XIA

Home Signal Location.

For General Notes see Sheet No. 1.



SHEET 11 OF 11

S-868

PENNSYLVANIA SYSTEM



STANDARD
LIGHTING CIRCUITS FOR POSITION LIGHT
GRADE SIGNALS

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., MARCH 28, 1922.

Correct

A. H. Wood
Chief Signal Engineer

NOT TO SCALE

Approved

[Signature]
Chief Engineer




FIG. 1
ARRANGEMENT FOR USE WHERE A.C. INTERLOCKING
TRACK CIRCUITS ARE PROVIDED.




FIG. 2
ARRANGEMENT FOR USE WHERE D.C. INTERLOCKING
TRACK CIRCUITS ARE PROVIDED.

D.C. POWER SUPPLY FOR APPROACH RELAYS AND SIGNAL INDICATION
CIRCUIT WHERE RELIABLE A.C. POWER IS AVAILABLE.

NOTE:-

1. ⊕ = MECHANICAL STICK PUSH BUTTON.
2. WHERE TIME LOCKING ONLY IS INSTALLED OMIT PORTION OF CIRCUIT SHOWN IN DOTTED LINES, SH'S. 3&4&5.
3. CLOCKWORK RELEASES SHALL BE EQUIPPED WITH LATCH AND THE NORMAL POSITION OF THE POINTER SET AT ZERO. THE SETTING OF THE RELEASES SHALL BE IN ACCORDANCE WITH C.S.E. 9.
4. INDICATION LIGHTS CONNECTED IN MULTIPLE WITH THE INDICATION LOCK, AS SHOWN ON SH'S. 3&4, SHALL BE INSTALLED WHERE, IN THE JUDGMENT OF THE SUPERINTENDENT OF TELEGRAPH & SIGNALS, THEY ARE NECESSARY.

REVISIONS.

SHEET 1 OF 5

S-870



THE PENNSYLVANIA RAILROAD
TYPICAL

SIGNAL INDICATION AND
APPROACH LOCKING CIRCUITS

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., MARCH 30, 1928.

Approved *am. h. m.*
Chief Signal Engineer

NOT TO SCALE
Approved *[Signature]*
Chief Engineer




FIG. 1
(STEAM ROAD)
FOR USE WHERE TRACK RELAY CONTACT (X1A) IS NOT INCLUDED
IN POLE-CHANGING CIRCUIT FOR X1B.




FIG. 2
(STEAM ROAD)
FOR USE WHERE TRACK RELAY CONTACT (X1A) IS INCLUDED
IN POLE-CHANGING CIRCUIT FOR X1B.




FIG. 3
(ELECTRIC ROAD)




FIG. 4
(STEAM ROAD)
TWO BLOCK INDICATION.




FIG. 5
(STEAM ROAD)
FOR USE WHERE POLARIZED TRACK AND NEUTRAL LINE
CIRCUITS ARE PROVIDED-PLAN S-857-FIG. 5.




FIG. 6
(STEAM OR ELECTRIC ROAD)
FOR USE WHERE NEUTRAL TRACK AND POLARIZED LINE
CIRCUITS ARE PROVIDED-PLAN S-857-FIGS. 1 & 2.
THREE BLOCK INDICATION




FIG. 7
DISTANT SIGNALS NORMALLY LIGHTED.




FIG. 8
DISTANT SIGNALS APPROACH LIGHTED.
MANUAL BLOCK TERRITORY

FOR GENERAL NOTES SEE SHEET NO. 1.




FIG. 9
WHERE POWER IS OBTAINED FROM PRIMARY
OR PORTABLE STORAGE BATTERIES APPROACH
INDICATORS (WITHOUT CONTACTS) SHALL BE USED.




FIG. 10
WHERE POWER IS OBTAINED FROM SOURCE
OTHER THAN PRIMARY OR PORTABLE STORAGE
BATTERIES APPROACH INDICATION LIGHTS
SHALL BE USED.

REVISIONS.

SUPERSEDES APPROACH RELAY
CONTROLS SHOWN ON SHS. 1 & 2
OF PLAN S-870, DATED 3-3-25,
LAST REVISED 3-3-25.

S-870


SHEET 2 OF 3


THE PENNSYLVANIA RAILROAD
TYPICAL
SIGNAL INDICATION AND
APPROACH LOCKING CIRCUITS

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., MARCH 30, 1928.

Approved *A. H. H.*
Chief Signal Engineer

NOT TO SCALE
Approved *[Signature]*
Chief Engineer





REVISIONS

ARRANGEMENT PROVIDES TIME LOCKING ONLY. MAY BE USED IN TERRITORY WHERE TRAFFIC CONDITIONS DO NOT REQUIRE THE USE OF APPROACH LOCKING.

NOV. 3, 1942. INDICATION LIGHT PROVIDED. APPROVED: *H. C. Stanton*

SHEET 1 OF 8


S-872


THE PENNSYLVANIA RAILROAD TYPICAL CONTROL CIRCUITS FOR ELEC. SW. LOCKS ON NON-INTERLOCKED SWS.

OFFICE OF CHIEF ENGINEER,
PHILA., PA., AUG. 6, 1942.


APPROVED: *H. C. Stanton*
ASST. CHIEF ENGINEER-SIGS.


NOT TO SCALE
APPROVED: *M. J. Sullivan*
CHIEF ENGINEER














REVISIONS.

DEC. 17 1946. 46
NOTE CHANGED.


RUE. 12. 1946.
CIRCUITS FOR ILLUMINATED "DE"
SIGN AT DISTANT SIGNAL ADDED
AND INDICATION LIGHT IN TELE-
PHONE SHELTER BOX CHANGED.
APPROVED:
[Signature]

EX-111

5-879

W. Higgins
CHIEF ENGINEER.

DRAGGING EQUIPMENT DETECTORS SHALL BE LOCATED THE MINIMUM DISTANCE FROM THE DISTANT SIGNAL WHICH SHALL NOT BE LESS THAN THE LENGTH OF THE LONGEST TRAIN TO BE PROTECTED PLUS 1500 FEET.



FOR SELF RESTORING TYPE
DRAGGING EQUIPMENT DETECTOR

SHEET 4 OF 4

S-879

THE PENNSYLVANIA RAILROAD
TYPICAL

CIRCUITS FOR
DRAGGING EQUIPMENT DETECTORS

OFFICE OF CHIEF ENGINEER,
PHILA., PA., OCT. 5, 1948.


NOT TO SCALE

APPROVED:



W. Griffith
ASST. CHIEF ENGINEER, T. C. S.

APPROVED:


W. Griffith
CHIEF ENGINEER



FOR USE IN A.C. TRACK CIRCUIT TERRITORY - STEAM ROAD



FOR USE IN D.C. TRACK CIRCUIT TERRITORY



FOR USE IN A.C. TRACK CIRCUIT TERRITORY STEAM ROAD

REVISIONS

FOR TRACK ARRANGEMENT AND OTHER CIRCUITS SEE SH. 1

100 CYCLE CODE

D.C. TRACK CIRCUIT
100 CYCLE A.C. TRACK CIRCUIT
STEAM ROAD

SUPERSEDES PLAN 5881; SHS. 2 & 3, DATED 10-23-26; SHS. 4 & 5, DATED 6-6-27; SH. 6, DATED 10-2-28; AND SH. 7, DATED 1-11-29.

SHEET 2 OF 4

S-881

THE PENNSYLVANIA RAILROAD TYPICAL CODED TRACK CIRCUITS FOR INTERLOCKINGS



OFFICE OF CHIEF ENGINEER
PHILA., PA., JULY 31, 1943.

APPROVED:

N. C. Stanton
ASST. CHIEF ENGINEER-SIGS.

APPROVED:

NOT TO SCALE
CHIEF ENGINEER




REVISIONS.

3-26-27. CONTACT ON "XIASA"
REMOVED FROM "XIAB" CONTROL
FIGURES 1 AND 2.


APPROVED *at* [Signature]

FILE [Stamp]



FOR LIGHTING CIRCUITS SEE PLAN S-856, FIG. 1A.

FIGURE 3.



FOR LIGHTING CIRCUITS SEE PLAN S-856, FIG. 8, FOR AND FIG. 11, FOR.

FIGURE 4.

STEAM ROAD.
100 CYCLE TRACK CIRCUIT.
100 CYCLE CODE.

REVISIONS.

3-26-27 CONTACT ON XIASA
REMOVED FROM "XIAV" CONTROL,
FIG. 4.

APPROVED: *[Signature]*

S-883

SHEET 2 OF 9


THE PENNSYLVANIA RAILROAD
STANDARD
CODED TRACK CIRCUITS APPROACHING
DISTANT INTERLOCKING SIGNAL

OFFICE OF CHIEF SIGNAL ENGINEER
PHILA. PA., JAN. 26, 1927


Approved: *[Signature]*
Chief Signal Engineer

NOT TO SCALE

Approved: *[Signature]*
Chief Engineer



THREE BLOCK TERRITORY
FOR LIGHTING CIRCUITS SEE PLAN S-856, FIG. 2.
FIGURE 5.



TWO BLOCK TERRITORY
FOR LIGHTING CIRCUITS SEE PLAN S-856, FIG. 3.
FIGURE 6.

STEAM ROAD
60 CYCLE TRACK CIRCUIT.
100 CYCLE CODE.

| REVISIONS. |
|---|
| 3-26-27 CONTACT ON XIASA
REMOVED FROM "MAN" CONTROL,
FIGURES 4 & 6. |
| APPROVED <i>[Signature]</i> C.E.E. |

SHEET 3 OF 8

THE PENNSYLVANIA RAILROAD
STANDARD
**CODED TRACK CIRCUITS APPROACHING
DISTANT INTERLOCKING SIGNAL**



OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., JAN. 29, 1927

Approved *[Signature]* Chief Signal Engineer

NOT TO SCALE

Approved *[Signature]* Chief Engineer

S-883



FOR LIGHTING CIRCUITS SEE PLAN S-856, FIG. 14


FOR LIGHTING CIRCUITS SEE PLAN S-856, FIG. 8, FOR
AND FIG. 11, FOR

STEAM ROAD
60 CYCLE TRACK CIRCUIT.
100 CYCLE CODE.


REVISIONS.

3-26-27. CONTACT ON "XIASA"
REMOVED FROM "XIAV" CONTROL,
FIG. 8.

APPROVED *am* *Red* FEC
4/1/28



THREE BLOCK TERRITORY
FOR SIGNAL OPERATING CIRCUITS SEE PLAN S-847, FIG. 3.
FIGURE 9



TWO BLOCK TERRITORY
FOR SIGNAL OPERATING CIRCUITS SEE PLAN S-847, FIG. 3 FOR
AND PLAN S-847, FIG. 2 FOR
AND PLAN S-847, FIG. 4 FOR
FIGURE 10

STEAM ROAD
60 CYCLE TRACK CIRCUIT,
100 CYCLE CODE.

SHEET 5 OF 9

S-883

THE PENNSYLVANIA RAILROAD
STANDARD
CODED TRACK CIRCUITS APPROACHING
DISTANT INTERLOCKING SIGNAL

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., JAN. 20, 1927



Approved: *A. H. [Signature]*
Chief Signal Engineer

Approved: *[Signature]*
Chief Engineer

NOT TO SCALE

REVISIONS.

3-26-27. CONTACT ON "XIAA"
REMOVED FROM MAIN CONTROL,
FIGURES 9 & 10.
APPROVED: *A. H. [Signature]*



NORMALLY ENERGIZED
"V" RELAYS.
100 CYCLE CODERS.
60 CYCLE TRACK CIRCUIT.
100 CYCLE CODE.
STEAM ROAD

7-3-29. "V" RELAYS
FORMERLY D.C. AND NORMALLY
DEENERGIZED.

APPROVED: *A. H. [Signature]*

SHEET 6 OF 9

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., AUG. 19, 1928.

Approved  Chief Signal Engineer

NOT TO SCALE


Approved  Chief Engineer

0004

THREE BLOCK TERRITORY
POLARIZED TRACK CONTROL FOR TOP ARM-LINE CONTROL FOR BOT ARM.
FOR LIGHTING CIRCUITS SEE CIRCUIT PLAN FOR INTERLOCKING.


FIGURE 12.

A=PROCEED INDICATION. (180 CODE)
B=APPROACH RESTRICTING INDICATION. (120 CODE)
C=APPROACH INDICATION. (80 CODE)


[illegible]

S-88:

Approved 
Chief Engineer



A = PROCEED INDICATION (180 CODE)
 B = APPROACH RESTRICTING INDICATION (120 CODE)
 C = APPROACH INDICATION (80 CODE)



NORMALLY ENERGIZED "V" RELAYS
 100 CYCLE CODERS
 60 CYCLE TRACK CIRCUIT
 100 CYCLE CODE
 STEAM ROAD

SHEET 9 OF 9


S-883

THE PENNSYLVANIA RAILROAD
 STANDARD
 CODED TRACK CIRCUITS APPROACHING
 DISTANT INTERLOCKING SIGNAL

OFFICE OF CHIEF SIGNAL ENGINEER,
 PHILA., PA., JULY 3, 1929.

Approved *A. H. H. H.*
 Chief Signal Engineer

NOT TO SCALE
 Approved *[Signature]*
 Chief Engineer



NOTE:-
FOR SIGNAL LIGHTING AND CONTROL
CIRCUITS SEE PLAN S-857, SHEET 5.

100 CYCLE CODE.
D.C. TRACK CIRCUITS WITH
MULTIPLE RELAY ARRANGEMENT
FOR FOREIGN CURRENT PROTECTION.

7-24-28, 110V. SECONDARY FORMERLY
SHOWN ON 4 SECONDARY TRANSFORMER
APPROVED: *W. H. Rudd*

SHEET 1 OF 17

S-884


THE PENNSYLVANIA RAILROAD
STANDARD
CODED TRACK CIRCUITS IN
AUTOMATIC TERRITORY


OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., OCT. 6, 1927

Approved: *W. H. Rudd*
Chief Signal Engineer

Approved: *W. H. Rudd*
Chief Engineer

NOT TO SCALE





- NOTE:-
1. FOR LIGHTING CIRCUITS SEE PLAN S-857, FIG. 4.
 2. RESISTOR "X" SHALL BE IN ACCORDANCE WITH PLAN S-812.
 3. WHERE A.C. SLOW-ACTING RELAYS ARE USED OMIT CONTACT (1SA) AND RESISTOR "X" IN CONTROL CIRCUIT FOR SA RELAY; ENERGY BEING SUPPLIED FROM THE 110V-60~ BUS.

NORMALLY ENERGIZED "V" RELAYS.
100 CYCLE CODERS.

60 CYCLE TRACK CIRCUIT.
100 CYCLE CODE.

TWO BLOCK TERRITORY.
STEAM ROAD.

A = PROCEED INDICATION. (180 CODE)
B = APPROACH RESTRICTING INDICATION. (120 CODE)
C = APPROACH INDICATION. (80 CODE)

REVISIONS.

5-23-29. "V" RELAYS
FORMERLY D.C. AND
NORMALLY DEENERGIZED.

APPROVED: *[Signature]*
S.E.G.

SHEET 10 OF 17

S-884


THE PENNSYLVANIA RAILROAD STANDARD CODED TRACK CIRCUITS IN AUTOMATIC TERRITORY

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., JULY 30, 1928

Approved: *[Signature]*
Chief Signal Engineer

NOT TO SCALE

Approved: *[Signature]*
Chief Engineer



NOTE:-
1. FOR LIGHTING CIRCUITS SEE PLAN S-857, FIG. 2.

NORMALLY ENERGIZED "V" RELAYS.
100 CYCLE CODERS.

60 CYCLE TRACK CIRCUIT.
100 CYCLE CODE.

THREE BLOCK TERRITORY.

STEAM ROAD.

NEUTRAL TRACK & POLARIZED LINE
CONTROL IN ACCORDANCE WITH
PLAN S-857-FIG. 2.

REVISIONS.

S-28-29. "V" RELAYS FORMERLY D.C.
AND NORMALLY DEENERGIZED.

APPROVED: *[Signature]* **CHIEF SIGNAL ENGINEER**

SHEET 11 OF 17

S-884


THE PENNSYLVANIA RAILROAD
STANDARD
CODED TRACK CIRCUITS IN
AUTOMATIC TERRITORY

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., JULY 20, 1928.

Approved: *[Signature]*
Chief Signal Engineer


Approved: *[Signature]*
Chief Engineer

A = PROCEED INDICATION. (180 CODE)
B = APPROACH RESTRICTING INDICATION. (120 CODE)
C = APPROACH INDICATION. (80 CODE)



NOT TO SCALE

[Signature]
Chief Engineer



NOTE:-
1. FOR SIGNAL OPERATING CIRCUITS SEE PLAN S-847, FIG. 1.

A=PROCEED INDICATION.(180 CODE)
B=APPROACH RESTRICTING INDICATION.(120 CODE)
C=APPROACH INDICATION.(80 CODE)

REVISIONS.

100 CYCLE CODERS.
60 CYCLE TRACK CIRCUIT.
100 CYCLE CODE.
THREE BLOCK TERRITORY
STEAM ROAD.

S-28-29 D.C. RELAYS
FORMERLY D.C. AND
NORMALLY DEENERGIZED.

APPROVED: A.H. [Signature]

SHEET 13 OF 17

S-884


THE PENNSYLVANIA RAILROAD
STANDARD
CODED TRACK CIRCUITS IN
AUTOMATIC TERRITORY

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., JULY 30, 1928.

Approved: [Signature]
Chief Signal Engineer

Approved: [Signature]
Chief Engineer

NOT TO SCALE



NOTE:-
1. FOR SIGNAL OPERATING CIRCUITS SEE PLAN S-847, FIG. 2.

REVISIONS

5-23-29. "V" RELAYS
FORMERLY D.C. AND
NORMALLY DEENERGIZED.

APPROVED: *[Signature]* *[Signature]*

"V" RELAYS NORMALLY ENERGIZED.
100 CYCLE CODERS
60 CYCLE TRACK CIRCUIT
100 CYCLE CODE
STEAM ROAD

SHEET 14 OF 17


S-884

THE PENNSYLVANIA RAILROAD STANDARD CODED TRACK CIRCUITS IN AUTOMATIC TERRITORY

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., JULY 30, 1928.

Approved: *[Signature]*
Chief Signal Engineer

NOT TO SCALE
Approved: *[Signature]*
Chief Engineer



NOTE:-
 1. RESISTOR "X" SHALL BE IN ACCORDANCE WITH PLAN S-812.
 2. FOR NOTES IN CONNECTION WITH SIGNAL LIGHTING CIRCUITS SEE PLAN S-857, SH. 1.
 3. TRACK CIRCUITS SHALL NOT EXCEED 5500' IN LENGTH. WHERE DISTANCE BETWEEN SIGNALS IS GREATER THAN 5500', CUT-SECTIONS IN ACCORDANCE WITH SH. 17 OF PLAN S-884 SHALL BE PROVIDED.
 4. WHERE STRUCTURES ARE GROUNDED TO RAILS, TRACK CIRCUITS SHALL NOT EXCEED 4500' IN LENGTH.

A-PROCEED INDICATION. (100 CODE)
 B-APPROACH RESTRICTING INDICATION. (120 CODE)
 C-APPROACH INDICATION. (80 CODE)

100 CYCLE TRACK CIRCUIT
 100 CYCLE CODE
 TWO BLOCK TERRITORY
 ELECTRIC ROAD
 A.C. PROPULSION

REVISIONS

5-23-29. NOTES 3 & 4
 ADDED.
 APPROVED. *[Signature]*
 S.E.C.
 S.H.G.

S-884

SHEET 15 OF 17


THE PENNSYLVANIA RAILROAD STANDARD CODED TRACK CIRCUITS IN AUTOMATIC TERRITORY

OFFICE OF CHIEF SIGNAL ENGINEER,
 PHILA., PA., FEB. 20, 1929.

Approved *[Signature]*
 Chief Signal Engineer

NOT TO SCALE

Approved *[Signature]*
 Chief Engineer



SEE PLAN
S-884 SH. 15

ACCE-E
ACCW-E

BI CI

ACCW-W
ACCE-W

SEE PLAN
S-884 SH. 15

NO. 1 TRACK

110V
100~
CT4

250W
1AJ

110V
100~
CT4

QUICK ACTING
BI

SEE PLAN
S-884 SH. 15

SEE PLAN
S-884 SH. 15

110V
100~
CT4

250W
1AJ

110V
100~
CT4

QUICK ACTING
BI

NOTE:-
CUT-SECTIONS SHALL BE PROVIDED AS SPECIFIED
ON PLAN S-884, SH. 15.

2V
3V
4V
CT2
CT1

THIS SIDE OF
CUT-SECTION FOR NO.
3 & 4 TRACK

110V
100~
CT4

250W
1AJ

110V
100~
CT4

QUICK ACTING
BI

TO NO. 2 TRACK

A=PROCEED INDICATION.(180 CODE)
B=APPROACH RESTRICTING INDICATION.(120 CODE)
C=APPROACH INDICATION.(80 CODE)

REVISIONS.

100 CYCLE TRACK CIRCUIT
100 CYCLE CODE
CUT-SECTION
FOR
TWO BLOCK TERRITORY
ELECTRIC ROAD
A.C. PROPULSION

SHEET 17 OF 17


S-884

THE PENNSYLVANIA RAILROAD
STANDARD
CODED TRACK CIRCUITS IN
AUTOMATIC TERRITORY

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA., PA., MAY 9, 1920.

Approved
Chief Signal Engineer

NOT TO SCALE
Approved
Chief Engineer



100 CYCLE TRACK CIRCUIT,
100 CYCLE CODE

SHEET 3 OF 3

S-887







THE PENNSYLVANIA RAILROAD
TYPICAL
CODED TRACK CIRCUITS APPROACHING
HOME INTERLOCKING SIGNALS

OFFICE OF CHIEF SIGNAL ENGINEER,
PHILA. PA., NOV. 26, 1920.

Approved *Arthur*
Chief Signal Engineer

NOT TO SCALE
Approved *Wm. H. H.*
Chief Engineer



REVISIONS.

J.P.H.




FIG. 1 - ELECTRIC ROAD, UNIVERSAL CODE




FIG. 3 - STEAM ROAD, A.C. TRACK CIRCUITS




FIG. 2 - ELECTRIC ROAD, CENTRIFUGAL TYPE TRACK RELAYS

- NOTE:-
1. BRIDGING TRANSFORMERS SHALL BE SO LOCATED AND ADJUSTED TO CAUSE CAB SIGNAL TO CHANGE TO RESTRICTING APPROXIMATELY 1000' FROM HOME SIGNAL WHEN ITS INDICATION IS LESS FAVORABLE THAN APPROACH.
 2. W-23 TRANS., PCE 242552, TO BE USED AS BRIDGING TRANSFORMERS AND TO BE HOUSED IN INSTRUMENT CASE ADJACENT TO TRACK. STORES CAT. REF 2A-3193.
 3. TOTAL LENGTH OF WIRE (+ & - CONNECTIONS) BETWEEN BRIDGING TRANSFORMER AND TRACK SHALL NOT EXCEED 0.014 OHMS - 35' OF #6 WIRE OR 56' OF #4 WIRE. WHERE TOTAL LENGTH OF LEADS EXCEEDS 56', TWO #6 WIRES UP TO 70' OR TWO #4 WIRES UP TO 112' CONNECTED IN MULTIPLE, SHALL BE PROVIDED.

BRIDGING TRANSFORMER
A.C. TRACK CIRCUITS

SHEET 1 OF 2

S-889

THE PENNSYLVANIA RAILROAD
TYPICAL
CODE CHANGE POINT APPROACHING
HOME INTERLOCKING SIGNALS

OFFICE OF CHIEF ENGINEER,
PHILA., PA., FEB. 24, 1944.

APPROVED:
N.L. Stanton
ASST. CHIEF ENGINEER-SIGS.

APPROVED:
NOT TO SCALE
CHIEF ENGINEER

REVISIONS




FIG. 4 - STEAM ROAD, D. C. CODED TRACK CIRCUITS




FIG. 5 - STEAM ROAD, D. C. NEUTRAL TRACK CIRCUITS

REVISIONS

CODE FOLLOWING RELAY
D. C. TRACK CIRCUITS

SHEET 2 OF 2



THE PENNSYLVANIA RAILROAD
TYPICAL
CODE CHANGE POINT APPROACHING
HOME INTERLOCKING SIGNALS

OFFICE OF CHIEF ENGINEER,
PHILA., PA., FEB. 24, 1944.

APPROVED:

N. L. Stanton
ASST. CHIEF ENGINEER-SIGS.

APPROVED:

NOT TO SCALE
W. H. Griffith
CHIEF ENGINEER

S-889

MAY 8, 1947.
FIG. 4 CHANGED FORMERLY
FRONT CONTACT CODING.
APPROVED:
W. H. Griffith
K. E.

AUTOMATIC CIRCUIT BREAKER
TO SECONDARY OF
6600-110V. TRANSFORMER




FIG. 3

AUTOMATIC CIRCUIT BREAKER
TO SECONDARY OF
6600-110V. TRANSFORMER




FIG. 4

NOTES:

1. FOR NOTES IN CONNECTION WITH SIGNAL LIGHTING CIRCUITS, SEE PLAN 5-887, SHEET 1.
2. TRACK CIRCUITS SHALL NOT EXCEED 5000' IN LENGTH. WHERE DISTANCE BETWEEN SIGNALS IS GREATER THAN 6000' CUT SECTIONS IN ACCORDANCE WITH FIG. 1 OR FIG. 2 SHEET 1 OF PLAN 5-894 SHALL BE PROVIDED.
3. WHERE STRUCTURES ARE GROUNDED TO RAILS, TRACK CIRCUITS SHALL NOT EXCEED 4500' IN LENGTH.

| | MAXIMUM FRONT & BACK CONTACTS OF RELAY | TYPE OF RELAY | RESISTANCE OF RELAY | RESISTANCE OF SHUB | PIECE NUMBER OF RELAY |
|-----|--|---------------|---------------------|--------------------|-----------------------|
| FSA | 2F | 2B UNION-DNE2 | 60 OHMS | 120 OHMS | 188686 |
| | 4F | 4B UNION-DNII | 100 OHMS | 120 OHMS | 188774 |
| | 6F | 6B UNION-DNII | 60 OHMS | 50 OHMS | 189933 |
| H | 4F | 4B UNION-DNII | 100 OHMS | 50 OHMS | 188687 |
| | 6F | 4B UNION-DNII | 100 OHMS | 50 OHMS | 188647 |
| | 2F | 2B UNION-DNE2 | 55 OHMS | NO SHUB | 188770 |
| J | 4F | 4B UNION-DNII | 55 OHMS | NO SHUB | 188688 |
| | 6F | 4B UNION-DNII | 55 OHMS | NO SHUB | 188698 |
| | 2F | 2B UNION-DNE2 | 60 OHMS | 200 OHMS | 206943 |
| BSA | 4F | 4B UNION-DNII | 100 OHMS | 200 OHMS | 206944 |
| | 6F | 6B UNION-DNII | 60 OHMS | 80 OHMS | 206945 |

A=PROCEED INDICATION (180 CODE)
B=APPROACH RESTRICTING INDICATION (120 CODE)
C=APPROACH INDICATION (15 CODE)

* = 3 SPARK ARRESTER (2.5 MF CONDENSER).

APPROVED FOR P. R. R. P. V. A.
ELECTRIFICATION AGREEMENT
DATED DEC. 20th, 1933
GIBBS & HULL, ENGINEER
BY: *[Signature]*

THREE BLOCK TO
TWO BLOCK TERRITORY

100 CYCLE CODE
ELECTRIC ROAD
A.C. PROPULSION

Sheet 2 of 3



THE PENNSYLVANIA RAILROAD
STANDARD
CODED TRACK CIRCUITS APPROACHING
DISTANT INTERLOCKING SIGNAL
UNIVERSAL CODE

OFFICE OF ELECTRICAL ENGINEER
PHILADELPHIA, PA., MARCH 27, 1934.
APPROVED:-

APPROVED: *[Signature]* ELECTRICAL ENGINEER
APPROVED: *[Signature]* CHIEF SIGNAL ENGINEER
APPROVED: *[Signature]* CHIEF ENGINEER

MAR. 6, 1937. LOCKOUT FEATURE
CHANGED - AS S.G. LETTER 1-10-37.
APPROVED: *[Signature]*
March 1, 1935
Spark arresters added.
Oct. 28, 1934.
Lockout feature changed
per U.S. & S. Co. letters dated
6-2-34 & 8-20-34.

S-893



- NOTES:**

1. FOR NOTES IN CONNECTION WITH SIGNAL LIGHTING CIRCUITS, SEE PLAN S-857, SHEET 1.
2. TRACK CIRCUITS SHALL NOT EXCEED 6000' IN LENGTH. WHERE DISTANCE BETWEEN SIGNALS IS GREATER THAN 6000' CUT SECTIONS IN ACCORDANCE WITH FIG.1 OR FIG.2 SHEET 1 OF PLAN S-894 SHALL BE PROVIDED.
3. WHERE STRUCTURES ARE GROUNDED TO RAILS, TRACK CIRCUITS SHALL NOT EXCEED 4500' IN LENGTH.

| | MAXIMUM
FRONT & BACK
CONTACTS
OF RELAY | TYPE
OF RELAY | RESISTANCE
OF RELAY | RESISTANCE
OF SHUB | PIECE
NUMBER
OF RELAY |
|-----|---|------------------|------------------------|-----------------------|-----------------------------|
| F3A | 2F | 2B UNION-DN22 | 60 OHMS | 120 OHMS | 188686 |
| | 4F | 4B UNION-DN11 | 100 OHMS | 120 OHMS | 188774 |
| | 6F | 6B UNION-DN11 | 60 OHMS | 50 OHMS | 189933 |
| H | 4F | 4B UNION-DN11 | 100 OHMS | 50 OHMS | 188687 |
| | 6F | 4B UNION-DN11 | 100 OHMS | 50 OHMS | 188647 |
| | 2F | 2B UNION-DN22 | 55 OHMS | NO SHUB | 188770 |
| J | 4F | 4B UNION-DN11 | 55 OHMS | NO SHUB | 188688 |
| | 6F | 4B UNION-DN11 | 55 OHMS | NO SHUB | 188698 |
| | 2F | 2B UNION-DN22 | 60 OHMS | 200 OHMS | 206943 |
| BSA | 4F | 4B UNION-DN11 | 100 OHMS | 200 OHMS | 206944 |
| | 6F | 6B UNION-DN11 | 60 OHMS | 80 OHMS | 206945 |

A=PROCEED INDICATION (180 CODE)
B=APPROACH RESTRICTING INDICATION (120 CODE)
C=APPROACH INDICATION (75 CODE)

* - SPARK ARRESTER (2.5 MF CONDENSER).

REVISIONS

MAR 6, 1937, LOCKOUT FEATURE
CHANGED: U.S. & S. LETTER 2103

APPROVED: *A. H. Reed* **100%**

April 29, 1935 **U.S. & S.**
10JB checked in lockout circuit.

March 1, 1935 **U.S. & S.**
Spark arresters added.

OCT. 29, 1936 **U.S. & S.**
Lockout feature changed per
U.S. & S. Co. letter 2103 10-10

100 CYCLE CODE
ELECTRIC ROAD
A.C. PROPULSION

Sheet 3 of 3

S-893

THE PENNSYLVANIA RAILROAD
STANDARD
CODED TRACK CIRCUITS APPROACHING
DISTANT INTERLOCKING SIGNAL
UNIVERSAL CODE

OFFICE OF ELECTRICAL ENGINEER
PHILADELPHIA, PA., MARCH 27, 1934

APPROVED: *[Signature]* APPROVED: *[Signature]* APPROVED: *[Signature]*
ELECTRICAL ENGINEER CHIEF SIGNAL ENGINEER CHIEF ENGINEER




FIG. 1

CUT SECTION

SHALL BE PROVIDED WHERE APPROACH LOCKING OR HIGHWAY CROSSING CONTROL STARTS AT THIS POINT.




FIG. 4

CUT SECTION

SHALL BE PROVIDED AS SPECIFIED IN NOTES.

(SHALL BE USED FOR ALL CUT-SECTIONS BETWEEN LEAVING END OF INTERLOCKING AND NEXT SIGNAL EXCEPT WHERE FIG. 1 IS REQUIRED).

FIG. 2

CUT SECTION

SHALL BE PROVIDED AS SPECIFIED IN NOTES. (ALSO SEE FIG. 4).




FIG. 3

NOTES:-

1. FOR NOTES IN CONNECTION WITH SIGNAL LIGHTING CIRCUITS, SEE PLAN S-857 SHEET 1.
2. TRACK CIRCUITS SHALL NOT EXCEED 6000' IN LENGTH. WHERE DISTANCE BETWEEN SIGNALS IS GREATER THAN 6000' FIG. 2 SHALL BE PROVIDED FOR ONE CUT SECTION AND FIG. 4 FOR ANY ADDITIONAL CUT SECTIONS, EXCEPT WHERE FIG. 1 IS NECESSARY.
3. WHERE STRUCTURES ARE GROUNDED TO RAILS, TRACK CIRCUITS SHALL NOT EXCEED 4500' IN LENGTH.

| | MAXIMUM
PRINT & MARK
CONTACTS
OF RELAY | TYPE
OF RELAY | RESISTANCE
OF RELAY | RESISTANCE
OF SNUB | PIECE
NUMBER
OF RELAY |
|-------------------------------|---|------------------|------------------------|-----------------------|-----------------------------|
| SA
EXCEPT
BSA
FIG. 3 | 2F 2B | UNION-DW22 | 60 OHMS | 120 OHMS | 188686 |
| | 4F 4B | UNION-DW11 | 100 OHMS | 120 OHMS | 188774 |
| | 6F 6B | UNION-DW11 | 60 OHMS | 50 OHMS | 189933 |
| H | 4F 4B | UNION-DW11 | 100 OHMS | 50 OHMS | 188687 |
| | 6F 6B | UNION-DW11 | 100 OHMS | 50 OHMS | 188847 |
| J | 2F 2B | UNION-DW22 | 55 OHMS | NO SNUB | 188770 |
| | 4F 4B | UNION-DW11 | 55 OHMS | NO SNUB | 188688 |
| | 6F 6B | UNION-DW11 | 55 OHMS | NO SNUB | 188679 |
| BSA
FIG. 3 | 2F 2B | UNION-DW22 | 60 OHMS | 200 OHMS | 206943 |
| | 4F 4B | UNION-DW11 | 100 OHMS | 200 OHMS | 206944 |
| | 6F 6B | UNION-DW11 | 60 OHMS | 80 OHMS | 206945 |

* = SPARK ARRESTER (2.5 MF CONDENSER)

| REVISIONS | |
|--|-------|
| APPROVED FOR P. R. R. ELECTRIFICATION AGREEMENT
DATED DEC. 27th, 1933
J. H. & HILL, ENGRS.
BY: <i>[Signature]</i> | |
| TWO BLOCK TERRITORY
100 CYCLE CODE
ELECTRIC ROAD
AC PROPULSION | |
| SHEETS 3 & 4 OBSOLETE. | |
| MAR. 6, 1937, LOCKOUT FEATURE
CHANGED - U.S. & S. CO. LATER 2.10.37 | |
| APPROVED: <i>[Signature]</i> <i>[Signature]</i> <i>[Signature]</i> | |
| March 1, 1935
Spark arresters added. | |
| OCT. 23, 1934
LOCKOUT FEATURE CHANGED
PER U.S. & S. CO. LETTERS
DATED 6-2-34 & 5-22-34 | |
| SHEET 1 OF 6 | S-874 |

THE PENNSYLVANIA RAILROAD
STANDARD
CODED TRACK CIRCUITS
IN AUTOMATIC TERRITORY
UNIVERSAL CODE


OFFICE OF ELECTRICAL ENGINEER
PHILADELPHIA, PA., MARCH 27, 1934.

APPROVED: *[Signature]*
ELECTRICAL ENGINEER

APPROVED: *[Signature]*
CHIEF SIGNAL ENGINEER

APPROVED: *[Signature]*
CHIEF ENGINEER

NOT TO SCALE



NOTES:-

1. FOR NOTES IN CONNECTION WITH SIGNAL LIGHTING CIRCUITS, SEE PLAN S-857 SHEET 1.
2. TRACK CIRCUITS SHALL NOT EXCEED 6000' IN LENGTH. WHERE DISTANCE BETWEEN SIGNALS IS GREATER THAN 6000' CUT SECTIONS IN ACCORDANCE WITH FIG. 1 OR FIG. 2, SHEET 1 OF PLAN S-894 SHALL BE PROVIDED.
3. WHERE STRUCTURES ARE GROUNDED TO RAILS, TRACK CIRCUITS SHALL NOT EXCEED 4500' IN LENGTH.

| | MAXIMUM LENGTH OF RELAY | TYPE OF RELAY | RESISTANCE OF RELAY | RESISTANCE OF SWAG | PIECE NUMBER OF RELAY |
|-----|-------------------------|---------------|---------------------|--------------------|-----------------------|
| FSA | 2F 2B | UNION-DW22 | 60 OHMS | 120 OHMS | 188686 |
| | 4F 4B | UNION-DW1 | 100 OHMS | 120 OHMS | 188774 |
| | 6F 6B | UNION-DW1 | 60 OHMS | 50 OHMS | 189933 |
| H | 4F 4B | UNION-DW1 | 100 OHMS | 50 OHMS | 188687 |
| | 6F 4B | UNION-DW1 | 100 OHMS | 50 OHMS | 188947 |
| J | 2F 2B | UNION-DW22 | 55 OHMS | NO SWAG | 188770 |
| | 4F 4B | UNION-DW1 | 55 OHMS | NO SWAG | 188688 |
| | 6F 4B | UNION-DW1 | 55 OHMS | NO SWAG | 188678 |
| BSA | 2F 2B | UNION-DW22 | 60 OHMS | 200 OHMS | 206943 |
| | 4F 4B | UNION-DW1 | 100 OHMS | 200 OHMS | 206944 |
| | 6F 6B | UNION-DW1 | 60 OHMS | 80 OHMS | 206945 |

A=PROCEED INDICATION (180 CODE)

B=APPROACH RESTRICTING INDICATION (120 CODE)

C=APPROACH INDICATION (75 CODE)

* = SPARK ARRESTER (2.5 MF CONDENSER).

APPROVED FOR P. R. R. - P. W. A.
ELECTRIFICATION AGREEMENT
DATED DEC. 28th, 1933
GIGGS & HILL, ENGINEER
BY: *[Signature]*

TWO BLOCK TO
THREE BLOCK TERRITORY

100 CYCLE CODE
ELECTRIC ROAD
AC PROPULSION

| REVISIONS |
|---|
| MAR. 6, 1937, LOCKOUT FEATURE
CHANGED, U.S. & S. CO. LETTER # 2-10-37. |
| APPROVED: <i>[Signature]</i> |
| April 29, 1935 <i>[Signature]</i> |
| IAJB checked in lockout circuit. |
| March 1, 1935 <i>[Signature]</i> |
| Spark arresters added. |
| OCT. 23, 1934 <i>[Signature]</i> |
| LOCKOUT FEATURE CHANGED
PER U.S. & S. CO. LETTERS
DATED 8-2-34 & 8-20-34. |

SHEET 5 OF 6

S-894

THE PENNSYLVANIA RAILROAD
STANDARD
CODED TRACK CIRCUITS
IN AUTOMATIC TERRITORY
UNIVERSAL CODE

OFFICE OF ELECTRICAL ENGINEER
PHILADELPHIA, PA., MARCH 21, 1934.

APPROVED: *[Signature]*
ELECTRICAL ENGINEER

APPROVED: *[Signature]*
CHIEF SIGNAL ENGINEER

NOT TO SCALE
APPROVED: *[Signature]*
CHIEF ENGINEER

3.0
D.M.
H.E.A.

